

## HUSKY OIL COMPANY

### III. Blowout and Accessory Equipment (continued)

3. Pit level indicator should be working and set for minimum conditions.
4. All gauges and pump stroke counters should be in working order.
5. Each driller will record daily the mud weight, viscosity, and pump pressure at some reduced rate (20-30 SPM).
6. An inside BOP and T.I.W. valve should be on the rig floor with proper crossovers to get to drill string.