

9. No abnormal temperatures or H<sub>2</sub>S hazards are expected at this location or during drilling of this well. Potential pay zones do not contain either of these hazards in comparable offset field wells.

Abnormal pressure is expected in the Atoka sequences beginning at about 11,890'. This hazard will be controlled through the use of weighted muds, pressure control systems and the setting of a casing prior to drilling out into lower pressured zones at deeper depths.

10. It is anticipated that the drilling operations will begin July 3, 1980 and be completed November 3, 1980. Completion operations will then commence and should take approximately 10 days.