

8. TESTING, LOGGING AND CORING PROGRAMS:

Drill stem tests will be made when samples, drilling time and mud logging data are sufficient to indicate a test is warranted.

It is planned that electric logs will include Gamma-Ray CNL and FDC logs and DLL logs.

No coring is planned.

9. ABNORMAL PRESSURES, TEMPERATURES OR HYDROGEN SULFIDE GAS:

None anticipated.

10. ANTICIPATED STARTING DATE:

It is planned that drilling operations will commence about August 6, 1980, with drilling and completion operations lasting about 60 days.