

PENWELL ENERGY, INC.

1100 ARCO BUILDING
600 N. MARIENFELD
MIDLAND, TEXAS 79701

OFF: (915) 683-2534
FAX: (915) 683-4514

Penwell proposes to set CIBP @ approximately 9,700' and cap w/35' of cement.
* Set 100' CMT. plug @ TOC - 8750' & 6000'.
Set additional CIBP @ approximately 4,800'. Perforate 4 squeeze holes at approximately 4,780'. Set cement retainer @ approximately 4,750', bring cement behind 5 1/2" production casing up to 2,500' w/600 sks. of class "C" cement.

WOC minimum of 72 hrs. Run CBL and determine TOC. Perforate Delaware and attempt to make commercial oilwell.

Attachment to C-101
State IZ Com. #1.
1880' FNL & 1980' FWL
Sec. 31 - T235-R25E
Eddy County, New Mexico

* Plugging Mvd between all plugs.
BGA