

TEST

After nipping up on surface pipe, but before drilling out the cement plug, the BOP's shall be tested to the rated working pressure.

FREQUENCY

The BOP's shall be cycled on every trip.

