

**8. TESTING, LOGGING & CORING PROGRAM:**

No DST planned.

No cores planned.

A GR-CBL will be run in 9.625" casing to evaluate bond prior to running 5.5" casing.

**9. ABNORMAL PRESSURES OR TEMPERATURES:**

None anticipated. Majority of drilling is in csg.

**10. ESTIMATED STARTING DATE:**

It is proposed to commence reentry operations by 3-10-92 upon approval of this application. An expedited approval will allow testing of shallow potential prior to the lease expiration of 4-1-92.