

0-2600' - CNL, GR
9500' to TD - Mud logging.

9. No abnormal temperatures or H₂S hazards are expected at this location.

Abnormal pressure is possible in the Strawn - Atoka sequence beginning at about 11,000'. This pressure will be controlled through the use of weighted muds, pressure control systems and the setting of a liner with cement.

10. It is anticipated that drilling operations will begin on November 1, 1982 and be completed in 80 days. Completion operations will then commence and should take approximately 30 days.