

BELCO DEVELOPMENT CORPORATION  
 JAMES RANCH NO. 15  
 BOTTOM HOLE PRESSURE FLOW TEST AND  
 BOTTOM HOLE PRESSURE BUILD-UP TEST.  
 TABULATION OF TIMES AND PRESSURES.

TEST CONDUCTED BY:  
 JOHN WEST ENGINEERING COMPANY

RECEIVED BY
NOV 19 1984
O. C. D.
ARTESIA, OFFICE

TEST DATE: OCTOBER 23 to 31, 1984  
 TEST DEPTH: 14,300 FEET  
 ELEMENT NO: 53217 (0-7100 PSI)  
 OPERATOR: W.S.

DATE	TIME	CUM HRS./MIN.		PSIG @ 14,300 FEET
10-23-84	6:00 P.M.	00 Hrs.	00 Min.	5623 Gauge reached 14,300'
	6:30 P.M.	00	30	5419
	7:00 P.M.	01	00	5190
	7:30 P.M.	01	30	5061
	8:00 P.M.	02	00	4967
	9:00 P.M.	03	00	4867
10-23-84	10:00 P.M.	04	00	4770
	11:00 P.M.	05	00	4727
10-24-84	12:00 A.M.	06	00	4706
	1:00 A.M.	07	00	4867
	2:00 A.M.	08	00	4964
	3:00 A.M.	09	00	4992
	4:00 A.M.	10	00	4824
	5:00 A.M.	11	00	4731
	6:00 A.M.	12	00	4781
	7:00 A.M.	13	00	4760
	8:00 A.M.	14	00	4760
	9:00 A.M.	15	00	4756
	10:00 A.M.	16	00	4734
	11:00 A.M.	17	00	4713
	12:00 Noon	18	00	4702
	1:00 P.M.	19	00	4681
	2:00 P.M.	20	00	4652
	3:00 P.M.	21	00	4623
	4:00 P.M.	22	00	4609
10-24-84	4:00 P.M.	00 Hrs.	00 Min.	4609 Shut-In, Begin Build-Up
	4:30 P.M.	00	30	4942
	5:00 P.M.	01	00	5419
	5:30 P.M.	01	30	5602
	6:00 P.M.	02	00	5691
	7:00 P.M.	03	00	5817
	8:00 P.M.	04	00	5924
	9:00 P.M.	05	00	5992
	10:00 P.M.	06	00	6014
	11:00 P.M.	07	00	6043
10-24-84	12:00 A.M.	08	00	6072
10-25-84	1:00 A.M.	09	00	6108
	2:00 A.M.	10	00	6129
	7:00 A.M.	15	00	6219
	12:00 Noon	20	00	6280
	5:00 P.M.	25	00	6309
10-25-84	10:00 P.M.	30	00	6334
10-26-84	3:00 A.M.	35	00	6352
	8:00 A.M.	40	00	6367
	1:00 P.M.	45	00	6377
10-26-84	6:00 P.M.	50	00	6381
10-27-84	4:00 A.M.	60	00	6403
10-27-84	2:00 P.M.	70	00	6413
10-28-84	12:00 A.M.	80	00	6417
	10:00 A.M.	90	00	6421
10-28-84	8:00 P.M.	100	00	6428
10-29-84	6:00 A.M.	110	00	6431
10-29-84	4:00 P.M.	120	00	6435
10-30-84	2:00 A.M.	130	00	6439
	12:00 Noon	140	00	6439
10-30-84	10:00 P.M.	150	00	6442
10-31-84	3:00 A.M.	155	00	6442 Chart ran down, end of tes