

8. Testing, Logging and Coring Program:

Drill Stem Tests will be made when samples, drilling time and other data indicate a test is warranted.

It is planned that electric logs will include Gamma Ray-CNL, LDT, and dual laterologs.

Note: A gamma ray log will be run over the surface casing from its base to the ground surface.

No coring is planned.

9. Anticipated abnormal pressure: None

10. Anticipated Starting Date: It is planned to commence drilling operations upon approval of APD and location exception.