

**MARALO, INC.**  
**GOLD RUSH "30" FED COM #1**  
**OCTOBER 7, 1994**

9. Flow back and evaluate.
10. If additional stimulation is needed, frac as directed by Midland office.
11. After flow rate has stabilized, run 72-hr bombs and shut well in for BHP build up.
12. Open up well for 4-point test. Place well on production.