

POGO PRODUCING COMPANY
LOST TANK "3" FEDERAL # 7
LOT 2 UNIT "B" SECTION 3
T22S-R31E EDDY CO. NM

12. LOGGING, CORING, AND TESTING PROGRAM:

A. Open hole logs: Dual Induction, SNP, LDT Gamma Ray Caliper from TD back to Intermediate casing shoe. Gamma Ray, Neutron from Intermediate casing shoe back to surface.

B. Mud logger on hole from 4200' to TD.

C. No DST's, or cores are planned at this time

13. POTENTIAL HAZARDS:

No abnormal pressures or temperatures are expected. There is no known presence of H²S in this area. If H²S is encountered the operator will comply with the provisions of Onshore Oil and Gas Order No. 6. No lost circulation is expected to occur. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. Estimated BHP 1200 PSI, and Estimated BHT 140°.

14. ANTICIPATED STARTING DATE AND DURATION OF OPERATION:

Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon after BLM approval and as soon as a rig will be available. Move in operation and drilling is expected to take 25 days. If production casing is run then an additional 30 days will be needed to complete well and construct surface facilities and/or lay flowlines in order to place well on production.

15. OTHER FACETS OF OPERATIONS:

After running casing, cased hole Gamma Ray, Neutron Collar logs will be run from TD back to all possible productive zones. The Bone Spring formation will be perforated and stimulated in order to establish production. The well will be swab tested and potentialized as an oil well.