

Logging

Electrical Logging: A DLL, FDC and GR-Sonic will be run from the base of the surface casing (1600') to TD.

9. No abnormal pressures are anticipated in this well. Temperatures are expected to be normal and no hazards are expected.
10. The anticipated starting date for this well is August 30, 1980. Drilling operations are expected to be completed within 90 days.