

Pogo Producing Company
Federal 35 No. 1
Sec 6, T-26-S, R-29-E
Eddy County, New Mexico

Page 2.

8. Drill stem tests are possible for the Delaware Sands and Bone Springs. No core tests are planned.
9. Ten foot samples of cuttings will be caught from the base of the surface pipe (250') to total depth. A mud logging unit is planned from the base of the intermediate casing (2640') to total depth.
10. Adequate Electrical and Resistivity logs will be run from total depth to the base of the intermediate casing at 2640', the Gamma Ray will be run to the surface.
11. No abnormal temperatures or additional hazards are expected to be encountered.
12. The anticipated starting date is March 31, 1982 with the completion expected by May 15, 1982.