

Enron Oil & Gas Company
S.D.S. "11" Federal, Well No. 1
2090' FNL & 1980' FWL
Sec. 11, T24S, R31E
Eddy County, New Mexico

4. Casing Program:

<u>Hole Size</u>	<u>Interval</u>	<u>OD csg</u>	<u>Weight Grade Jt. Cond. Type</u>
14-3/4	0- 600'	11-3/4	42# H-40 A ST&C
11	0- 4200'	8-5/8	32# J-55 LT&C
7-5/8	0- 8600'	5-1/2	17# J-55 LT&C

Cementing Program:

- 11-3/4" Surface casing: Cement to surface with 275 sx of Class C + 2% CaCl₂ + 1/4#/sx flocele.
- 8-5/8" Intermediate: Cement to surface with 800 sx of Premium Plus lite + 15#/sx salt + 1/4#/sx Flocele and 300 sx Cl C + 2% CaCl₂
- 5-1/2" Prod casing: Cement with 300 sx 50/50 Cl H/Poz + 0.8% Halad 9 + 1/4#/sx Flocele. This cement slurry is designed to bring TOC to 7000'.

5. Minimum Specifications for Pressure Control:

The blowout preventer equipment (BOP) shown in Exhibit #1 will consist of a double ram-type (3000 psi WP) preventer and an annular preventer (3000 psi WP). Units will be hydraulically operated and the ram-type will be equipped with blind rams on top and drill pipe rams on bottom. All will be installed on the 11-3/4" surface casing and used continuously until TD is reached. All BOP's and accessory equipment will be tested to 1000 psi before drilling out of surface casing. Before drilling out of intermediate casing, the ram-type BOP and accessory equipment will be tested to 3000 psi and the hydril to 70% of rated working pressure (2100 psi).

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. A 2" kill line and 4" choke line will be included in the drilling spool located below the ram-type BOP. Other accessories to the BOP equipment will include a kelly cock and floor safety 2 valve (inside BOP) and choke lines and choke manifold with 3000 psi WP rating.