

Production Csg

Install 11" 5M psi x 7-1/16" 10M psi tbh head. Test head to 4,350 psi (70 % x Casing Pc of 6,230) or the wellhead manufacturer's recommendation, whichever is less. NU 7-1/16" 10M psi WP BOP's including annular w/rotating head (API RP53 fig 2.C.9 RSRRAG). Test ram BOP's and choke manifold to 250 psi and 10,000 psi, test annular BOP to 250 psi and 3,500 psi utilizing a test plug and an independent tester.