Production - Cement to surface with a total of +/- 800 cu ft as follows::

<u>Lead Slurry</u> - 330 sks 35 Poz: 65 Class "C" + 6% Gel

Tail Slurry - 470 sks 50 Poz: 50 Class "C" +32% Gel + 3% salt + 0.4 % FL-52

6. Mud Program

		Weight	Funnel	Water
<u>Depth</u>	Mud Type	ppg	Viscosity	<u>Loss</u>
0'-580'	Spud Mud	8.4-8.9	29-34	NC
580'-2900'	Brine	10.0-10.2	28-30	NC
2900'-3800'	SWG	10.0-10.4	30-35	≤15 cc

7. Auxiliary Equipment

Upper Kelly Cock, Lower Kelly Cock, and Full Opening Stabbing Valve

8. Testing, Coring, and Logging Program

- A. Drill Stem Tests None planned.
- B. Coring None planned.
- C. Mud Logging -2500'-TD
- D. Electric Logs

Open Hole:

AIT, CNL/LDT, GR:

TD to 2800'

9. Anticipated Abnormal Temperature, Pressure, or Hazards

10. Anticipated Starting Date and Duration of Operations

Pending favorable weather and permit approval, construction work on this location is planned to begin in January, 1999. Construction work will require 2 days, move-in and rig up rotary tools, 1 day, drill and complete, 18 days. It is planned to spud the well in January, 1999.