

8. TESTING, LOGGING AND CORING PROGRAM:
Samples: Surface casing shoe to TD
DST's: None anticipated
Logging: Gamma Ray-Neutron log and other logs as recommended by well-site geologist.
Coring: None anticipated
9. ABNORMAL PRESSURES, TEMPERATURES OR HYDROGEN SULFIDE: None anticipated. Maximum bottom-hole pressure should not exceed 1500 psi. Bottom-hole temperature will be about 110°F.
10. ANTICIPATED STARTING DATE: Drilling will commence about January 1, 1982. Drilling should be completed within 10 days. Completion operations (perforations and stimulation) will follow drilling operations.