

8. The Testing, Logging and Coring Programs to be Followed

- (a) DST's are anticipated in the Wolf Camp and Cisco horizons. Other zones will be tested as needed.
- (b) The logging program will consist of a Dual Laterolog, a Density/Neutron from 3550' to T.D. and Gamma Ray to surface. Any other logs will be determined at well site to best evaluate any shows.
- (c) No coring is anticipated.
- (d) Stimulation procedures will consist of acidizing if indicated after evaluation of logs. Appropriate Sundry Notice will be submitted.

9. Any Anticipated Abnormal Pressures or Temperatures

Possible high pressures are anticipated in Wolf Camp horizon. These will be contained by heavy drilling mud. Bottom hole pressure in 1974 was 3730' psig. Pressure buildup in 1976 indicates BHP of 2200' psig.

No hydrogen sulfide or other hazardous fluids or gases have been found, reported or known to exist at these depths in the area.

10. Anticipated Starting Date and Duration of the Operations

The anticipated starting date is set for August 1, 1979, or as soon as possible after examination and approval of drilling requirements. Operations should be completed within 50 days.