

400' to TD 6500' - Brine water conditioned as necessary for control of PH, viscosity (28-32 sec.), and seepage. Weighted as necessary for well control.

7. AUXILIARY EQUIPMENT:

Geolograph from surface to total depth.

Mud logging trailer from 2700' to total depth.

8. TESTING, LOGGING & CORING PROGRAM:

No DST planned.

Open-hole logs include GR-CNL-LDT-CAL and GR-DLL-MSFL.

No cores planned.

9. ABNORMAL PRESSURES OR TEMPERATURES: None anticipated.

10. ESTIMATED STARTING DATE:

* ~~This lease expires 4-1-92 unless drilling operations have commenced.~~ An expeditious approval of this APD is respectfully requested. Upon verbal approval, dirt work will start immediately and a rig moved in to spud the well.

* NOT SINCE WELL NO.1 WAS COMPLETED.
(Adc)