

8. Testing, Logging and Coring Program:

Samples: Out from under surface casing to TD.

DST's: As warranted.

Coring: None anticipated.

Logging: Dual Induction Laterolog, Gamma Ray/Litho Density, Gamma Ray/Compensated Neutron with Caliper Log.

9. No abnormal pressures or temperatures are anticipated. No H₂S is expected to be encountered during drilling operations. BHP @ TD ~ 3488 psig.

SSS 10. Anticipated starting date: As soon as possible after approval / Duration: 30 days.