

7. METHODS OF HANDLING WASTE DISPOSAL:

- A.
  1. Drill cuttings will be disposed of in the reserve pit.
  2. Trash, waste paper, and garbage will be contained in covered trash containers and disposed of in an authorized land fill.
  3. If needed, sewage from the trailer house will drain into holes with minimum depth of 10' 00". These holes will be covered during drilling and backfilled upon completion. Portable sanitation facilities will be provided and properly maintained during drilling and completion operations for the rig crews.
  4. All extraneous material such as surplus casing, tubing, thread protectors, unused chemicals and containers, will be removed from the location.
- B. Remaining drilling fluids will be allowed to evaporate in the reserve pit until the pit is dry enough for backfilling.

Water produced during testing of the well will be disposed of in the reserve pit. Oil produced during testing of the well will be stored in test tanks until sold and hauled from the site.

8. ANCILLARY FACILITIES:

None are planned or required.

9. WELLSITE LAYOUT:

- A. Exhibit I shows the relative location and dimensions of the well pad, reserve pits and major rig components.
- B. The land is relatively flat with sandy soil.
- C. The pad and pit area have been staked.

10. PLANS FOR RESTORATION OF THE SURFACE:

Rehabilitation of the location and reserve pit will start in a timely manner after all drilling operations cease. The type of reclamation will depend on whether the well is a producer or a dry hole.

After finishing drilling and/or other completion operations, all equipment and other materials not needed for further operations will be removed. Pits will be filled, and the location cleaned of all trash and junk to leave the wellsite as pleasant in appearance as possible.

If the proposed well is nonproductive, all restoration and/or vegetation requirements of the Bureau of Land Management will be complied with and will be accomplished as quickly as possible. All pits will be filled and levelled within 90 days after abandonment.