District I
1625 N French Dr , Hobbs, NM 88240
District II
1301 W. Grand Avenue, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505

- State of New Mexico
Energy Minerals and Natural Resources
Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

For temporary pits, closed-loop systems, and below-grade tanks, submit to the appropriate NMOCD District Office.

For permanent pits and exceptions submit to the Santa Fe Environmental Bureau office and provide a copy to the appropriate NMOCD District Office.

Pit, Closed-Loop System, Below-Grade Tank, or Proposed Alternative Method Permit or Closure Plan Application			
Type of action: Closure of a pit, closed-loop system, below-grade tank, or proposed alternative method Closure of a pit, closed-loop system, below-grade tank, or proposed alternative method Modification to an existing permit Closure plan only submitted for an existing permitted or non-permitted pit, closed-loop system, below-grade tank, or proposed alternative method			
Instructions: Please submit one application (Form C-144) per individual pit, closed-loop system, below-grade tank or alternative request Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.			
Operator: XTO Energy, Inc. OGRID #:			
Facility or well name: WF STATE 16 #3			
API Number: 3004530076 OCD Permit Number: 14W 6			
U/L or Qtr/Qtr Section 16 Township 30N Range 14W County: San Juan			
Center of Proposed Design: Latitude 36.81038 Longitude 108.31231 NAD: 1927 1983 Surface Owner: Federal State Private Tribal Trust or Indian Allotment			
Surface Owner: Federal State Private Tribal Trust or Indian Allotment 2. Pit: Subsection F or G of 19.15.17.11 NMAC Temporary: Drilling Workover Permanent Emergency Cavitation P&A Lined Unlined Liner type: Thickness mil LLDPE HDPE PVC Other String-Reinforced Liner Seams: Welded Factory Other Volume: bbl Dimensions X W 3. Closed-loop System: Subsection H of 19.15.17.11 NMAC Type of Operation: P&A Drilling a new well Workover or Drilling (Applies to activities which require prior approval of a permit or notice of intent) Drying Pad Above Ground Steel Tanks Haul-off Bins Other Lined Unlined Liner type: Thickness mil LLDPE HDPE PVC Other Liner Seams: Welded Factory Other			
Below-grade tank: Subsection I of 19.15.17.11 NMAC Volume: 120			
Submittal of an exception request is required. Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.			

Fencing: Subsection D of 19.15.17.11 NMAC (Applies to permanent pits, temporary pits, and below-grade tanks) Chain link, six feet in height, two strands of barbed wire at top (Required if located within 1000 feet of a permanent residence, school, hospital,				
institution or church) Note The institution of church is a second secon				
Alternate. Please specify				
7.				
Netting: Subsection E of 19.15.17.11 NMAC (Applies to permanent pits and permanent open top tanks)				
Screen Netting Other Monthly importing (15 netting an apprain is not playing the Contill)				
Monthly inspections (If netting or screening is not physically feasible)				
Signs: Subsection C of 19.15.17.11 NMAC				
12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers				
☑ Signed in compliance with 19.15.3.103 NMAC				
9.				
Administrative Approvals and Exceptions: Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance.				
Please check a box if one or more of the following is requested, if not leave blank:				
Administrative approval(s): Requests must be submitted to the appropriate division district or the Santa Fe Environmental Bureau of	office for			
consideration of approval. Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.	I			
10.				
Siting Criteria (regarding permitting): 19.15.17.10 NMAC Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of accept	table source			
material are provided below. Requests regarding changes to certain siting criteria may require administrative approval from the appropriate or may be considered an exception which must be submitted to the Santa Fe Environmental Bureau office for consideration of approximately approval.	priate district			
Applicant must attach justification for request. Please refer to 19.15.17.10 NMAC for guidance. Siting criteria does not apply to dryi	ng pads or			
above-grade tanks associated with a closed-loop system.				
Ground water is less than 50 feet below the bottom of the temporary pit, permanent pit, or below-grade tank. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	☐ Yes ☒ No			
Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).				
- Topographic map; Visual inspection (certification) of the proposed site				
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. (Applies to temporary, emergency, or cavitation pits and below-grade tanks)	☐ Yes ☒ No ☐ NA			
- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image				
Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. (Applies to permanent pits)	☐ Yes ☐ No ☐ NA			
- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image				
Within 500 horizontal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock	☐ Yes 🛭 No			
watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site				
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance	☐ Yes ⊠ No			
adopted pursuant to NMSA 1978, Section 3-27-3, as amended. - Written confirmation or verification from the municipality; Written approval obtained from the municipality				
Within 500 feet of a wetland.				
- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☒ No			
Within the area overlying a subsurface mine Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division	☐ Yes ⊠ No			
Within an unstable area	☐ Yes ☒ No			
 Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map 				
Within a 100-year floodplain FEMA map	☐ Yes ⊠ No			

11				
Temporary Pits, Emergency Pits, and Below-grade Tanks Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.				
Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 NMAC Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC				
Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC				
Previously Approved Design (attach copy of design) API Number: or Permit Number:				
12				
Closed-loop Systems Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.				
 ☐ Geologic and Hydrogeologic Data (only for on-site closure) - based upon the requirements of Paragraph (3) of Subsection B of 19.15.17.9 ☐ Siting Criteria Compliance Demonstrations (only for on-site closure) - based upon the appropriate requirements of 19.15.17.10 NMAC ☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC ☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC 				
Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC				
Previously Approved Design (attach copy of design) API Number:				
Previously Approved Operating and Maintenance Plan API Number:				
above ground steet tanks or natit-off bins and propose to implement waste removal for closure)				
Permanent Pits Permit Application Checklist: Subsection B of 19.15.17.9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached. Hydrogeologic Report - based upon the requirements of Paragraph (1) of Subsection B of 19.15.17.9 NMAC Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC Climatological Factors Assessment Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC Dike Protection and Structural Integrity Design - based upon the appropriate requirements of 19.15.17.11 NMAC Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC Quality Control/Quality Assurance Construction and Installation Plan Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC Nuisance or Hazardous Odors, including H ₂ S, Prevention Plan Cisure Plan - based upon the appropriate requirements of 19.15.17.9 NMAC and 19.15.17.13 NMAC				
Proposed Closure: 19.15.17.13 NMAC Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan.				
Type: Drilling Workover Emergency Cavitation P&A Permanent Pit Below-grade Tank Closed-loop System Alternative				
Proposed Closure Method: Waste Excavation and Removal Waste Removal (Closed-loop systems only)				
On-site Closure Method (Only for temporary pits and closed-loop systems)				
☐ In-place Burial ☐ On-site Trench Burial ☐ Alternative Cleaves Mathed (Exceptions must be submitted to the Sente Re Environmental Bureau for consideration)				
Alternative Closure Method (Exceptions must be submitted to the Santa Fe Environmental Bureau for consideration)				
Waste Excavation and Removal Closure Plan Checklist: (19.15.17 13 NMAC) Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached. Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC				
Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17 13 NMAC				
🔯 Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings)				
Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC				

Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only: (19 15.17.13.1 Instructions: Please indentify the facility or facilities for the disposal of liquids, drilling fluids and drill cuttings. Use attachment if facilities are required.	O NMAC) nore than two	
Disposal Facility Name: Disposal Facility Permit Number:		
Disposal Facility Name: Disposal Facility Permit Number:		
Will any of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future server Yes (If yes, please provide the information below) No		
Required for impacted areas which will not be used for future service and operations: Soil Backfill and Cover Design Specifications based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC Re-vegetation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC	C	
Siting Criteria (regarding on-site closure methods only): 19.15 17.10 NMAC Instructions: Each siting criteria requires a demonstration of compliance in the closure plan. Recommendations of acceptable sour provided below. Requests regarding changes to certain siting criteria may require administrative approval from the appropriate distriction considered an exception which must be submitted to the Santa Fe Environmental Bureau office for consideration of approval. Justif demonstrations of equivalency are required. Please refer to 19.15.17.10 NMAC for guidance.	rict office or may be	
Ground water is less than 50 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	☐ Yes ☐ No ☐ NA	
Ground water is between 50 and 100 feet below the bottom of the buried waste - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	Yes No	
Ground water is more than 100 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	☐ Yes ☐ No ☐ NA	
Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	Yes No	
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	Yes No	
Within 500 horizontal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database; Visual inspection (certification) of the proposed site	Yes No	
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. - Written confirmation or verification from the municipality; Written approval obtained from the municipality	Yes No	
Within 500 feet of a wetland US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☐ No	
Within the area overlying a subsurface mine Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division	☐ Yes ☐ No	
 Within an unstable area. Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map 	☐ Yes ☐ No	
Within a 100-year floodplain. - FEMA map	☐ Yes ☐ No	
On-Site Closure Plan Checklist: (19 15 17.13 NMAC) Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached. Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19 15.17.10 NMAC Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of 19.15.17.11 NMAC Construction/Design Plan of Temporary Pit (for in-place burial of a drying pad) - based upon the appropriate requirements of 19.15.17.13 NMAC Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC Waste Material Sampling Plan - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings or in case on-site closure standards cannot be achieved) Soil Cover Design - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC Re-vegetation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC		

19.		
Operator Application Certification:		
I hereby certify that the information submitted with this application is true, accu	urate and complete to the	he best of my knowledge and belief.
Name (Print): Kim Champlin	Title	Environmental Representative
Signature: Kim Chanylin	Date:	9-8-08
e-mail address: kim_champlin@xtoenergy.com	Telephone:	(505) 333-3100
OCD Approval: Permit Application (including busine plan) Closure	Plan (only)	Conditions (see attachment)
OCD Representative Signature: Deputy Oil & Gas Inspector,		Approval Date: <u>4/25/20</u> (2
Title: District #3	OCD Pommit Num	ber:
Tine, Diotrice no	OCD Fermit Num	Der:
21. Clasure Banart (required within 60 days of alcours completion). Subsection	- V of 10 15 17 12 NIV	1AC
Closure Report (required within 60 days of closure completion): Subsection Instructions: Operators are required to obtain an approved closure plan prior		
The closure report is required to be submitted to the division within 60 days of		
section of the form until an approved closure plan has been obtained and the	closure activities have	been completed.
	Closure Com	pletion Date:
22.		
Closure Method:		
Waste Excavation and Removal On-Site Closure Method Altern	native Closure Method	☐ Waste Removal (Closed-loop systems only)
If different from approved plan, please explain.	- Miles	
23. Closure Report Regarding Waste Removal Closure For Closed-loop System	re That Utiliza Abaya	Cround Steel Tanks or Haul-off Rins Only
Instructions: Please indentify the facility or facilities for where the liquids, dr	illing fluids and drill c	cuttings were disposed. Use attachment if more than
two facilities were utilized.		,
Disposal Facility Name:	Disposal Facility P	ermit Number:
Disposal Facility Name:		ermit Number:
Were the closed-loop system operations and associated activities performed on o	-	
Yes (If yes, please demonstrate compliance to the items below) No		
Required for impacted areas which will not be used for future service and opera	ations:	
Site Reclamation (Photo Documentation)		
Soil Backfilling and Cover Installation		
Re-vegetation Application Rates and Seeding Technique		
24. Closure Report Attachment Checklist: Instructions: Each of the following	items must be attached	to the closure report. Please indicate, by a check
mark in the box, that the documents are attached.		
Proof of Closure Notice (surface owner and division)		
Proof of Deed Notice (required for on-site closure) Plot Plan (for on-site closures and temporary pits)		
Confirmation Sampling Analytical Results (if applicable)		
Waste Material Sampling Analytical Results (required for on-site closure)	
 Disposal Facility Name and Permit Number Soil Backfilling and Cover Installation 		
Re-vegetation Application Rates and Seeding Technique		
Site Reclamation (Photo Documentation)		
On-site Closure Location: Latitude Long	gitude	NAD: ∐1927 ∐ 1983
25.		
Operator Closure Certification:	anantintona anarrat	and complete to the best of my broughder and
I hereby certify that the information and attachments submitted with this closure belief. I also certify that the closure complies with all applicable closure require	ements and conditions	e and complete to the best of my knowledge and specified in the approved closure plan.
Name (Print).	Title:	
Signature:	Date:	
e-mail address:	Telephone:	

Dia at 1 PO lies 1980, Hobbs, NM 88241-1980 Dhuid II PO 1 rawer DD, Artesia, NM 88211-0719 5 District III

OIL CONSERVATION DIVISION

Form C-102 Revised Fe iary 21, 1994

Institutions on back

Submit to Appropriat sistrict Office State I vo - 4 Copies

Fee I e - 3 Copies

AMEI ED REPORT

PO Box 2088 Santa Fe, NM 87504-2088

State of New Mexico
Energy, Minerals & Natural Resources Department

1000 Rio Brama Rd., Aztec, NM 87410 District IV PO Box 2088, Santa Fe, NM 87504-2088

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number	1 Pool Cade	· Pool Name	
30-045-300	76 71629 & 78160	Basin Fruitland Coal & Harper Hi	ll Fruitland Sand PC
Property Code		1 Property Name /	1-10 Mumber
	WF	State /6	-3
OCHID No.		* Operator Name	' Elevation
019219	RICHARDSON	N OPERATING COMPANY	137001
	10 (Surface Location	

North/South line East/West line County UL or lot no. Feet from the Section Township Range Lot Ida Feet from the 1970 East San Juan 16 14 W 1280 South O 30 N 11 Bottom Hole Location If Different From Surface Lot Ida North/South line Feet from the East/West line County Ul. or lot po. Section Feet from the Township Rapge " D'dieated Acres " Joint or Infill " Consolidation Code 1" Order No. 160 320

NO ALLOWABLE WILL BE ASSICNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED

OK V NON-91 VI	DAKD UNII HAS B	EEN APPROVED BY	THE DIVISION
16	.006		17 OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief
	Original Fruitland Well	1745'	Du C
			Signature Drew Carnes Printed Name
		Craix	Operations Manager Title 01/07/03 Date
·	, cruit		18 SURVEYOR CERTIFICATION 1 hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same a true and
	/	CHES	correct to the best of my bellet. Date of Survey NEXICO Signature and Scales Professional Survey.
·	/	1970'	Signature to Scart Professional Survey.
	1280	/	Certificate Number

Lodestar Services, Inc. P0 Box 4465, Durango, C0 81302

Pit Permit Siting Criteria nformation Sheet

Client:	XTO Energy	
Project:	Pit Permits	
Revised:	9/4/2008	
Prepared by:	Brooke Herb	

FO BOX 4403, Durango,	Information Shee	Prepared by:	Brooke Herb
API#:	30-045-30076	USPLSS:	T30N, R14W,S16O
Name:	WF State 16-3	Lat/Long:	36.8066181727273/-108.305381281504
Depth to groundwater:	50-100'	Geologic formation:	Kirtland and Fruitland Formations
Distance to closest continuously flowing watercourse:	5.3 Miles to La Plata River		
Distance to closest significant watercourse, lakebed, blaya lake, or sinkhole:	3.4 miles SE of Youngs Lake, 4.65 miles west of Jackson lake		
		Soil Type:	Entisols
Permanent residence, school, hospital, institution or church within 300'	No		
		Annual Precipitation:	8.62 Avg Annual Precipitation
Domestic fresh water well or spring within 500'	No	Precipitation Notes:	No significant precip event
Any other fresh water well or spring within 1000'	No	<u> </u>	
Within incorporated municipal boundaries	No	Attached Documents:	Groundwater Report, Groundwater Data
Within defined municipal fresh water well field	No ·		Mines, Mills, and Quarries Location
			FEMA Flood Index Map
Wetland within 500'	No	Mining Activity:	.58 Miles to Coal Permit boundary
Within unstable area	No ·		4.6 Miles to Hilltop Pit
Within 100 year flood plain	No	:	
Additional Notes:			

WF State 16 #3 Below Ground Tank Hydrogeologic Report for Siting Criteria

General Geology and Hydrology

The San Juan Basin is a typical Rocky Mountain basin with a gently dipping southern flank and a steeply dipping northern flank. Asymmetrically layered Tertiary sandstones and shales, along with Quaternary alluvial deposits, dominate surficial geology (Dane and Bachman, 1965). The proposed pit location will be situated near the head of Coolidge Arroyo, just north of the town of Kirtland, New Mexico.

The predominant geologic formation is the Fruitland Formation/Kirtland Shale of Late Cretaceous age, which underlies surface soils and is often exposed as broad shalely hills (Dane and Bachman, 1965). Deposits of Quaternary alluvial sands also occur prominently near the surface of the area, especially near streams and washes. The Fruitland Formation consists of interbedded sandy shale, carbonaceous shale, sandstone and coal units. The Kirtland Shale is divided into a lower shale member, a middle sandstone unit and an upper sandy shale member. The two formations are difficult to differentiate and are often treated together. The combined thickness of the Fruitland-Kirtland interval ranges from 100 to 2000 feet (Stone et al., 1983).

Cretaceous and Tertiary sandstones, as well as Quaternary alluvial deposits serve as the primary aquifers in the San Juan Basin (Stone et al., 1983). Aquifers within the Fruitland-Kirtland Formations are primarily limited to the Farmington Sandstone Member, which is the middle unit within the Kirtland Shale. Reported discharge from stock wells is about 10 gallons per minute (Stone et al., 1983). The aquifer supplies low yielding stock wells.

The prominent soil type at the proposed site is enitsols, which are defined as soils that exhibit little to no profile development (www.emnrd.state.nm.us). Soils are basically unaltered from their parent rock. Miles of arroyos, washes and intermittent streams exist as part of the drainage network towards the San Juan River. These features often cut into soil and other unconsolidated materials, contributing to sedimentation downstream. The sudden influx of water from storm events easily erodes the soils that cover the area and prohibits effective recharge to the underlying aquifers.

Dry and arid weather further prohibit active recharge. The climate of the region is arid, averaging just over 8 inches of rainfall annually. As is typical of the southwestern United States monsoonal weather patterns, most precipitation falls from August through October. The heaviest rainfall occurs in the summer in isolated, intense cloudbursts. November through June is relatively dry. Snow generally falls from December to mid-February and averages less than one-half inch in depth. However, most recharge occurs during the winter months during snowmelt periods from the upper elevations (Western Regional Climate Center www.wrcc.dri.edu).

The predominant vegetation is sagebrush and grasses with a more restricted pinon-juniper association (Dick-Peddie, 1993).


Site Specific Hydrogeology

Depth to groundwater is estimated to be between 50 and 100 feet. This estimation is based on data from Stone and others (1983), the USGS Groundwater Atlas of the United States and depth to groundwater data published on the New Mexico State Engineer's iWaters Database website. Local topography and proximity to surface hydrologic features are also taken into consideration.


Beds of water-yielding sandstone are primarily confined to the Farmington Sandstone Member of the Fruitland Formation, which is 20-480 feet thick (Stone et al., 1983). The site is located in a shalely unit of the Fruitland Formation, as evidenced by the relatively flat topography that is easily eroded by arroyos. The eroded surfaces of the arroyos do not expose thick sequences of sandstone outcrops, the presence of which might indicate a water-bearing unit within the immediate subsurface.

This rural site location does not contain an abundant amount of groundwater elevation data. Groundwater data available from the NM State Engineer's iWaters Database for wells near the proposed site are attached. Wells located at lower elevations and closer to the San Juan River contain groundwater at depths ranging from 30 to 90 feet. A single data point located north of the site identifies groundwater depth at 5 feet; however, closer inspection of the well log indicates groundwater at 5 feet depth after completion of the well. During well installation, groundwater was not reached until 49 feet below ground surface. The site in question is located within a shaley area slightly southwest of Pinon Mesa, near the head of Coolidge Arroyo. It is approximately 5683 feet in elevation. Elevations within the closest arroyo are 62 feet lower, and the San Juan River is 500 feet lower in elevation.

Since representative groundwater data are lacking, local topographic features and geologic formations must be used to estimate depth to groundwater at the proposed site. Exposures of shale at the surface and within channel cuts of arroyos suggest groundwater is restricted to deeper sandstone units, as do well logs completed during groundwater well installations nearby. However, proximity of the site to the San Juan River should also be considered. Therefore, depth to groundwater is estimated to be between 50 and 100 feet.




Lodestar Services, Inc PO Box 4465 Durango, CO 81302 WF State 16-3 T30N, R14W, S16O San Juan County, NM Topographic Map and Aerial Photograph




New Mexico Office of the State Engineer POD Reports and Downloads

	Township: Range: 14V Sections:		
	NAD27 X: Y: Zone:	Search Radius:	
	County: Basin:	Number: Suffix:	
	Owner Name: (First) (Last)	Non-Domestic Domestic All	
	POD / Surface Data ReportAvg Depth to Wate	r ReportWater Column Report	
WATER COLUMN REPORT 08/20/2008 (quarters are 1=NW 2=NE 3=SW 4=SE) (quarters are biggest to smallest) Depth Depth Water (in feet)			
POD Number SJ 00944	Tws Rng Sec q q q Zone X 30N 14W 03 1 3	Well Water Column 61 5 56	

Record Count: 1





XTO Energy Inc. San Juan Basin Below Grade Tank Design and Construction Plan

In accordance with Rule 19.15.17.11 NMAC the following information describes the design and construction of below grade tanks on XTO Energy Inc. (XTO) locations. This is XTO's standard procedure for all below grade tanks. A separate plan will be submitted for any below grade tank (BGT) which does not conform to this plan.

General Plan

- 1. XTO will design and construct a BGT to contain liquids and solids and prevent contamination of fresh water and protect public heath and environment.
- 2. Prior to constructing the pit, topsoil will be stockpiled in the construction zone for later use in restoration.
- 3. XTO will post a well sign, in compliance with 19.15.3.103 NMAC, on the well site prior to construction of the BGT. The sign will list the Operator on record as the operator, the location of the well site by unit letter, section, township, range, and emergency telephone numbers.
- 4. XTO shall construct all new fences utilizing 48" steel mesh field-fence (hogwire) on the bottom with two strands of barbed wire on top, or with a pipe top rail. A 6' chain link fence topped with three stands of barbed wire will be used if the well location is within 1000' of a permanent residence, school, hospital, institution or church.
- 5. XTO shall construct an expanded metal covering on top of the BGT.
- 6. XTO will ensure that a BGT is constructed of materials resistant to the BGT's particular contents and resistant to damage from sunlight.
- The BGT system will have a properly constructed foundation consisting of a level base free of
 rocks, debris, sharp edges or irregularities to prevent punctures, cracks or indentations of the liner
 or tank bottom.
- XTO will construct a berm and/or diversion ditch in a manner that prevents the collection of surface water run-on.
- 9. XTO will construct and use BGT that does not have double walls. The BGT sidewalls will be open for visual inspection for leaks, the BGT bottom will be elevated a minimum of 6" above the underlying ground surface and the BGT will be underlain with a geomembrane liner to divert leaked liquid to a location that can be visually inspected.
- 10. XTO will equip BGT's designed in this manner with a properly functioning automatic high-level shut-off control device and manual controls to prevent overflows.
- 11. The geomembrane liner shall consist of 30-mil flexible PVC or 60-mil HDPE liner, or an equivalent liner material that the appropriate division district office approves. The geomembrane liner shall have a hydraulic conductivity greater that 1 x 10-9 cm/sec. The geomembrane liner shall be composed of an impervious, synthetic material that is resistant to petroleum hydrocarbons, salts and acidic and alkaline solutions. The liner material shall be resistant to ultraviolet light. Liner compatibility shall comply with EPA SW-846 method 9090A.
- 12. The general specifications for design and construction are attached.

XTO Energy Inc. San Juan Basin Below Grade Tank Maintenance and Operating Plan

In accordance with Rule 19.15.17.11 NMAC the following information describes the operation and maintenance of below grade tanks on XTO Energy Inc. (XTO) locations. This is XTO's standard procedure for all below grade tanks. A separate plan will be submitted for any below grade tank (BGT) which does not conform to this plan.

General Plan

- 1. XTO will operate and maintain a BGT to contain liquids and solids and prevent contamination of fresh water and protect public health and the environment.
- 2. XTO will not allow a BGT to overflow and will use berms and/or diversion ditch to prevent surface run on to enter the BGT.
- 3. XTO will continuously remove any visible or measurable layer of oil from the fluid surface of a BGT in order to prevent significant accumulation of oil.
- 4. XTO will inspect the BGT monthly and maintain written records for five years.
- 5. XTO will maintain adequate freeboard to prevent over topping of the BGT.

XTO Energy Inc. San Juan Basin Below Grade Tank Closure Plan

In accordance with Rule 19.15.17.11 NMAC the following information describes the closure requirements of below grade tanks on XTO Energy Inc. (XTO) locations. This is XTO's standard procedure for all below grade tanks. A separate plan will be submitted for any below grade tank (BGT) which does not conform to this plan.

General Plan

- XTO will close a BGT within the time periods provided in 19.15.17.13 NMAC, or by an earlier date that the division requires because of imminent danger to fresh water, public health or the environment.
- 2. XTO will close an existing BGT that does not meet the requirements of Paragraphs (1) through (4) of Subsection I of 19.15.17.11 NMAC or is not included in Paragraph (5) of Subsection I of 19.15.17.11 NMAC within five years after June 16, 2008, if not retrofitted to comply with Paragraphs (1) through (4) of Subsection I of 19.15.17.11 NMAC.
- 3. XTO will close a permitted BGT within 60 days of cessation of the BGT's operation or as required by the transitional provisions of Subsection B of 19.15.17.17 NMAC in accordance with a closure plan that the appropriate division district office approves. The closure report will be filed on form C-144.
- 4. XTO will remove liquids and sludge from a BGT prior to implementing a closure method and will dispose of the liquids and sludge in a division-approved facility.
- 5. XTO will remove the BGT and dispose of it in a division approved facility or recycle, reuse, or reclaim it in a manner that the appropriate division district office approves.
- 6. XTO will remove any on-site equipment associated with a BGT unless the equipment is required for some other purpose.
- 7. XTO will test the solids beneath the BGT to determine whether a release has occurred. At a minimum 5 point composite sample will be collected along with individual grab samples from any area that is wet, discolored or showing other evidence of a release. Samples will be analyzed for BTEX, TPH and chlorides to demonstrate that the benzene concentration, as determined by EPA SW-846 methods 8021B or 8260B or EPA method that the division approves, does not exceed 0.2 mg/kg; total BTEX concentration, as determined by EPA SW-846 methods 8021B or 8260B or other EPA method that the division approves, does not exceed 50 mg/kg; the TPH concentration, as determined by EPA method 418.1 or other EPA method that the division approves, does not exceed 100mg/kg; and the chloride concentration, as determined by EPA method 300.1 or other EPA method that the division approves, does not exceed 250 mg/kg, or the background concentration, whichever is greater. XTO will notify the division of its results on form C-141.
- 8. If XTO or the division determines that a release has occurred, XTO will comply with 19.15.3.116 NMAC and 19.15.1.19NMAC as appropriate.
- 9. If the sampling program demonstrates that a release has not occurred or that any release does not exceed the concentrations specified in Paragraph (4) of Subsection E of 19.15.17.13 NMAC, XTO will backfill the excavation with compacted, non-waste containing, earthen material; construct a division prescribed soil cover; recontour and re-vegetate the site.
- 10. Notice of Closure will be given to the Aztec Division District III office between 72 hours and one week of closure via email or verbally. The notification will include the following:
 - i. Operator's name
 - Location by Unit Letter, Section, Township, and Range. Well name and API number.

- 11. All closure activities will include proper documentation and be available for review upon request and will be submitted to OCD within 60 days of closure of the BGT. Closure report will be filed on form C-144 and incorporate the following:
 - i. Details on capping and covering, where applicable
 - ii. Inspection reports
 - iii. Sampling results
- 12. Re-contouring of location will match fit, shape, line, form and texture of the surrounding area. Re-shaping will include drainage control, prevent ponding, and prevent erosion. Natural drainages will be unimpeded and water bars and/or silt traps will be placed in areas where needed to prevent erosion on a large scale. Final re-contour shall have a uniform appearance with smooth surface, fitting the natural landscape.
- 13. XTO will seed the disturbed areas the first growing season after the operator closes the pit.

 Seeding will be accomplished via drilling on the contour whenever practical or by other division-approved methods. BLM or Forest Service stipulated seed mixes will be used on federal lands. Vegetative cover will equal 70% of the native perennial vegetative cover (un-impacted) consisting of at least three native plant species, including at least one grass, but not including noxious weeds, and maintain that cover through two successive growing seasons. Repeat seeding or planting will be continued until successful vegetative growth occurs.
- 14. A minimum of 4' of cover shall be achieved and the cover shall include 1' of suitable material to establish vegetation at the site, or the background thickness of topsoil, whichever is greater.
- 15. The surface owner shall be notified of XTO's proposal to close the BGT as per the approved closure plan using certified mail, return receipt requested.