

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: January 31, 2018

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

5. Lease Serial No.
N0G13121825

6. If Indian, Allottee or Tribe Name
EASTERN NAVAJO

7. If Unit or CA/Agreement, Name and/or No.
NMNM130812A

8. Well Name and No.
S ESCAVADA UNIT 351H

9. API Well No.
30-043-21317-00-X1

10. Field and Pool or Exploratory Area
BASIN MANCOS
RUSTY GALLUP

11. County or Parish, State
SANDOVAL COUNTY, NM

SUBMIT IN TRIPLICATE - Other instructions on page 2

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator **ENDURING RESOURCES LLC** Contact: **LACEY GRANILLO**
E-Mail: lgranillo@enduringresources.com

3a. Address **1050 17TH STREET SUITE 2500 DENVER, CO 80265**
3b. Phone No. (include area code) Ph: **505-636-9743**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
**Sec 27 T22N R7W NESE 2087FSL 417FEL
36.108429 N Lat, 107.555611 W Lon**

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	Change to Original APD
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.

change in plans

A summary of the requested changes to the approved APD is outlined below. Please reference the attachments for additional details.

C102
Moved BHL from section 22 to section 22
Moved POE from section 27 to section 27
Drilling Program
Directional plan updated based on new POE and BHL
Casing program change

**ADHERE TO PREVIOUS NMOCD
CONDITIONS OF APPROVAL
No NSL**

NMOCD

FEB 26 2020

DISTRICT III

14. I hereby certify that the foregoing is true and correct.

**Electronic Submission #501382 verified by the BLM Well Information System
For ENDURING RESOURCES LLC, sent to the Farmington
Committed to AFMSS for processing by JOE KILLINS on 02/24/2020 (20JK0134SE)**

Name (Printed/Typed) **LACEY GRANILLO**

Title **PERMITTING SPECIALIST**

Signature (Electronic Submission)

Date **01/29/2020**

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By **JOE KILLINS**

Title **PETROLEUM ENGINEER**

Date **02/24/2020**

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office **Farmington**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

**** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ****

NMOCD

17



Additional data for EC transaction #501382 that would not fit on the form

32. Additional remarks, continued

Surface: 9-5/8" to 13-3/8"

Intermediate: 7" to 9-5/8"

Production: 4-1/2" liner to 5-1/2" long-string

Frac Program

Fluid type: change from nitrogen foam to slick-water

Water volume: increase from not provided bbls to 210,000 bbls (estimated)

Sand weight: increase from 6.5 million lbs to 10.0 million lbs (estimated)



ENDURING RESOURCES IV, LLC
1050 SEVENTEENTH STREET, SUITE 2500
DENVER, COLORADO 80265

DRILLING PLAN: *Drill, complete, and equip single lateral in the Mancos-H formation*

WELL INFORMATION:

Name: S ESCAVADA UNIT 351H
API Number: 30-043-21317
AFE Number: not yet assigned
ER Well Number: not yet assigned
State: New Mexico
County: Sandoval

Surface Elevation: 6,749 ft ASL (GL) 6,774 ft ASL (KB)
Surface Location: 27-22N-07W Sec-Twn-Rng 2,087 ft FSL 417 ft FEL
 36.108428 ° N latitude 107.555611 ° W longitude (NAD 83)
BH Location: 22-22N-07W Sec-Twn-Rng 1,853 ft FSL 330 ft FWL
 36.122891 ° N latitude 107.570245 ° W longitude (NAD 83)

Driving Directions: FROM THE INTERSECTION OF US HWY 550 & US HWY 64 IN BLOOMFIELD, NM:

South on US Hwy 550 for 48.9 miles to MM 103; Right (South) on Atkins Road for 3.2 miles to fork; Left (South) continuing on Atkins Road for 1.1 miles to 4-way intersection; Straight (south) for 1.6 miles to 4-way intersection; Straight (South) for 1.9 miles to fork; Left (South) for 0.4 miles to fork; Right (South) for 0.3 miles to S Escavada Unit 350H access road; Left (South) along 350H access road for 0.7 miles to S Escavada Unit 350H Pad (Wells: 350H & 351H).

GEOLOGIC AND RESERVOIR INFORMATION:

<i>Prognosis:</i>	Formation Tops	TVD (ft ASL)	TVD (ft KB)	MD (ft KB)	O / G / W	Pressure
	Ojo Alamo	6,290	484	484	W	normal
	Kirtland	6,180	594	594	W	normal
	Fruitland	6,055	719	719	G, W	sub
	Pictured Cliffs	5,705	1,069	1,069	G, W	sub
	Lewis	5,610	1,164	1,164	G, W	normal
	Chacra	5,335	1,439	1,439	G, W	normal
	Cliff House	4,290	2,484	2,496	G, W	sub
	Menefee	4,270	2,504	2,516	G, W	normal
	Point Lookout	3,330	3,444	3,472	G, W	normal
	Mancos	3,125	3,649	3,680	O,G	sub (~0.38)
	Gallup (MNCS_A)	2,850	3,924	3,959	O,G	sub (~0.38)
	MNCS_B	2,740	4,034	4,071	O,G	sub (~0.38)
	MNCS_C	2,645	4,129	4,168	O,G	sub (~0.38)
	MNCS_Cms	2,615	4,159	4,198	O,G	sub (~0.38)
	MNCS_D	2,470	4,304	4,353	O,G	sub (~0.38)
	MNCS_E	2,330	4,444	4,521	O,G	sub (~0.38)
	MNCS_F	2,290	4,484	4,575	O,G	sub (~0.38)
	MNCS_G	2,215	4,559	4,695	O,G	sub (~0.38)
	MNCS_H	2,160	4,614	4,812	O,G	sub (~0.38)
	P.O.E. TARGET	2,114	4,660	5,048	O,G	sub (~0.38)
	PROJECTED TD	2,090	4,684	11,423	O,G	sub (~0.38)

Surface: Nacimiento

Oil & Gas Zones: Several gas bearing zones will be encountered; target formation is the Gallup

Pressure: Normal (0.43 psi/ft) or sub-normal pressure gradients anticipated in all formations

Max. pressure gradient: 0.43 psi/ft Evacuated hole gradient: 0.22 psi/ft
Maximum anticipated BH pressure, assuming maximum pressure gradient: 2,020 psi
Maximum anticipated surface pressure, assuming partially evacuated hole: 990 psi

Temperature: Maximum anticipated BHT is 130° F or less

H₂S INFORMATION:

H₂S Zones: Encountering hydrogen-sulfide bearing zones is **NOT** anticipated.

Safety: Sensors and alarms will be placed in the substructure, on the rig floor, above the pits, and at the shakers.

LOGGING, CORING, AND TESTING:

Mud Logs: None planned; remote geo-steering from drill out of 9-5/8" casing to TD; gas detection from drillout of 13-3/8" casing to TD.

MWD / LWD: Gamma Ray from drillout of 13-3/8" casing to TD

Open Hole Logs: None planned

Testing: None planned

Coring: None planned

Cased Hole Logs: CBL on 5-1/2" casing from deepest free-fall depth to surface

DRILLING RIG INFORMATION:

Contractor: Aztec

Rig No.: 1000

Draw Works: E80 AC 1,500 hp

Mast: Hyduke Triple (136 ft, 600,000 lbs, 10 lines)

Top Drive: NOV IDS-350PE (350 ton)

Prime Movers: 4 - GE Jenbacher Natural Gas Generator

Pumps: 2 - RS F-1600 (7,500 psi)

BOPE 1: Cameron double & single gate rams (13-5/8", 3,000 psi)

BOPE 2: Cameron annular (13-5/8", 5,000 psi)

Choke: Cameron (4", 10,000 psi)

KB-GL (ft): 25

NOTE: A different rig may be used to drill the well depending on rig availability

BOPE REQUIREMENTS:

See attached diagram for details regarding BOPE specifications and configuration.

- 1) Rig will be equipped with upper and lower kelly cocks with handles available.
- 2) Inside BOP and TIW valves will be available to use on all sizes and threads of drill pipe used while drilling the well.
- 2) BOP accumulator will have enough capacity to open the HCR valve, close all rams and annular preventer, and retain minimum of 200 psi above precharge on the closing manifold without the use of closing pumps. The fluid reservoir capacity shall be at least double the usable fluid volume of the accumulator system capacity, and the fluid level shall be maintained at manufacturer's recommendation. There will be two additional sources of power for the closing pumps (electric and air). Sufficient nitrogen bottles will be available and will be recharged when pressure falls below manufacturer's recommended minimum.
- 3) BOP testing shall be conducted (a) when initially installed, (b) whenever any seal is broken or repaired, (c) if the time since the previous test exceeds 30 days. Tests will be conducted using a test plug. BOP ram preventers will be tested to 3,000 psig for 10 minutes, and the annular preventer will be tested to 1,500 psi for 10 minutes. Ram and annular preventers will be tested to 250 psi for 5 minutes. Additionally, BOP and casing strings will be tested to .22 psi/ft or 1,500 psi, whichever is greater but not exceeding 70% of yield strength of the casing, for 30 minutes, prior to drilling out 13-3/8" and 9-5/8" casing. Rams and hydraulically operated remote choke line valve will be function tested daily at a minimum.
- 4) Remote valve for BOP rams, HCR, and choke shall be placed in a location that is readily available to the driller. The remote BOP valve shall be capable of closing and opening the rams.
- 5) Manual locking devices (hand wheels) shall be installed on rams. A valve will be installed on the annular preventer's closing line as close as possible to the preventer to act as a locking device. The valve will be maintained in the open position and shall only be closed when there is no power to the accumulator.

FLUIDS AND SOLIDS CONTROL PROGRAM:

- Fluid Measurement:** Pumps shall be equipped with stroke counters with displays in the dog-house. Slow pump speed shall be recorded daily and after mudding up, at a minimum, on the drilling report. A Pit Volume Totalizer will be installed and the readout will be displayed in the dog-house. Gas-detecting equipment will be installed at the shakers, and readouts will be available in the dog-house and the in the geologist's work-station (if geologist or mud-logger is on-site).
- Closed-Loop System:** A fully, closed-loop system will be utilized. The system will consist of above-ground piping and above-ground storage tanks and bins. The system will not entail any earthen pits, below-grade storage, or drying pads. All equipment will be disassembled and removed from the site when drilling operations cease. The system will be capable of storing all fluids and generated cuttings and of preventing uncontrolled releases of the same. The system will be operated in an efficient manner to allow the recycling and reuse of as much fluid as possible and to minimize the amount of fluids and solids that require disposal.
- Fluid Disposal:** Fluids that cannot be reused, recycled, or returned to the supplier will be hauled to and disposed of at an approved disposal site (Industrial Ecosystem, Inc. or Envirotech, Inc.).
- Solids Disposal:** Drilling solids will be stored (until haul-off) on-site in separate containers with no other waste, debris, or garbage products. Waste solids will be hauled to and disposed of at an approved disposal site (Industrial Ecosystem, Inc. or Envirotech, Inc.).
- Fluid Program:** See "Detailed Drilling Plan" section for specifics.

DETAILED DRILLING PLAN:

SURFACE: Drill vertically to casing setting depth (plus necessary rathole), run casing, cement casing to surface.

0 ft (MD)	to	350 ft (MD)	Hole Section Length:	350 ft
0 ft (TVD)	to	350 ft (TVD)	Casing Required:	350 ft

Note: Surface hole may be drilled, cased, and cemented with a smaller rig in advance of the drilling rig.

Fluid:	Type	MW (ppg)	FL (mL/30 min)	PV (cp)	YP (lb/100 sqft)	pH	Comments
	Fresh Water	8.4	N/C	2 - 8	2 - 12	9.0	Spud mud

Hole Size: 17-1/2"

Bit / Motor: Mill Tooth or PDC, no motor

MWD / Survey: No MWD, deviation survey

Logging: None

Casing Specs:		Wt (lb/ft)	Grade	Conn.	Collapse (psi)	Burst (psi)	Tens. Body (lbs)	Tens. Conn (lbs)
Specs	13.375	54.5	J-55	BTC	1,130	2,730	853,000	909,000
Loading					153	567	116,634	116,634
Min. S.F.					7.39	4.82	7.31	7.79

Assumptions: Collapse: fully evacuated casing with 8.4 ppg equivalent external pressure gradient
 Burst: maximum anticipated surface pressure with 9.5 ppg fluid inside casing while drilling intermediate hole and 8.4 ppg equivalent external pressure gradient
 Tension: buoyed weight in 8.4 ppg fluid with 100,000 lbs over-pull

MU Torque (ft lbs): Minimum: N/A Optimum: N/A Maximum: N/A

Make-up as per API Buttress Connection running procedure.

Casing Summary: Float shoe, 1 jt casing, float collar, casing to surface

Centralizers: 2 centralizers per jt stop-banded 10' from each collar on bottom 3 jts, 1 centralizer per 2 jts to surface

Cement:	Type	Weight (ppg)	Yield (cuft/sk)	Water (gal/sk)	Hole Cap. (cuft/ft)	% Excess	Planned TOC (ft MD)	Total Cmt (sx)
	Class G	15.8	1.174	5.15	0.6946	100%	0	414

Calculated cement volumes assume gauge hole and the excess noted in table
 Halliburton HALCEM surface cementing blend

Notify NMOCD & BLM if cement is not circulated to surface. Cement must achieve 500 psi compressive strength before drilling out.

INTERMEDIATE: Drill as per directional plan to casing setting depth, run casing, cement casing to surface.

350 ft (MD)	to	2,608 ft (MD)	Hole Section Length:	2,258 ft
350 ft (TVD)	to	2,604 ft (TVD)	Casing Required:	2,608 ft

Fluid:	Type	MW (ppg)	FL (mL/30 min)	PV (cp)	YP (lb/100 sqft)	pH	Comments
	LSND (KCI)	8.8 - 9.5	20	8 - 14	8 - 14	9.0 - 9.5	

Hole Size: 12-1/4"

Bit / Motor: PDC w/mud motor

MWD / Survey: MWD Survey with inclination and azimuth survey (every 100' at a minimum), GR optional

Logging: None

Pressure Test: NU BOPE and test (as noted above); pressure test 13-3/8" casing to 1,500 psi for 30 minutes.

Casing Specs:	Wt (lb/ft)	Grade	Conn.	Collapse (psi)	Burst (psi)	Tens. Body (lbs)	Tens. Conn (lbs)
Specs	9.625	36.0	J-55	LTC	2,020	3,520	564,000
Loading					1,137	1,139	181,875
Min. S.F.					1.78	3.09	3.10

Assumptions: Collapse: fully evacuated casing with 8.4 ppg equivalent external pressure gradient

Burst: maximum anticipated surface pressure with 9.5 ppg fluid inside casing while drilling production hole and 8.4 ppg equivalent external pressure gradient

Tension: buoyed weight in 8.4 ppg fluid with 100,000 lbs over-pull

MU Torque (ft lbs): Minimum: 3,400 Optimum: 4,530 Maximum: 5,660

Casing Summary: Float shoe, 1 jt casing, float collar, casing to surface

Centralizers: 2 centralizers per jt stop-banded 10' from each collar on bottom 3 jts, 1 centralizer per 2 jts to surface

Cement:	Type	Weight (ppg)	Yield (cuft/sk)	Water (gal/sk)	% Excess	Planned TOC (ft MD)	Total Cmt (sx)
Lead	G:POZ Blend	12.3	1.987	10.16	70%	0	580
Tail	Class G	15.8	1.148	4.98	20%	2,108	164

Annular Capacity 0.3627 cuft/ft 9-5/8" casing x 13-3/8" casing annulus

0.3132 cuft/ft 9-5/8" casing x 12-1/4" hole annulus

Calculated cement volumes assume gauge hole and the excess noted in table

Halliburton ECONOCEM & HALCEM cementing blend

Notify NMOCD & BLM if cement is not circulated to surface. Cement must achieve 500 psi compressive strength before drilling out.

PRODUCTION: Drill to TD following directional plan, run casing, cement casing to surface.

2,608 ft (MD)	to	11,423 ft (MD)	Hole Section Length:	8,815 ft
2,604 ft (TVD)	to	4,684 ft (TVD)	Casing Required:	11,423 ft

Estimated KOP:	4,087 ft (MD)	4,050 ft (TVD)
Estimated Landing Point (P.O.E.):	5,048 ft (MD)	4,660 ft (TVD)
Estimated Lateral Length:	6,375 ft (MD)	

Fluid:	Type	MW (ppg)	FL (mL/30')	PV (cp)	YP (lb/100 sqft)	pH	Comments
	LSND (FW)	8.8 - 9.5	20	8 - 14	8 - 14	9.0 - 9.5	OBM as contingency

Hole Size: 8-1/2"

Bit / Motor: PDC w/mud motor

MWD / Survey: MWD with GR, inclination, and azimuth (survey every joint from KOP to Landing Point and survey every 100' minimum before KOP and after Landing Point)

Logging: GR MWD for entire section, no mud-log or cuttings sampling, no OH WL logs

Pressure Test: NU BOPE and test (as noted above); pressure test 9-5/8" casing to **1,500** psi for 30 minutes.

Casing Specs:	Size (in)	Wt (lb/ft)	Grade	Conn.	Collapse (psi)	Burst (psi)	Tens. Body (lbs)	Tens. Conn (lbs)
Specs	5.500	17.0	P-110	LTC	7,460	10,640	546,000	445,000
Loading					2,314	8,938	267,569	267,569
Min. S.F.					3.22	1.19	2.04	1.66

Assumptions: Collapse: fully evacuated casing with 9.5 ppg fluid in the annulus (floating casing during running)

Burst: 8,500 psi maximum surface treating pressure with 10.2 ppg equivalent mud weight sand laden fluid with 8.4 ppg equivalent external pressure gradient

Tension: buoyed weight in 9.0 ppg fluid with 100,000 lbs over-pull

MU Torque (ft lbs): Minimum: 3,470 Optimum: 4,620 Maximum: 5,780

Casing Summary: Float shoe, 1 jt casing, float collar, 1 jt casing, float collar, 1 jt casing, toe-initiation sleeve, 20' marker joint, toe-initiation sleeve, casing to KOP with 20' marker joints spaced evenly in lateral every 2,000', floatation sub, casing to surface. **The toe-initiation sleeves must be positioned INSIDE the 330' unit setback.**

Centralizers: Centralizer count and placement may be adjusted based on well conditions and as-drilled surveys.

Lateral: 1 centralizer per joint

Curve: 1 centralizer per joint from landing point to KOP

KOP to surf: 1 centralizer per 2 joints

Cement:	Type	Weight (ppg)	Yield (cuft/sk)	Water (gal/sk)	% Excess	Planned TOC (ft MD)	Total Cmt (sx)
Lead	G:POZ blend	12.4	1.907	9.981	50%	0	796
Tail	G:POZ blend	13.3	1.360	5.999	10%	3,959	1,383

Annular Capacity 0.2691 cuft/ft 5-1/2" casing x 9-5/8" casing annulus

0.2291 cuft/ft 5-1/2" casing x 8-1/2" hole annulus

Calculated cement volumes assume gauge hole and the excess noted in table

Halliburton ECONOCEM & EXTENDACEM cementing blend

Notify NMOCD & BLM if cement is not circulated to surface.

Note: The lateral may be drilled outside the applicable unit setback to maximize the length of the completed interval and to maximize resource recovery. If the well is drilled outside the setback, the toe initiation sleeve(s) and all perforations will be placed inside the setback. An unorthodox location application is not required because the completed interval will be entirely within the setback as defined and allowed by NMAC 19.15.16.7B(1), NMAC 19.15.16.14B(2), NMAC 19.15.16.15B(2). S Escavada Unit Order Number is R-14347.

FINISH WELL: ND BOP, cap well, RDMO.

COMPLETION AND PRODUCTION PLAN:

Frac: 35 plug-and-perf stages with 210,000 bbls slickwater fluid and 10,000,000 lbs of proppant (estimated)

Flowback: Flow back through production tubing as pressures allow (ESP may be used for load recovery assistance)

Production: Produce through production tubing via gas-lift into permanent production and storage facilities

ESTIMATED START DATES:

Drilling: TBD

Completion: TBD

Production: TBD

Prepared by: Alec Bridge 1/28/2020

WELL NAME: S ESCAVADA UNIT 351H

OBJECTIVE: Drill, complete, and equip single lateral in the Mancos-H formation

API Number: 30-043-21317

AFE Number: not yet assigned

ER Well Number: not yet assigned

State: New Mexico

County: Sandoval

Surface Elev.: 6,749 ft ASL (GL) 6,774 ft ASL (KB)


Surface Location: 27-22N-07W Sec-Twn-Rng 2,087 ft FSL 417 ft FEL

BH Location: 22-22N-07W Sec-Twn-Rng 1853 ft FSL 330 ft FWL

Driving Directions: **FROM THE INTERSECTION OF US HWY 550 & US HWY 64 IN BLOOMFIELD, NM:**

South on US Hwy 550 for 48.9 miles to MM 103; Right (South) on Atkins Road for 3.2 miles to fork; Left (South) continuing on Atkins Road for 1.1 miles to 4-way intersection; Straight (south) for 1.6 miles to 4-way intersection; Straight (South) for 1.9 miles to fork; Left (South) for 0.4 miles to fork; Right (South) for 0.3 miles to S Escavada Unit 350H access road; Left (South) along 350H access road for 0.7 miles to S Escavada Unit 350H Pad (Wells: 350H & 351H).

QUICK REFERENCE	
Sur TD (MD)	350 ft
Int TD (MD)	2,608 ft
KOP (MD)	4,087 ft
KOP (TVD)	4,050 ft
Target (TVD)	4,660 ft
Curve BUR	10 ^o /100 ft
POE (MD)	5,048 ft
TD (MD)	11,423 ft
Lat Len (ft)	6,375 ft



	Tops	TVD (ft KB)	MD (ft KB)
	Ojo Alamo	484	484
	Kirtland	594	594
	Fruitland	719	719
	Pictured Cliffs	1,069	1,069
	Lewis	1,164	1,164
	Chacra	1,439	1,439
	Cliff House	2,484	2,496
	Menefee	2,504	2,516
	Point Lookout	3,444	3,472
	Mancos	3,649	3,680
	Gallup (MNCS_A)	3,924	3,959
	MNCS_B	4,034	4,071
	MNCS_C	4,129	4,168
	MNCS_Cms	4,159	4,198
	MNCS_D	4,304	4,353
	MNCS_E	4,444	4,521
	MNCS_F	4,484	4,575
	MNCS_G	4,559	4,695
	MNCS_H	4,614	4,812
	P.O.E. TARGET	4,660	5,048
	PROJECTED TD	4,684	11,423

WELL CONSTRUCTION SUMMARY:

	Hole (in)	TD MD (ft)	Csg (in)	Csg (lb/ft)	Csg (grade)	Csg (conn)	Csg Top (ft)	Csg Bot (ft)
Surface	17.500	350	13.375	54.5	J-55	BTC	0	350
Intermediate	12.250	2,608	9.625	36.0	J-55	LTC	0	2,608
Production	8.500	11,423	5.500	17.0	P-110	LTC	0	11,423

CEMENT PROPERTIES SUMMARY:

	Type	Wt (ppg)	Yd (cuft/sk)	Wtr (gal/sk)	Hole Cap. (cuft/ft)	% Excess	TOC (ft MD)	Total (sx)
Surface	Class G	15.8	1.174	5.15	0.6946	100%	0	414
Inter. (Lead)	G-POZ Blend	12.3	1.987	10.16	0.3627	70%	0	580
Inter. (Tail)	Class G	15.8	1.148	4.98	0.3132	20%	2,108	164
Prod. (Lead)	G-POZ blend	12.4	1.907	9.981	0.2691	50%	0	796
Prod. (Tail)	G-POZ blend	13.3	1.360	5.999	0.2291	10%	3,959	1,383

COMPLETION / PRODUCTION SUMMARY:

Frac: 35 plug-and-perf stages with 210,000 bbls slickwater fluid and 10,000,000 lbs of proppant (estimated)

Flowback: Flow back through production tubing as pressures allow (ESP may be used for load recovery assistance)

Production: Produce through production tubing via gas-lift into permanent production and storage facilities





Enduring Resources LLC

Directional Drilling Plan
Plan View & Section View

S Escavada Unit 351H

Sandoval County, New Mexico
T22N - R07W - Sec.27 - Lot I
Surface Latitude: 36.108428°N
Surface Longitude: 107.555611°W
Ground Level: 6749.0
Reference Elevation: KB @ 6774.0usft (Original Well Elev)



Design Target Details

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
351H KOP	4050.0	150.0	400.0	1861472.43	1255158.88	36.108855°N	107.554264°W
351H POE	4660.0	679.3	115.5	1862001.75	1254874.37	36.110298°N	107.555251°W
351H BHL	4684.0	5323.5	-4251.4	1866645.90	1250507.51	36.122891°N	107.570245°W

Directional Drilling Plan Details

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	Vsect
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.0
350.0	0.00	0.00	350.0	0.0	0.0	0.00	0.0
1500.0	0.00	0.00	1500.0	0.0	0.0	0.00	0.0
1839.2	10.18	69.44	1837.4	10.5	28.1	3.00	-9.3
4087.1	10.18	69.44	4050.0	150.0	400.0	0.00	-132.4
4351.4	26.24	351.39	4302.9	217.1	413.3	9.83	-88.3
5047.7	89.78	316.76	4660.0	679.3	115.5	9.83	458.8
11422.5	89.78	316.76	4684.0	5323.5	-4251.4	0.00	6812.8



Enduring Resources LLC

San Juan Basin - S Escavada Unit & Terra Wash CA

350H Pad

351H

Wellbore #1

Plan: Design #1

Standard Planning Report

28 January, 2020



Planning Report

Database: EDM
Company: Enduring Resources LLC
Project: San Juan Basin - S Escavada Unit & Terra Wash CA
Site: 350H Pad
Well: 351H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well 351H
TVD Reference: KB @ 6774.0usft (Original Well Elev)
MD Reference: KB @ 6774.0usft (Original Well Elev)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Project	San Juan Basin - S Escavada Unit & Terra Wash CA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Central Zone		

Site	350H Pad, Sandoval County, New Mexico		
Site Position:	Northing:	1,861,327.42 usft	Latitude: 36 108441"N
From: Lat/Long	Easting:	1,254,739.45 usft	Longitude: 107 555677"W
Position Uncertainty:	0.0 usft	Slot Radius: 13-3/16"	Grid Convergence: -0.77°

Well	351H		
Well Position	+N/-S	-5.0 usft	Northing: 1,861,322.43 usft
	+E/-W	19.4 usft	Easting: 1,254,758.88 usft
Position Uncertainty	0.0 usft	Wellhead Elevation:	Ground Level: 6,749.0 usft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	12/31/2009	9.89	63.00	50,570.92182318

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	321.39

Plan Survey Tool Program	Date	1/28/2020		
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks
1	0.0	11,422.5 Design #1 (Wellbore #1)	MWD	OWSG MWD - Standard

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
350.0	0.00	0.00	350.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,839.2	10.18	69.44	1,837.4	10.5	28.1	3.00	3.00	0.00	69.44	
4,087.1	10.18	69.44	4,050.0	150.0	400.0	0.00	0.00	0.00	0.00	351H KOP
4,351.4	26.24	351.39	4,302.9	217.1	413.3	9.83	6.08	-29.54	-98.98	
5,047.7	89.78	316.76	4,660.0	679.3	115.5	9.83	9.12	-4.97	-37.66	351H POE
11,422.5	89.78	316.76	4,684.0	5,323.5	-4,251.4	0.00	0.00	0.00	0.00	351H BHL



Planning Report

Database: EDM
Company: Enduring Resources LLC
Project: San Juan Basin - S Escavada Unit & Terra Wash CA
Site: 350H Pad
Well: 351H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well 351H
TVD Reference: KB @ 6774.0usft (Original Well Elev)
MD Reference: KB @ 6774.0usft (Original Well Elev)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0 0	0.00	0.00	0 0	0.0	0.0	0.0	0.00	0.00	0.00	
100 0	0.00	0.00	100 0	0.0	0.0	0.0	0.00	0.00	0.00	
200 0	0.00	0.00	200 0	0.0	0.0	0.0	0.00	0.00	0.00	
300 0	0.00	0.00	300 0	0.0	0.0	0.0	0.00	0.00	0.00	
350 0	0.00	0.00	350 0	0.0	0.0	0.0	0.00	0.00	0.00	
13 3/8"										
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00	
484.0	0.00	0.00	484.0	0.0	0.0	0.0	0.00	0.00	0.00	
Ojo Alamo										
500 0	0.00	0.00	500 0	0.0	0.0	0.0	0.00	0.00	0.00	
594 0	0.00	0.00	594 0	0.0	0.0	0.0	0.00	0.00	0.00	
Kirtland										
600 0	0.00	0.00	600 0	0.0	0.0	0.0	0.00	0.00	0.00	
700 0	0.00	0.00	700 0	0.0	0.0	0.0	0.00	0.00	0.00	
719 0	0.00	0.00	719 0	0.0	0.0	0.0	0.00	0.00	0.00	
Fruitland										
800 0	0.00	0.00	800 0	0.0	0.0	0.0	0.00	0.00	0.00	
900 0	0.00	0.00	900 0	0.0	0.0	0.0	0.00	0.00	0.00	
1,000 0	0.00	0.00	1,000 0	0.0	0.0	0.0	0.00	0.00	0.00	
1,069 0	0.00	0.00	1,069 0	0.0	0.0	0.0	0.00	0.00	0.00	
Pictured Cliffs										
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,164.0	0.00	0.00	1,164.0	0.0	0.0	0.0	0.00	0.00	0.00	
Lewis										
1,200 0	0.00	0.00	1,200 0	0.0	0.0	0.0	0.00	0.00	0.00	
1,300 0	0.00	0.00	1,300 0	0.0	0.0	0.0	0.00	0.00	0.00	
1,400 0	0.00	0.00	1,400 0	0.0	0.0	0.0	0.00	0.00	0.00	
1,439 0	0.00	0.00	1,439 0	0.0	0.0	0.0	0.00	0.00	0.00	
Chacra										
1,500 0	0.00	0.00	1,500 0	0.0	0.0	0.0	0.00	0.00	0.00	
1,600 0	3.00	69.44	1,600 0	0.9	2.5	-0.8	3.00	3.00	0.00	
1,700 0	6.00	69.44	1,699.6	3.7	9.8	-3.2	3.00	3.00	0.00	
1,800 0	9.00	69.44	1,798.8	8.3	22.0	-7.3	3.00	3.00	0.00	
1,839.2	10.18	69.44	1,837.4	10.5	28.1	-9.3	3.00	3.00	0.00	
1,900 0	10.18	69.44	1,897.3	14.3	38.2	-12.6	0.00	0.00	0.00	
2,000 0	10.18	69.44	1,995.7	20.5	54.7	-18.1	0.00	0.00	0.00	
2,100 0	10.18	69.44	2,094.1	26.7	71.3	-23.6	0.00	0.00	0.00	
2,200 0	10.18	69.44	2,192.5	32.9	87.8	-29.1	0.00	0.00	0.00	
2,300 0	10.18	69.44	2,291.0	39.1	104.4	-34.5	0.00	0.00	0.00	
2,400 0	10.18	69.44	2,389.4	45.3	120.9	-40.0	0.00	0.00	0.00	
2,496.1	10.18	69.44	2,484.0	51.3	136.8	-45.3	0.00	0.00	0.00	
Menefee										
2,500 0	10.18	69.44	2,487.8	51.5	137.4	-45.5	0.00	0.00	0.00	
2,516.4	10.18	69.44	2,504.0	52.6	140.2	-46.4	0.00	0.00	0.00	
Cliff House										
2,600 0	10.18	69.44	2,586.3	57.7	154.0	-51.0	0.00	0.00	0.00	
2,607.9	10.18	69.44	2,594.0	58.2	155.3	-51.4	0.00	0.00	0.00	
9 5/8"										
2,700 0	10.18	69.44	2,684.7	63.9	170.5	-56.4	0.00	0.00	0.00	
2,800 0	10.18	69.44	2,783.1	70.2	187.1	-61.9	0.00	0.00	0.00	
2,900 0	10.18	69.44	2,881.5	76.4	203.6	-67.4	0.00	0.00	0.00	
3,000 0	10.18	69.44	2,980.0	82.6	220.2	-72.9	0.00	0.00	0.00	



Planning Report

Database: EDM
Company: Enduring Resources LLC
Project: San Juan Basin - S Escavada Unit & Terra Wash CA
Site: 350H Pad
Well: 351H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well 351H
TVD Reference: KB @ 6774.0usft (Original Well Elev)
MD Reference: KB @ 6774.0usft (Original Well Elev)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
3,100.0	10.18	69.44	3,078.4	88.8	236.7	-78.3	0.00	0.00	0.00
3,200.0	10.18	69.44	3,176.8	95.0	253.2	-83.8	0.00	0.00	0.00
3,300.0	10.18	69.44	3,275.2	101.2	269.8	-89.3	0.00	0.00	0.00
3,400.0	10.18	69.44	3,373.7	107.4	286.3	-94.8	0.00	0.00	0.00
3,471.5	10.18	69.44	3,444.0	111.8	298.1	-98.7	0.00	0.00	0.00
Point Lookout									
3,500.0	10.18	69.44	3,472.1	113.6	302.9	-100.3	0.00	0.00	0.00
3,600.0	10.18	69.44	3,570.5	119.8	319.4	-105.7	0.00	0.00	0.00
3,679.7	10.18	69.44	3,649.0	124.7	332.6	-110.1	0.00	0.00	0.00
Mancos									
3,700.0	10.18	69.44	3,668.9	126.0	336.0	-111.2	0.00	0.00	0.00
3,800.0	10.18	69.44	3,767.4	132.2	352.5	-116.7	0.00	0.00	0.00
3,900.0	10.18	69.44	3,865.8	138.4	369.0	-122.2	0.00	0.00	0.00
3,959.1	10.18	69.44	3,924.0	142.1	378.8	-125.4	0.00	0.00	0.00
Gallup (MNCS A)									
4,000.0	10.18	69.44	3,964.2	144.6	385.6	-127.6	0.00	0.00	0.00
4,070.9	10.18	69.44	4,034.0	149.0	397.3	-131.5	0.00	0.00	0.00
MNCS_B									
4,087.1	10.18	69.44	4,050.0	150.0	400.0	-132.4	0.00	0.00	0.00
4,100.0	10.06	62.28	4,062.7	150.9	402.1	-133.0	9.83	-0.94	-55.75
4,167.5	11.84	28.02	4,129.0	159.8	410.5	-131.3	9.83	2.65	-50.74
MNCS_C									
4,198.3	13.67	17.09	4,159.0	166.0	413.1	-128.0	9.83	5.95	-35.57
MNCS_Cms									
4,200.0	13.79	16.56	4,160.7	166.4	413.2	-127.8	9.83	6.66	-30.45
4,300.0	21.69	356.79	4,255.9	196.4	415.6	-105.9	9.83	7.90	-19.77
4,351.4	26.24	351.39	4,302.9	217.1	413.3	-88.3	9.83	8.87	-10.50
4,352.6	26.34	351.22	4,304.0	217.7	413.3	-87.8	9.83	7.79	-13.54
MNCS_D									
4,400.0	30.16	345.57	4,345.7	239.6	408.7	-67.8	9.83	8.06	-11.92
4,500.0	38.78	337.15	4,428.1	292.9	390.2	-14.6	9.83	8.62	-8.43
4,520.6	40.61	335.80	4,444.0	305.0	385.0	-1.9	9.83	8.91	-6.51
MNCS_E									
4,575.4	45.56	332.68	4,484.0	338.6	368.7	34.5	9.83	9.03	-5.71
MNCS_F									
4,600.0	47.80	331.44	4,500.9	354.4	360.3	52.1	9.83	9.13	-5.02
4,694.8	56.56	327.38	4,559.0	418.8	322.1	126.2	9.83	9.23	-4.28
MNCS_G									
4,700.0	57.04	327.18	4,561.8	422.4	319.7	130.5	9.83	9.30	-3.79
4,800.0	66.39	323.75	4,609.2	494.8	269.8	218.3	9.83	9.35	-3.44
4,812.4	67.56	323.36	4,614.0	503.9	263.0	229.6	9.83	9.40	-3.14
MNCS_H									
4,900.0	75.81	320.77	4,641.5	569.5	211.9	312.8	9.83	9.42	-2.95
5,000.0	85.27	318.03	4,657.9	644.2	147.7	411.2	9.83	9.45	-2.74
5,047.7	89.78	316.76	4,660.0	679.3	115.5	458.8	9.83	9.46	-2.66
5,100.0	89.78	316.76	4,660.2	717.4	79.7	510.9	0.00	0.00	0.00
5,200.0	89.78	316.76	4,660.6	790.3	11.2	610.5	0.00	0.00	0.00
5,300.0	89.78	316.76	4,660.9	863.1	-57.3	710.2	0.00	0.00	0.00
5,400.0	89.78	316.76	4,661.3	936.0	-125.8	809.9	0.00	0.00	0.00
5,500.0	89.78	316.76	4,661.7	1,008.8	-194.3	909.6	0.00	0.00	0.00
5,600.0	89.78	316.76	4,662.1	1,081.7	-262.8	1,009.2	0.00	0.00	0.00
5,700.0	89.78	316.76	4,662.5	1,154.5	-331.3	1,108.9	0.00	0.00	0.00



Planning Report

Database: EDM Company: Enduring Resources LLC Project: San Juan Basin - S Escavada Unit & Terra Wash CA Site: 350H Pad Well: 351H Wellbore: Wellbore #1 Design: Design #1	Local Co-ordinate Reference: Well 351H TVD Reference: KB @ 6774 0usft (Original Well Elev) MD Reference: KB @ 6774 0usft (Original Well Elev) North Reference: Grid Survey Calculation Method: Minimum Curvature	
--	---	--

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
5,800 0	89 78	316 76	4 662 8	1,227 4	-399 8	1,208 6	0 00	0 00	0 00	
5,900 0	89 78	316 76	4 663 2	1,300 2	-468 3	1,308 3	0 00	0 00	0 00	
6,000 0	89 78	316 76	4 663 6	1,373 1	-536 8	1,407 9	0 00	0 00	0 00	
6,100 0	89 78	316 76	4 664 0	1,445 9	-605 3	1,507 6	0 00	0 00	0 00	
6,200 0	89 78	316 76	4 664 3	1,518 8	-673 6	1,607 3	0 00	0 00	0 00	
6,300 0	89 78	316 76	4 664 7	1,591 6	-742 4	1,706 9	0 00	0 00	0 00	
6,400 0	89 78	316 76	4 665 1	1,664 5	-810 9	1,806 6	0 00	0 00	0 00	
6,500 0	89 78	316 76	4 665 5	1,737 3	-879 4	1,906 3	0 00	0 00	0 00	
6,600 0	89 78	316 76	4 665 8	1,810 2	-947 9	2,006 0	0 00	0 00	0 00	
6,700 0	89 78	316 76	4 666 2	1,883 0	-1,016 4	2,105 6	0 00	0 00	0 00	
6,800 0	89 78	316 76	4 666 6	1,955 9	-1,084 9	2,205 3	0 00	0 00	0 00	
6,900 0	89 78	316 76	4 667 0	2,028 7	-1,153 4	2,305 0	0 00	0 00	0 00	
7,000 0	89 78	316 76	4 667 3	2,101 6	-1,221 9	2,404 7	0 00	0 00	0 00	
7,100 0	89 78	316 76	4 667 7	2,174 4	-1,290 4	2,504 3	0 00	0 00	0 00	
7,200 0	89 78	316 76	4 668 1	2,247 3	-1,358 9	2,604 0	0 00	0 00	0 00	
7,300 0	89 78	316 76	4 668 5	2,320 1	-1,427 4	2,703 7	0 00	0 00	0 00	
7,400 0	89 78	316 76	4 668 9	2,393 0	-1,495 9	2,803 4	0 00	0 00	0 00	
7,500 0	89 78	316 76	4 669 2	2,465 8	-1,564 4	2,903 0	0 00	0 00	0 00	
7,600 0	89 78	316 76	4 669 6	2,538 7	-1,632 9	3,002 7	0 00	0 00	0 00	
7,700 0	89 78	316 76	4 670 0	2,611 6	-1,701 4	3,102 4	0 00	0 00	0 00	
7,800 0	89 78	316 76	4 670 4	2,684 4	-1,769 9	3,202 1	0 00	0 00	0 00	
7,900 0	89 78	316 76	4 670 7	2,757 3	-1,838 4	3,301 7	0 00	0 00	0 00	
8,000 0	89 78	316 76	4 671 1	2,830 1	-1,906 9	3,401 4	0 00	0 00	0 00	
8,100 0	89 78	316 76	4 671 5	2,903 0	-1,975 4	3,501 1	0 00	0 00	0 00	
8,200 0	89 78	316 76	4 671 9	2,975 8	-2,043 9	3,600 7	0 00	0 00	0 00	
8,300 0	89 78	316 76	4 672 2	3,048 7	-2,112 4	3,700 4	0 00	0 00	0 00	
8,400 0	89 78	316 76	4 672 6	3,121 5	-2,180 9	3,800 1	0 00	0 00	0 00	
8,500 0	89 78	316 76	4 673 0	3,194 4	-2,249 4	3,899 8	0 00	0 00	0 00	
8,600 0	89 78	316 76	4 673 4	3,267 2	-2,317 9	3,999 4	0 00	0 00	0 00	
8,700 0	89 78	316 76	4 673 8	3,340 1	-2,386 4	4,099 1	0 00	0 00	0 00	
8,800 0	89 78	316 76	4 674 1	3,412 9	-2,454 9	4,198 8	0 00	0 00	0 00	
8,900 0	89 78	316 76	4 674 5	3,485 8	-2,523 4	4,298 5	0 00	0 00	0 00	
9,000 0	89 78	316 76	4 674 9	3,558 6	-2,591 9	4,398 1	0 00	0 00	0 00	
9,100 0	89 78	316 76	4 675 3	3,631 5	-2,660 4	4,497 8	0 00	0 00	0 00	
9,200 0	89 78	316 76	4 675 6	3,704 3	-2,728 9	4,597 5	0 00	0 00	0 00	
9,300 0	89 78	316 76	4 676 0	3,777 2	-2,797 4	4,697 2	0 00	0 00	0 00	
9,400 0	89 78	316 76	4 676 4	3,850 0	-2,865 9	4,796 8	0 00	0 00	0 00	
9,500 0	89 78	316 76	4 676 8	3,922 9	-2,934 4	4,896 5	0 00	0 00	0 00	
9,600 0	89 78	316 76	4 677 1	3,995 7	-3,002 9	4,996 2	0 00	0 00	0 00	
9,700 0	89 78	316 76	4 677 5	4,068 6	-3,071 4	5,095 8	0 00	0 00	0 00	
9,800 0	89 78	316 76	4 677 9	4,141 4	-3,139 9	5,195 5	0 00	0 00	0 00	
9,900 0	89 78	316 76	4 678 3	4,214 3	-3,208 4	5,295 2	0 00	0 00	0 00	
10,000 0	89 78	316 76	4 678 6	4,287 1	-3,276 9	5,394 9	0 00	0 00	0 00	
10,100 0	89 78	316 76	4 679 0	4,360 0	-3,345 4	5,494 5	0 00	0 00	0 00	
10,200 0	89 78	316 76	4 679 4	4,432 8	-3,413 9	5,594 2	0 00	0 00	0 00	
10,300 0	89 78	316 76	4 679 8	4,505 7	-3,482 4	5,693 9	0 00	0 00	0 00	
10,400 0	89 78	316 76	4 680 2	4,578 5	-3,550 9	5,793 6	0 00	0 00	0 00	
10,500 0	89 78	316 76	4 680 5	4,651 4	-3,619 4	5,893 2	0 00	0 00	0 00	
10,600 0	89 78	316 76	4 680 9	4,724 2	-3,687 9	5,992 9	0 00	0 00	0 00	
10,700 0	89 78	316 76	4 681 3	4,797 1	-3,756 4	6,092 6	0 00	0 00	0 00	
10,800 0	89 78	316 76	4 681 7	4,870 0	-3,824 9	6,192 3	0 00	0 00	0 00	
10,900 0	89 78	316 76	4 682 0	4,942 8	-3,893 4	6,291 9	0 00	0 00	0 00	
11,000 0	89 78	316 76	4 682 4	5,015 7	-3,961 9	6,391 6	0 00	0 00	0 00	



Planning Report

Database: EDM
Company: Enduring Resources LLC
Project: San Juan Basin - S Escavada Unit & Terra Wash CA
Site: 350H Pad
Well: 351H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well 351H
TVD Reference: KB @ 6774.0usft (Original Well Elev)
MD Reference: KB @ 6774.0usft (Original Well Elev)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
11,100.0	89.78	316.76	4,682.8	5,088.5	-4,030.4	6,491.3	0.00	0.00	0.00
11,200.0	89.78	316.76	4,683.2	5,161.4	-4,098.9	6,591.0	0.00	0.00	0.00
11,300.0	89.78	316.76	4,683.5	5,234.2	-4,167.4	6,690.6	0.00	0.00	0.00
11,400.0	89.78	316.76	4,683.9	5,307.1	-4,235.9	6,790.3	0.00	0.00	0.00
11,422.5	89.78	316.76	4,684.0	5,323.5	-4,251.4	6,812.8	0.00	0.00	0.00

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
351H KOP - plan hits target center - Point	0.00	360.00	4,050.0	150.0	400.0	1,861,472.43	1,255,158.88	36 108855°N	107 554264°W
351H POE - plan hits target center - Point	0.00	360.00	4,660.0	679.3	115.5	1,862,001.75	1,254,874.37	36.110298°N	107 555251°W
351H BHL - plan hits target center - Point	0.00	0.00	4,684.0	5,323.5	-4,251.4	1,866,645.90	1,250,507.51	36 122891°N	107 570245°W

Casing Points

Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (")	Hole Diameter (")
350.0	350.0	13 3/8"	13-3/8	17-1/2
2,607.9	2,594.0	9 5/8"	9-5/8	12-1/4



Planning Report

Database:	EDM	Local Co-ordinate Reference:	Well 351H
Company:	Enduring Resources LLC	TVD Reference:	KB @ 6774.0usft (Original Well Elev)
Project:	San Juan Basin - S Escavada Unit & Terra Wash CA	MD Reference:	KB @ 6774.0usft (Original Well Elev)
Site:	350H Pad	North Reference:	Grid
Well:	351H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
484.0	484.0	Ojo Alamo		0.00		
594.0	594.0	Kirtland		0.00		
719.0	719.0	Fruitland		0.00		
1,069.0	1,069.0	Pictured Cliffs		0.00		
1,164.0	1,164.0	Lewis		0.00		
1,439.0	1,439.0	Chacra		0.00		
2,496.1	2,484.0	Menefee		0.00		
2,516.4	2,504.0	Cliff House		0.00		
3,471.5	3,444.0	Point Lookout		0.00		
3,679.7	3,649.0	Mancos		0.00		
3,959.1	3,924.0	Gallup (MNCS A)		0.00		
4,070.9	4,034.0	MNCS_B		0.00		
4,167.5	4,129.0	MNCS_C		0.00		
4,198.3	4,159.0	MNCS_Cms		0.00		
4,352.6	4,304.0	MNCS_D		0.00		
4,520.6	4,444.0	MNCS_E		0.00		
4,575.4	4,484.0	MNCS_F		0.00		
4,694.8	4,559.0	MNCS_G		0.00		
4,812.4	4,614.0	MNCS_H		0.00		