Form 3160-3 (September 2001)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED OMB No. 1004-0136 Expires January 31, 2004

-		_	_		
5.	Ĺ	ease	S	erial	No.

BUREAU OF LAND MANAGEMENT APPLICATION FOR PERMIT TO DRILL OR	PAM Sinc	11	89	2	50 SF-078765
APPLICATION FOR PERMIT TO DRILL OR	REENTER	-خا		- (6. If Indian, Allottee or Tribe Name

			·	
la. Type of Work: 🛛 DRILL 🔲 REENTER	ATO FARM	HISTON	7. If Unit or CA Agreeme	
			8. Lease Name and Well N	
1b. Type of Well: Oil Well Gas Well Other	Single Zone Mul	tiple Zone	181B	
Name of Operator Williams Production Company, LLC.			9. API Well No. 30-039-2	9901
3a. Address	3b. Phone No. (include area code)		10. Field and Pool, or Expl	
P.O. Box 640 Aztec, NM 87410	(505) 634-4208		Bianco Mesaverde	
4. Location of Well (Report location clearly and in accordance with any	State requirements. *)		11. Sec., T., R., M., or Blk	. and Survey or Area
At surface 2420' FSL & 1460' FWL, T31N, R6W, Secti	on 11 K			
At proposed prod. zone 2420' FSL & 340' FEL, T31N, R6	SW, Section 10 T		Section 19, 31N, 6\	V .
14. Distance in miles and direction from nearest town or post office*			12. County or Parish	13. State
approximately 26 miles northeast of Blanco, New Mexico			Rio Arriba	NM
 Distance from proposed* location to nearest property or lease line, ft. 	16. No. of Acres in lease	17. Spacing	g Unit dedicated to this well	
(Also to nearest drig. unit line, if any) 1460'	2,460.230	320	.0 (E/2)	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.	19. Proposed Depth	20. BLM/E	BIA Bond No. on file	
500'	6,609'	UT0	<u> </u>	78
21. Elevations (Show whether DF, KDB, RT, GL, etc.)	22. Approximate date work will	start*	23. Estimated duration	
6,263' GR	June 1, 2006		1 month	
	24. Attachments			
 The following, completed in accordance with the requirements of Onshor Well plat certified by a registered surveyor. A Drilling Plan. A Surface Use Plan (if the location is on National Forest System I SUPO shall be filed with the appropriate Forest Service Office). 	4. Bond to cover t Item 20 above) 5. Operator certific	he operations . cation. specific info	sunless covered by an exist	•
25. Signature	Name (Printed/Typed)		Dat	e
lany Argan	Larry Higgins			5/8/2006
Title				
Drilling COM				
Approved by (Signature)	Name (Printed/Typed)		Date €	120/86
Title AEM	Office FI	د		γ
Application approval does not warrant or certify that the applicant holds to operations thereon. Conditions of approval, if any, are attached.	egal or equitable title to those rights	in the subject l	ease which would entitle the	applicant to conduct
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it states any false, fictitious or fraudulent statements or representations as to		nd willfully to	make to any department or	agency of the United
*(Instructions on reverse)	any matter within its jurisdiction.			
Williams Exploration and Production Company, LLC, proposes to caccordance with the attached drilling and surface use plans.	frill a well to develop the Blanco I	Mesaverde fo	ormation at the above desc	cribed location in
The surface is under jurisdiction of the Bureau of Land Manageme	nt, Farmington Field Office.			
This location has been archaeologically surveyed La Plata Archaed	ological Consultants. Copies of the	eir report ha	ve been submitted directly	to the BLM/FFO.
This APD is also serving as an application to obtain a pipeline right operated by Williams Field Services.	r-of-way (ROW) grant. A 137.60-1	foot pipeline	tie would be required for th	nis location, to be
	-		Walnut i	, TUIIX

This action is subject to technical and propedural review pursuant to 43 CFR 3165.3 and appeal pursuant to 43 CFR 3165.4

District I PO Box 1980, Hobbs, NM 88241-1980

District II PO Drawer DD, Artesia, NM 88211-0719

District III 1000 Rio Brazos Rd., Aztec, NM 87410

District IV PO Box 2088, Santa Fe, NM 87504-2088

State of New Mexico Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION PO Box 2088,

Santa Fe, NM 87504-2088

Form C-102 Revised February 21, 1994 Instructions on back

Submit to Appropriate District Office

State Lease - 4 Copies Fee Lease - 3 Copies

RECEIVED OTO FARMINGTON NM AMENDED REPORT


WELL LOCATION AND ACREAGE DEDICATION PLAT

30:039-21	'Pool Code 72319	*Pool Name BLANCO MESAVERDI	:
'Property Code 17033		Property Name ROSA UNIT	°Well Number 1818
'OGRID № 120782		Operator Name PRODUCTION COMPANY	*Elevation 6263

¹⁰ Surface Location


UL or lot no.	Section 11	Township 31N	Range 6W	Lot Idn	Feet from the 2420	North/South line SOUTH	Feet from the	East/West line WEST	County RIO ARRIBA
		11 E	Bottom	Hole L	ocation I	f Different	From Surf	ace	
UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
I	10	31N	6W		2420	SOUTH	340	EAST	RIO ARRIBA
Dedicated Acres 320.0 Acres - (E/2)		¹³ Joint or Infill	¹⁴ Consolidation Code	²⁵ Order No.					

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



	Submit 3 Copies To Appropriate District	State of	New M	exico		Form C-103
	Office District I	Energy, Minerals	and Nat	ural Resources		May 27, 2004
	1625 N. French Dr., Hobbs, NM 88240				WELL API NO.	9-79901
	District II 1301 W. Grand Ave., Artesia, NM 88210	OIL CONSER'	VATION	NOISIVID I	5. Indicate Type of Le	ace EEDERAL Y
	District III	1220 Sout	h St. Fra	ncis Dr.	STATE	FEE
	1000 Rio Brazos Rd., Aztec, NM 87410 District IV	Santa F	e, NM 8	7505	6. State Oil & Gas Lea	
	1220 S. St. Francis Dr., Santa Fe, NM	·			SF-078771	
[87505 SUNDRY NOT	CES AND REPORTS O	N WELLS	5	7. Lease Name or Unit	Agreement Name
	(DO NOT USE THIS FORM FOR PROPO	SALS TO DRILL OR TO DEE	PEN OR PL	UG BACK TO:A		
	DIFFERENT RESERVOIR. USE "APPLIC PROPOSALS.)	CATION FOR PERMIT" (FOR	M C-101) F	OR SUCH	Rosa Unit	· · · · · · · · · · · · · · · · · · ·
Į	1. Type of Well: Oil Well	Gas Well 🛛 Other			8. Well Number	181B
Ì	2. Name of Operator				9. OGRID Number	120782
Į	Williams Production Company, LL	.C				
	3. Address of Operator				Basin Fruitland Coal	
ļ	P.O. Box 640 Aztec, NM 87410					
1	4. Well Location					
	Unit Letter K: 2420 feet f					
ļ	Section 11 Townshi			NMPM	County Rio Ar	riba
The Parket		11. Elevation (Show wi		, RKB, RT, GR, etc.,		
14.7	Pit or Below-grade Tank Application 🛛 o		3' GR	,)200
	Pit typereserve_Depth to Groundwate		rest fresh w	ater well >1 000' Dist	ance from nearest surface wat	-
- 1		Grade Tank: Volume	est II esii w	bbls; Construction N		
L						
	12. Check A	Appropriate Box to In	dicate N	lature of Notice,	Report or Other Data	l
	NOTICE OF IN	TENTION TO:		SUB	SEQUENT REPOF	RT OF:
	PERFORM REMEDIAL WORK □	PLUG AND ABANDON		REMEDIAL WOR		ERING CASING
	TEMPORARILY ABANDON	CHANGE PLANS	\boxtimes	COMMENCE DRI	· · · · · · · · · · · · · · · · · · ·	
	PULL OR ALTER CASING	MULTIPLE COMPL		CASING/CEMENT	TJOB 🔲	
	OTHER.			OTUED		
-	OTHER: 13. Describe proposed or complete.	leted operations (Clearly	r state all	OTHER:	d give pertinent dates inc	luding estimated date
	of starting any proposed wo					
	or recompletion.	,·			won wone or any and	proposed compretion
_	Orilling/Completion pit to be least	ad approximately 50 to	75 foot f	rom well bond. Di	t multi uso drilling and	aamnlation ta avaid
	Drilling/Completion pit to be locate additional site disturbance and pit					
	operated and closed in accordance					orion dolog,
	•	· ·		F		
-	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1			11 11 0	
	hereby certify that the information a rade tank has been/will be constructed or of					
	/	1/ 2	5ulucinies <u>e</u>	s, a general permit	or an (attached) afternative o	сь-арргочей ріап Ц.
S	GIGNATURE CANTAL !	tigg -	TITLE_I	Orilling COM	_DATE4-24-2006_	
_						
	Type or print name Larry Higgins	E-mail address: larry	y.higgins@	williams.com T	Celephone No. (505) 634-	4208
r	For State Use Only	1/2 1	W		Managa -	
A	APPROVED BY:	Mask.	TITLE 2	eputy oal & gas in	ispector, dist. 🕖 Dat	EUN 2 8 2006
	Conditions of Approval (if any):		` 			
		. u =				

WILLIAMS PRODUCTION COMPANY ROSA UNIT #181B 2420' FSL & 1460' FWL, SECTION 11, T31N, R6W, NMPM RIO ARRIBA COUNTY, NEW MEXICO GROUND BLEVATION: 6263'





WILLIAMS PRODUCTION COMPANY

Operations Plan

(Note: This procedure will be adjusted on site based upon actual conditions)

DATE:

5/8/2006

FIELD:

Blanco MV

WELL NAME:

Rosa #181B

Rio Arriba, NM

SURFACE:

BLM

BH LOCATION:

NESE Sec 10-31N-6W

MINERALS:

BLM

SURF LOCATION:

NESW Sec 11-31N-6W

ELEVATION:

6,263' GR

LEASE#

SF-078771

MEASURED DEPTH: 6,609'

I. GEOLOGY:

Surface formation - San Jose

A. FORMATION TOPS: (KB)

Name	TVD	MD	Name	TVD	MD
Ojo Alamo	2,302	2,770	Cliff House	5,282	5,877
Kirtland	2,402	2,899	Menefee	5,327	5,922
Fruitland	2,822	3,393	Point Lookout	5,562	6,157
Picture Cliffs	3,082	3,670	Mancos	5,897	6,492
Lewis	3,377	3,971	TD	6,012	6,609

- B. MUD LOGGING PROGRAM: none
- C. LOGGING PROGRAM: Cased Hole Logs only
- **D.** <u>NATURAL GAUGES:</u> Gauge any noticeable increases in gas flow. Record all gauges in Tour book and on morning reports.

II. DRILLING:

- A. <u>MUD PROGRAM:</u> Clear water with benex to 7" casing point. Convert to a LSND mud to log and run pipe. Treat for lost circulation as necessary. Obtain 100% returns prior to cementing. Notify Engineering of any mud losses. Use air w/Air Hammer from 7 in. csg.to TD.
- B. <u>BOP TESTING:</u> While drill pipe is in use, the pipe rams and the blind rams will be function tested once each trip. The anticipated reservoir is expected to be less than 1300 psi, so the BOPE will be tested to 250 psi (Low) for 5 minutes and 1500 psi (High) for 10 minutes. Utilize a BOPE Testing Unit with a recording chart and appropriate test plug for testing. The drum brakes will be inspected and tested each tour. All tests and inspections will be recorded in the tour book as to time and results.

III. MATERIALS

A. CASING PROGRAM:

CASING TYPE	HOLE SIZE	DEPTH (MD)	CASING SIZE	WT. & GRADE
Surface	12-1/4"	+/- 300'	9-5/8"	36# K-55
Intermediate	8-3/4"	+/- 4,197'	7"	20# K-55
Prod. Liner	6-1/4"	+/- 4,097'-6,609'	4-1/2"	10.5# K-55

B. FLOAT EQUIPMENT:

- 1. <u>SURFACE CASING:</u> 9-5/8" notched regular pattern guide shoe. Run (1) standard centralizer on each of the bottom (3) joints of Surface Casing.
- 2. <u>INTERMEDIATE CASING:</u> 7" cement nose guide shoe with a self-fill insert float. Place float collar one joint above the shoe. Install (1) Turbulent centralizer on each of the bottom (3) joints and one standard centralizer every (3) joints to 2,500 ft. Run (1) Turbulent centralizer at 2,700 ft., 2,500 ft., 2,300ft., 2,000ft., 1,500 ft., and 1,000 ft. (NTL-FRA 90-1).
- 3. <u>PRODUCTION CASING:</u> 4-1/2" & 5-1/2" whirler type cement nose guide shoe with a latch collar on top of 20' bottom joint. Place marker joint above 5,400'. Place centralizers as needed across selected production intervals.

IV. CEMENTING:

(Note: Volumes may be adjusted onsite due to actual conditions)

- 1. <u>SURFACE</u>: Slurry: <u>150sx</u> (205 cu.ft.) of "Type III" + 2% CaCl₂ + ¼ # of cello-flake/sk (Yield = 1.39 cu.ft./sk, Weight = 14.5 #/gal.). The 100% excess should circulate cement to the surface. WOC 12 hours. Test csg to 1500psi.
- 2. <u>INTERMEDIATE</u>: Lead 540 sx (1,121 cu.ft.) of "Type III" 65/35 poz with 8% gel, 1% CaCl₂ and 1/4# cello-flake/sk (Yield = 2.09 cu.ft./sk, Weight = 12.1 #/gal.). Tail 50 sx (70cu.ft.) of "Type III" with 1/4# cello-flake/sk, and 1% CaCl₂ (Yield = 1.4 cu.ft./sk, Weight = 14.5#/gal.). Use 100% excess in Lead Slurry to circulate to surface. No excess in Tail Slurry. Total volume = 1,191 cu.ft. Bump Plug to 1,500 psi. Notify engineering if cement is not circulated to surface.
- 3. PRODUCTION LINER: 10 bbl Gelled Water space. Lead: $50sx (130ft^3)$ of Premium Light HS + 1% FL-52 + .2% CD-32, 0.1% R-3, 3 #/sk CSE. (Yield = 2.59 cu.ft./sk, Weight = 11.6 #/gal.). Tail: $100 sx (215 ft^3)$ of Premium Light HS + 1% FL-52 + .2% CD-32, 0.1% R-3, 3 #/sk CSE, ½ #/sk cello flake and 4% Phenoseal. (Yield = 2.15 ft³/sk, Weight = 12.3 #/gal.). Displace cement at a minimum of 8 BPM. The 20% excess in lead and tail should cover 100 ft into intermediate casing. Total volume 322 ft³. WOC 12 hours

V. IV COMPLETION

A. CBL

1. Run Cement Bond Log across all intervals to be perforated and find Top of Cement behind all casing strings if cement is not circulated to surface.

B. PRESSURE TEST

1. Pressure test 7" & 4-1/2" casing to 3300# for 15 minutes.

C. STIMULATION

- 1. Perforate the Point Lookout as determined from the open hole logs.
- 2. Stimulate with approximately 9,300# of 14/30 LitePropTM sand in slick water.
- 3. Isolate Point Lookout with a CIBP.
- 4. Perforate the Menefee/Cliff House as determined from the open hole logs.
- 5. Stimulate with approximately 9,300# of 14/30 LiteProp[™] sand in slick water.
- 6. Test each zone before removing bridge plugs.

D. RUNNING TUBING

1. <u>Mesa Verde:</u> Run 2-3/8", 4.7#, J-55, EUE tubing with a SN (1.91" ID) on top of bottom joint. Land tubing approximately 25' above the bottom Point Lookout perforation.

Gary Sizemore

Sr. Drilling Engineer

Rosa #181B Dir Ops Plan.doc

Williams Production

HALLIBURTON

Sperry Drilling Services



Project: Rio Arriba Co. NM NAD 27 Site: Sec 11-T31N-R06W

> Well: Rosa Unit #181B Wellbore: Wellbore #1

Plan: Plan 032206 (Rosa Unit #181B/Wellbore #1)

	CASING E		
TVD	MD	Name	Size
3600.00	4197.26	7"	7

M Azimuths to True North Magnetic North: 10.45° Magnetic Field


Strength: 51423.5nT Dip Angle: 63.84° Date: 3/22/2006 Model: BGGM2005

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	
1511.70	44.47	270.00	1403.41	0.00	-410.18	4.00	270.00	410.18	
2714.98	44.47	270.00	2262.12	0.00-	1253.09	0.00	0.00	1253.09	
4197.26	0.00	0.00	3600.00	0.00-	1800.00	3.00	180.00	1800.00	7" Csg Pt RU #181B
6609.26	0.00	0.00	6012.00	0.00-	1800.00	0.00	0.00	1800.00	
	0.00 400.00 1511.70 2714.98 4197.26	0.00 0.00 400.00 0.00 1511.70 44.47 2714.98 44.47 4197.26 0.00	0.00 0.00 0.00 400.00 0.00 0.00 1511.70 44.47 270.00 2714.98 44.47 270.00 4197.26 0.00 0.00	0.00 0.00 0.00 0.00 400.00 0.00 0.00 400.00	0.00 0.00 0.00 0.00 400.00 0.00 0.00 400.00 0.00 1511.70 44.47 270.00 1403.41 0.00 2714.98 44.47 270.00 2262.12 0.00 4197.26 0.00 0.00 3600.00 0.00	$\begin{array}{cccccccccccccccccccccccccccccccccccc$	$\begin{array}{cccccccccccccccccccccccccccccccccccc$	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 400.00 0.00 0.00 400.00 0.00 0.00 0.00 0.00 0.00 1511.70 44.47 270.00 1403.41 0.00 -410.18 4.00 270.00 2714.98 44.47 270.00 2262.12 0.00-1253.09 0.00 0.00 4197.26 0.00 0.00 3600.00 0.00-1800.00 3.00 180.00	0.00 10.00 1

WELLBORE TARGET DETAILS (MAP CO-ORDINATES)

Name TVD +N/-S +E/-W Northing Easting Shape 7" Csg Pt RU #181B 3600.00 0.00 -1800.00 2152054.08 614488.72 Point



6000


Mancos Shale

0 1000 2 Vertical Section at 270.00° (1000 ft/in)

WELL DETAILS: Rosa Unit #181B

Ground Level: 6263.00

Northing Easting Latittude Longitude
2152061.59 616288.71 36° 54' 49.000 N 107° 26' 8.000 W



Plan: Plan 032206 (Rosa Unit #181B/Wellbore #1)

Approved:

 Created By: Dennis Cook
 Date: 3/18/2006

 Checked:
 Date:

 Reviewed:
 Date:

Date:

GENERAL ROSA DRILLING PLAN

Rosa Unit boundries:

T31N, R4W: all except sections 32-36 T31N, R5W: all except sections 1 & 2

T31N, R6W: all except sections 6,7,18,20, & 27-36

T32N, R6W: sections 32-36

FORMATION	LITHOLOGY	WATER	GAS	OIL/COND	OVER-PRES	LOST CIRC
Nacimiento	Interbedded shales, siltstones and sandstones	Possible	Possible	No	No	No
Ojo Alamo	Sandstone and conglomerates with lenses of shale	Fresh	No	No	No	No
Kirtland	Shale W/interbedded sandstones	No	Possible	No	No	No
	Inter, SS, SiltSt, SH &Coals w/carb, SS, SiltSt, SH	Yes	Yes	No	Possible	Possible
]	Massive Sandstone w/thin interbedded shales	Possible	Yes	Possible	No	Possible
	Shale w/thin interbedded sandstones and siltstones	No	Possible	No	No	No
Cliff House	Transgressive sandstones	Possible	Yes	No	No	No
Menefee	Sandstones, carb shales and coal	Possible	Yes	No	No	No
j.	Regressive coastal barrier sandstone	Possible	Yes	Possible	No	Yes
Mancos I	Marine shale and interbedded sandstone	No	Possible	Possible	No	Possible
Jpr Dadota	Marine sand and shales	No	Yes	Possible	No	Possible
.wr Dakota F	Fluvial sands, shales, & coal	Possible	Yes	Possible	No	Possible

DRILLING

Potential Hazards:

- 1. There are no overpressured zones expected in this well...
- 2. No H2S zones will be penetrated while drilling this well.

Mud System:

- Surface The surface hole will be drilled with a low-solids, non-dispersed system with starch and lost circulation material as needed. Expected mud weights will be in the 8.4 to 9.0 lb per gal range. Viscosities will be in the 30 to 60 sec/qrt range as needed to remove drill cuttings.
- 2. Intermediate The intermediate hole will be drilled with clear water and Benex to TD where the well will be mudded up to log and run casing. The mud system will be low-solids, non-dispersed with mud weights in the 9 to 10 lb per gal range as needed to control the well. Viscosities will be in the 45 to 55 range as needed to support any weight material. The weight material will consist of Barite.
- 3. Production The well will be drilled using air from the intermediate casing point to TD. For Fruitland Coal wells, the coal section will be drilled with air/mist.

....umans rroduction Company, LLC

Well Control Equipment Schematic for 2M Service

Attachment to Drilling Technical Program

Typical BOP setup

