

District I  
1625 N French Dr, Hobbs, NM 88240  
District II  
1301 W Grand Avenue, Artesia, NM 88210  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
District IV  
1220 S St Francis Dr, Santa Fe, NM 87505

State of New Mexico  
Energy Minerals and Natural Resources  
Department  
Oil Conservation Division  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-144  
July 21, 2008

**For temporary pits, closed-loop systems, and below-grade tanks,** submit to the appropriate NMOCD District Office.  
**For permanent pits and exceptions** submit to the Santa Fe Environmental Bureau office and provide a copy to the appropriate NMOCD District Office.

4566

Pit, Closed-Loop System, Below-Grade Tank, or  
Proposed Alternative Method Permit or Closure Plan Application

- Type of action: ☐ Permit of a pit, closed-loop system, below-grade tank, or proposed alternative method  
☒ Closure of a pit, closed-loop system, below-grade tank, or proposed alternative method  
☐ Modification to an existing permit  
☐ Closure plan only submitted for an existing permitted or non-permitted pit, closed-loop system, below-grade tank, or proposed alternative method

**Instructions: Please submit one application (Form C-144) per individual pit, closed-loop system, below-grade tank or alternative request**

Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.

1.  
Operator: XTO Energy Inc. OGRID #: 5380  
Address: #382 County Road 3100, Aztec, NM 87410  
Facility or well name: Irish #2 (Previously Irish #1E)  
API Number: 30-045-33743 OCD Permit Number: \_\_\_\_\_  
U/L or Qtr/Qtr K Section 22 Township 25N Range 10W County: San Juan  
Center of Proposed Design: Latitude 36.23008 N Longitude 107.53092 W NAD: ☐ 1927 ☒ 1983  
Surface Owner: ☐ Federal ☐ State ☐ Private ☒ Tribal Trust or Indian Allotment

2.  
☒ **Pit:** Subsection F or G of 19.15.17.11 NMAC  
Temporary: ☒ Drilling ☐ Workover  
☐ Permanent ☐ Emergency ☐ Cavitation ☐ P&A  
☒ Lined ☐ Unlined Liner type: Thickness 20 mil ☒ LLDPE ☐ HDPE ☐ PVC ☐ Other \_\_\_\_\_  
☐ String-Reinforced  
Liner Seams: ☐ Welded ☒ Factory ☐ Other \_\_\_\_\_ Volume: \_\_\_\_\_ bbl Dimensions: L 200 x W 60 x D 15

3.  
☐ **Closed-loop System:** Subsection H of 19.15.17.11 NMAC  
Type of Operation: ☐ P&A ☐ Drilling a new well ☐ Workover or Drilling (Applies to activities which require prior approval of a permit or notice of intent)  
☐ Drying Pad ☐ Above Ground Steel Tanks ☐ Haul-off Bins ☐ Other \_\_\_\_\_  
☐ Lined ☐ Unlined Liner type: Thickness \_\_\_\_\_ mil ☐ LLDPE ☐ HDPE ☐ PVC ☐ Other \_\_\_\_\_  
Liner Seams: ☐ Welded ☐ Factory ☐ Other \_\_\_\_\_

4.  
☐ **Below-grade tank:** Subsection I of 19.15.17.11 NMAC  
Volume: \_\_\_\_\_ bbl Type of fluid: \_\_\_\_\_  
Tank Construction material: \_\_\_\_\_  
☐ Secondary containment with leak detection ☐ Visible sidewalls, liner, 6-inch lift and automatic overflow shut-off  
☐ Visible sidewalls and liner ☐ Visible sidewalls only ☐ Other \_\_\_\_\_  
Liner type: Thickness \_\_\_\_\_ mil ☐ HDPE ☐ PVC ☐ Other \_\_\_\_\_

5.  
☐ **Alternative Method:**  
Submittal of an exception request is required. Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

6.  
**Fencing:** Subsection D of 19.15.17.11 NMAC (*Applies to permanent pits, temporary pits, and below-grade tanks*).  
☐ Chain link, six feet in height, two strands of barbed wire at top (*Required if located within 1000 feet of a permanent residence, school, hospital, institution or church*)  
☒ Four foot height, four strands of barbed wire evenly spaced between one and four feet  
☐ Alternate. Please specify \_\_\_\_\_

7.  
**Netting:** Subsection E of 19.15.17.11 NMAC (*Applies to permanent pits and permanent open top tanks*)  
☐ Screen ☐ Netting ☐ Other \_\_\_\_\_  
☐ Monthly inspections (If netting or screening is not physically feasible)

8.  
**Signs:** Subsection C of 19.15.17.11 NMAC  
☐ 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers  
☒ Signed in compliance with 19.15.3.103 NMAC

9.  
**Administrative Approvals and Exceptions:**  
Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance.  
**Please check a box if one or more of the following is requested, if not leave blank:**  
☐ Administrative approval(s): Requests must be submitted to the appropriate division district or the Santa Fe Environmental Bureau office for consideration of approval.  
☐ Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

10.  
**Siting Criteria (regarding permitting):** 19.15.17.10 NMAC  
*Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria may require administrative approval from the appropriate district office or may be considered an exception which must be submitted to the Santa Fe Environmental Bureau office for consideration of approval. Applicant must attach justification for request. Please refer to 19.15.17.10 NMAC for guidance. Siting criteria does not apply to drying pads or above-grade tanks associated with a closed-loop system.*

Ground water is less than 50 feet below the bottom of the temporary pit, permanent pit, or below-grade tank. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. ( <i>Applies to temporary, emergency, or cavitation pits and below-grade tanks</i> ) - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA
Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. ( <i>Applies to permanent pits</i> ) - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA
Within 500 horizontal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. - Written confirmation or verification from the municipality; Written approval obtained from the municipality	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within 500 feet of a wetland. - US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within the area overlying a subsurface mine. - Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within an unstable area. - Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within a 100-year floodplain. - FEMA map	<input type="checkbox"/> Yes <input type="checkbox"/> No

11.  
**Temporary Pits, Emergency Pits, and Below-grade Tanks Permit Application Attachment Checklist:** Subsection B of 19.15.17.9 NMAC  
*Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.*

☐ Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC  
☐ Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 NMAC  
☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC  
☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC  
☐ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

☐ Previously Approved Design (attach copy of design)    API Number: \_\_\_\_\_ or Permit Number: \_\_\_\_\_

12.  
**Closed-loop Systems Permit Application Attachment Checklist:** Subsection B of 19.15.17.9 NMAC  
*Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.*

☐ Geologic and Hydrogeologic Data (only for on-site closure) - based upon the requirements of Paragraph (3) of Subsection B of 19.15.17.9  
☐ Siting Criteria Compliance Demonstrations (only for on-site closure) - based upon the appropriate requirements of 19.15.17.10 NMAC  
☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC  
☐ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

☐ Previously Approved Design (attach copy of design)    API Number: \_\_\_\_\_  
☐ Previously Approved Operating and Maintenance Plan    API Number: \_\_\_\_\_ (Applies only to closed-loop system that use above ground steel tanks or haul-off bins and propose to implement waste removal for closure)

13.  
**Permanent Pits Permit Application Checklist:** Subsection B of 19.15.17.9 NMAC  
*Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.*

☐ Hydrogeologic Report - based upon the requirements of Paragraph (1) of Subsection B of 19.15.17.9 NMAC  
☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC  
☐ Climatological Factors Assessment  
☐ Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Dike Protection and Structural Integrity Design - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Quality Control/Quality Assurance Construction and Installation Plan  
☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC  
☐ Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Nuisance or Hazardous Odors, including H<sub>2</sub>S, Prevention Plan  
☐ Emergency Response Plan  
☐ Oil Field Waste Stream Characterization  
☐ Monitoring and Inspection Plan  
☐ Erosion Control Plan  
☐ Closure Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

14.  
**Proposed Closure:** 19.15.17.13 NMAC  
*Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan.*

Type: ☒ Drilling   ☐ Workover   ☐ Emergency   ☐ Cavitation   ☐ P&A   ☐ Permanent Pit   ☐ Below-grade Tank   ☐ Closed-loop System  
☐ Alternative

Proposed Closure Method: ☐ Waste Excavation and Removal  
☐ Waste Removal (Closed-loop systems only)  
☒ On-site Closure Method (Only for temporary pits and closed-loop systems)  
☒ In-place Burial   ☐ On-site Trench Burial  
☐ Alternative Closure Method (Exceptions must be submitted to the Santa Fe Environmental Bureau for consideration)

15.  
**Waste Excavation and Removal Closure Plan Checklist:** (19.15.17.13 NMAC) *Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.*

☐ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC  
☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC  
☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings)  
☐ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC  
☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC  
☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC

16.

**Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:** (19.15.17.13.D NMAC)

*Instructions: Please indentify the facility or facilities for the disposal of liquids, drilling fluids and drill cuttings. Use attachment if more than two facilities are required.*

Disposal Facility Name: \_\_\_\_\_ Disposal Facility Permit Number: \_\_\_\_\_

Disposal Facility Name: \_\_\_\_\_ Disposal Facility Permit Number: \_\_\_\_\_

Will any of the proposed closed-loop system operations and associated activities occur on or in areas that *will not* be used for future service and operations?

☐ Yes (If yes, please provide the information below) ☐ No

*Required for impacted areas which will not be used for future service and operations:*

☐ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC

☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC

17.

**Siting Criteria (regarding on-site closure methods only):** 19.15.17.10 NMAC

*Instructions: Each siting criteria requires a demonstration of compliance in the closure plan. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria may require administrative approval from the appropriate district office or may be considered an exception which must be submitted to the Santa Fe Environmental Bureau office for consideration of approval. Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17.10 NMAC for guidance.*

Ground water is less than 50 feet below the bottom of the buried waste.

- NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells

☐ Yes ☒ No  
☐ NA

Ground water is between 50 and 100 feet below the bottom of the buried waste

- NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells

☒ Yes ☐ No  
☐ NA

Ground water is more than 100 feet below the bottom of the buried waste.

- NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells

☐ Yes ☒ No  
☐ NA

Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☒ No

Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☒ No

Within 500 horizontal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application.

- NM Office of the State Engineer - iWATERS database; Visual inspection (certification) of the proposed site

☐ Yes ☒ No

Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended.

- Written confirmation or verification from the municipality; Written approval obtained from the municipality

☐ Yes ☒ No

Within 500 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☒ No

Within the area overlying a subsurface mine.

- Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division

☐ Yes ☒ No

Within an unstable area.

- Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map

☐ Yes ☒ No

Within a 100-year floodplain.

- FEMA map

☐ Yes ☒ No

18.

**On-Site Closure Plan Checklist:** (19.15.17.13 NMAC) *Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.*

☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC

☐ Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC

☐ Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of 19.15.17.11 NMAC

☐ Construction/Design Plan of Temporary Pit (for in-place burial of a drying pad) - based upon the appropriate requirements of 19.15.17.11 NMAC

☐ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC

☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC

☐ Waste Material Sampling Plan - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC

☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings or in case on-site closure standards cannot be achieved)

☐ Soil Cover Design - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC

☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC

19.

**Operator Application Certification:**

I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.

Name (Print): \_\_\_\_\_ Title: \_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

e-mail address: \_\_\_\_\_ Telephone: \_\_\_\_\_

20.

**OCD Approval:** ☐ Permit Application (including closure plan) ☐ Closure Plan (only) ☐ OCD Conditions (see attachment)

**OCD Representative Signature:** \_\_\_\_\_ **Approval Date:** \_\_\_\_\_

**Title:** \_\_\_\_\_ **OCD Permit Number:** \_\_\_\_\_

21.

**Closure Report (required within 60 days of closure completion):** Subsection K of 19.15.17.13 NMAC

*Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.*

☒ **Closure Completion Date:** March 17, 2009

22.

**Closure Method:**

☐ Waste Excavation and Removal ☒ On-Site Closure Method ☐ Alternative Closure Method ☐ Waste Removal (Closed-loop systems only)  
☐ If different from approved plan, please explain.

23.

**Closure Report Regarding Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:**

*Instructions: Please identify the facility or facilities for where the liquids, drilling fluids and drill cuttings were disposed. Use attachment if more than two facilities were utilized.*

Disposal Facility Name: \_\_\_\_\_ Disposal Facility Permit Number: \_\_\_\_\_

Disposal Facility Name: \_\_\_\_\_ Disposal Facility Permit Number: \_\_\_\_\_

Were the closed-loop system operations and associated activities performed on or in areas that *will not* be used for future service and operations?

☐ Yes (If yes, please demonstrate compliance to the items below) ☐ No

*Required for impacted areas which will not be used for future service and operations:*

- ☐ Site Reclamation (Photo Documentation)  
☐ Soil Backfilling and Cover Installation  
☐ Re-vegetation Application Rates and Seeding Technique

24.

**Closure Report Attachment Checklist:** *Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check mark in the box, that the documents are attached.*

- ☒ Proof of Closure Notice (surface owner and division)  
☐ Proof of Deed Notice (required for on-site closure)  
☒ Plot Plan (for on-site closures and temporary pits)  
☐ Confirmation Sampling Analytical Results (if applicable)  
☒ Waste Material Sampling Analytical Results (required for on-site closure)  
☒ Disposal Facility Name and Permit Number  
☒ Soil Backfilling and Cover Installation  
☒ Re-vegetation Application Rates and Seeding Technique  
☒ Site Reclamation (Photo Documentation)

On-site Closure Location: Latitude \_\_\_\_\_ Longitude \_\_\_\_\_ NAD: ☐ 1927 ☐ 1983

25.

**Operator Closure Certification:**

I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.

Name (Print): Kim Champlin Title: EH&S Administrative Coordinator

Signature: *Kim Champlin* Date: 12/09/2009

e-mail address: kim\_champlin@xtoenergy.com Telephone: (505) 333-3100

*Approved Brandon Powell NMOC 1/5/09*

# **XTO Energy Inc. San Juan Basin Closure Report**

**Lease Name: Irish #2**

**API No.: 30-045-33743**

**Description: Sec. 22K-T25N-R10W**

**Note: Well and pit were originally permitted as Irish #1E. BLM Form 3160-5 reflecting the name change to Irish #2 is included in this report.**

In accordance with Rule 19.15.17.13 NMAC the following information describes the closure of the temporary pit referenced above. All proper documentation regarding closure activities is being included with the C-144.

- Proof of Closure Notice
  - Proof of Deed Notice (Not Required)
  - Plot Plan
  - C-105
  - Sampling Results
  - Details on Soil Backfilling and Cover Installation
  - Re-vegetation Application Rates and Seeding Technique
  - Site Reclamation Photos (Including Steel Marker)
1. All free standing liquids will be removed at the start of the pit closure process from the pit and disposed of in a division-approved facility or recycled, reused, or reclaimed in a manner that the Aztec Division office approves.  
**Cuttings were run through a centrifuge unit operated by Patriot to remove fluids August 4 through August 7, 2008 and fluids were disposed of at Basin Disposal NM01-005.**
  2. The preferred method of closure for all temporary pits will be on-site, in-place burial, assuming that all criteria listed in Subsection (B) of 19.15.17.13 are met.  
**On-site, in-place burial plan for this location was approved by the Aztec Division office on August 26, 2008.**
  3. The surface owner shall be notified of XTO proposed closure plan using a means that provides proof of notice, i.e., Certified Mail, return receipt requested.  
**The surface owner was notified of XTO's proposed closure plan via email on August 15, 2008 and of on-site burial by certified mail, return receipt requested, December 8, 2008 (attached).**
  4. Within 6 months of Rig Off status occurring XTO will ensure that temporary pits are closed, re-contoured, and reseeded.  
**Rig moved off location July 26, 2008. Pit closed March 17, 2009. Area seeded April 8, 2009 (beginning of first growing season after closure).**
  5. Notice of Closure will be given to the Aztec Division office between 72 hours and one week of closure via email, or verbally. The notification of closure will include the following:
    - i. Operator's Name
    - ii. Well Name and API Number
    - iii. Location by Unit Letter, Section. Township, Range

Notice was given to OCD by XTO within the specified time period (December 3, 2008, attached). Closure activity began December 8, 2008.

6. Pit contents shall be mixed with non-waste containing, earthen material in order to achieve appropriate solidification. The solidification process will be accomplished using a combination of natural drying and mechanically mixing. Pit contents will be mixed with non-waste, earthen material to a consistency that is deemed as safe and stable. The mixing ratio shall not exceed 3 parts clean soil to 1 part pit contents.

**Pit contents were mixed with non-waste containing, earthen material in order to achieve appropriate solidification. The solidification process was accomplished using a combination of natural drying and mechanically mixing using a dozer and trachoe. Pit contents were mixed with non-waste, earthen material to a consistency that was deemed safe and stable. Approximately 1580 cubic yards of sandylome earthen material from the location was added to pit contents of 790 cubic yards. The mixing ratio did not exceed 3 parts clean soil to 1 part pit contents. Solidification was completed February 21, 2009.**

7. Liner of temporary pit shall be removed above "mud level" after stabilization. Removal of liner will consist of manually or mechanically cutting liner at mud level and removing all remaining liner. Care will be taken to remove "ALL" of the liner i.e., edges of liner entrenched or buried. All excessive liner will be disposed of at a licensed disposal facility.

**Liner of temporary pit was removed above "mud level" after stabilization. Removal of the liner consisted of manually cutting liner at mud level and removing all remaining liner. Care was taken to remove "ALL" of the liner i.e., edges of liner entrenched or buried. All excessive liner was disposed of at a licensed disposal facility, (San Juan County Landfill).**

8. A five point composite sample will be taken using sampling tools and all samples tested per Subsection B of 19.15.17.13(B)(1)(b). In the event that the criteria are not met, all contents will be handled per Subparagraph (a) of Paragraph (1) of Subsection B of 19.15.17.13 i.e. dig and haul. Disposal facilities to be utilized should this method be required will be Envirotech, Permit No. NM01-0011 or IEI, Permit No. NM01-0010B

**A five point composite sample was taken of the pit using sampling tools and all samples tested per Subsection B of 19.15.17.1 3(B)( 1 )(b). (Sample results attached).**

Components	Test Method	Limit (mg/Kg)	Results
Benzene	EPA SW-846 8021B or 8260B	0.2	ND
BTEX	EPA SW-846 8021B or 8260B	50	ND
TPH	EPA SW-846 418.1	2500	72
GRO/DRO	EPA SW-846 8015M	500	130
Chlorides	EPA 300.1	1000 or background	14* (Resample)

9. Upon completion of solidification and testing, the pit area will be backfilled with compacted, non-waste containing earthen material. A minimum of four feet of cover shall be achieved and the cover shall include one foot of suitable material to establish vegetation at the site, or the background thickness of topsoil, whichever is greater.

**Upon completion of solidification and testing, the pit area was backfilled with compacted, non-waste containing, earthen material. A minimum of four feet of cover was achieved and the cover included just over one foot of background topsoil suitable for establishing vegetation at the site. Backfill and cover were placed to match existing grade.**

10. Re-contouring of the location will match fit, shape, line, form and texture of the surrounding area. Re-shaping will include drainage control, ponding prevention, and erosion prevention. Natural drainages will be unimpeded and water bars and/or silt traps will be placed in areas where needed to prevent erosion on a large scale. Final re-contour shall have a uniform appearance with a smooth surface, fitting the natural landscape.

**Re-contouring of location matches fit, shape, line, form and texture of the surrounding area. Re-shaping of the location included drainage control, ponding prevention, and erosion prevention. Natural drainages were unimpeded and water bars and/or silt traps were placed**

**in areas where needed to prevent erosion on a large scale. Final re-contour has a uniform appearance with smooth surface, fitting the natural landscape and was completed March 17, 2009.**

11. Notification will be sent to OCD when the reclaimed area is seeded.

**Notification via C-103 is included in this report. Seeding date was April 8, 2009.**

12. XTO shall seed the disturbed areas the first growing season after the pit is closed. Seeding will be accomplished via drilling on the contour whenever practical or by other division-approved methods. BLM of Forest Service stipulated seed mixes will be used on Federal Lands. Vegetative cover will equal 70% of the native perennial vegetative cover (un-impacted) consisting of at least three native plant species, including at least one grass, but not including noxious weeds, and maintain that cover through two successive growing seasons. Repeat seeding or planting will be continued until successful vegetative growth occurs.

**Notification via C-103 will be sent to OCD when the reclaimed area successfully achieves re-vegetation for two successive growing seasons.**

13. The temporary pit will be located with a steel marker, no less than four inches in diameter, cemented in a hole three feet deep in the center of the on-site burial upon the abandonment of all the wells on the pad. The marker will be flush with the ground to allow access of the active well pad and for safety concerns. The marker will include a threaded collar to be used for future abandonment. The top of the marker will contain a welded steel 12" square plate that indicates the onsite burial of the temporary pit. The plate will be easily removable and a four foot riser will be threaded into the top of the collar marker and welded around the base with the operator's information at the time all wells on the pad are abandoned. The operator's information will include the following: Operator's Name, Lease Name, Well Name and Number, Unit Number, Section, Township, Range and an indicator that the marker is an on-site burial location.

**The temporary pit has been located with a steel marker, no less than four inches in diameter, cemented in a hole three feet deep in the center of the onsite burial upon the abandonment of all the wells on the pad. The marker includes a four foot tall riser welded around the base with the operator's information. The riser will be set in a way to not impede reclamation activities. The operator's information includes the following: XTO Energy, Irish #2, 22K-T25N-R10W "Pit Burial".**

14. XTO shall file a deed notice identifying the exact location of the on-site burial with the county clerk in the county where the on-site burial occurs.

**Not required on state, federal, or tribal land according to FAQ dated October 30, 2008 and posted on the OCD website.**



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0137  
Expires: March 31, 2007

**SUNDRY NOTICES AND REPORTS ON WELLS** **14 2008**

*Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.*

5. Lease Serial No  
**N0-G-0503-1729**

6. If Indian, Allottee or Tribe Name  
**NAVAJO ALLOTMENT**

7. If Unit or CA/Agreement, Name and/or No  
**N/A**

8. Well Name and No  
**IRISH #1E chg to IRISH #2**

9. API Well No.  
**30-045-33743**

10. Field and Pool, or Exploratory Area  
**BASIN DAKOTA**

11. County or Parish, State  
**SAN JUAN, NM**

**SUBMIT IN TRIPLICATE- Other instructions on reverse side.**

1. Type of Well  
☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator  
**XTO Energy, Inc.**

3a. Address  
**382 CR 3100 AZTEC, NM 87410**

3b. Phone No (include area code)  
**505-333-3100**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
**1550' FSL X 1900' FWL in Sec 22, T25N, R10W**

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <b>CHG DEDICATION</b>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	<b>&amp; WELL NAME</b>
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

XTO would like to change the dedication of this well from a W/2 standup to a S/2 laydown and change the name back to the Irish #2.  
See attached revised C102.

New Name: IRISH #2

RCVD OCT 22 '08  
OIL CONS. DIV.  
DIST. 3

14. I hereby certify that the foregoing is true and correct  
Name (Printed/Typed)  
**Kyla Vaughan**

Title **Regulatory Analyst**

Signature *Kyla Vaughan* Date **10/10/2008**

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by *Wayne Townsend* Title **Reg. Eng.** Date **10/17/08**

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office **FFO**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

NMOCDB

Submit To Appropriate District Office Two Copies <b>District I</b> 1625 N French Dr., Hobbs, NM 88240 <b>District II</b> 1301 W. Grand Avenue, Artesia, NM 88210 <b>District III</b> 1000 Rio Brazos Rd., Aztec, NM 87410 <b>District IV</b> 1220 S. St. Francis Dr., Santa Fe, NM 87505	<b>State of New Mexico</b> <b>Energy, Minerals and Natural Resources</b>  <b>Oil Conservation Division</b> <b>1220 South St. Francis Dr.</b> <b>Santa Fe, NM 87505</b>	<b>Form C-105</b> <b>July 17, 2008</b>  <b>1. WELL API NO.</b> 30-045-33743  <b>2. Type of Lease</b> <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/> FED/INDIAN  <b>3. State Oil &amp; Gas Lease No</b>								
<b>WELL COMPLETION OR RECOMPLETION REPORT AND LOG</b>										
<b>4. Reason for filing:</b> <input type="checkbox"/> <b>COMPLETION REPORT</b> (Fill in boxes #1 through #31 for State and Fee wells only) <input checked="" type="checkbox"/> <b>C-144 CLOSURE ATTACHMENT</b> (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)		<b>5. Lease Name or Unit Agreement Name</b> Irish  <b>6. Well Number</b> #2								
<b>7. Type of Completion:</b> <input checked="" type="checkbox"/> <b>NEW WELL</b> <input type="checkbox"/> <b>WORKOVER</b> <input type="checkbox"/> <b>DEEPENING</b> <input type="checkbox"/> <b>PLUGBACK</b> <input type="checkbox"/> <b>DIFFERENT RESERVOIR</b> <input type="checkbox"/> <b>OTHER</b>		<b>9. OGRID</b> 5380								
<b>8. Name of Operator</b> XTO Energy Inc.		<b>11. Pool name or Wildcat</b>								
<b>10. Address of Operator</b> 382 County Road 3100 Aztec, NM 87410										
<b>12. Location</b>	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County
<b>Surface:</b>	K	22	25N	10W		1550	S	1900	W	San Juan
<b>BH:</b>										
<b>13. Date Spudded</b>	<b>14. Date T.D. Reached</b>	<b>15. Date Rig Released</b>		<b>16. Date Completed (Ready to Produce)</b>		<b>17. Elevations (DF and RKB; RT, GR, etc.)</b>				
07/16/2008	07/23/2008	07/26/2008		11/10/2008						
<b>18. Total Measured Depth of Well</b>		<b>19. Plug Back Measured Depth</b>		<b>20. Was Directional Survey Made?</b>			<b>21. Type Electric and Other Logs Run</b>			
<b>22. Producing Interval(s), of this completion - Top, Bottom, Name</b>										
<b>23. CASING RECORD (Report all strings set in well)</b>										
CASING SIZE	WEIGHT LB/FT	DEPTH SET	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED					
<b>24. LINER RECORD</b>						<b>25. TUBING RECORD</b>				
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN	SIZE	DEPTH SET	PACKER SET			
<b>26. Perforation record (interval, size, and number)</b>					<b>27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC.</b>					
					DEPTH INTERVAL					
					AMOUNT AND KIND MATERIAL USED					
<b>28. PRODUCTION</b>										
<b>Date First Production</b>		<b>Production Method (Flowing, gas lift, pumping - Size and type pump)</b>				<b>Well Status (Prod. or Shut-in)</b>				
<b>Date of Test</b>	<b>Hours Tested</b>	<b>Choke Size</b>	<b>Prod'n For Test Period</b>	<b>Oil - Bbl</b>	<b>Gas - MCF</b>	<b>Water - Bbl</b>	<b>Gas - Oil Ratio</b>			
<b>Flow Tubing Press.</b>	<b>Casing Pressure</b>	<b>Calculated 24-Hour Rate</b>	<b>Oil - Bbl</b>	<b>Gas - MCF</b>	<b>Water - Bbl</b>	<b>Oil Gravity - API - (Corr.)</b>				
<b>29. Disposition of Gas (Sold, used for fuel, vented, etc.)</b>						<b>30. Test Witnessed By</b>				
<b>31. List Attachments</b>										
<b>32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.</b>										
<b>33. If an on-site burial was used at the well, report the exact location of the on-site burial.</b>										
Latitude 36.40605      Longitude 107.75176      NAD 1927 <span style="border: 1px solid black; padding: 0 2px;">1983</span>										
I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief										
<b>Signature</b> <i>Kim Champlin</i>		<b>Printed Name</b> Kim Champlin		<b>Title</b> EH&S Administrative Mgr.			<b>Date</b> 12/10/2009			
<b>E-mail Address</b> kim_champlin@xtoenergy.com										

DISTRICT I  
1625 N. French Dr., Hobbs, N.M. 88240

DISTRICT II  
1301 W. Grand Ave., Artesia, N.M. 88210

DISTRICT III  
1000 Rio Brazos Rd., Aztec, N.M. 87410

DISTRICT IV  
1220 South St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION

1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-102

Revised October 12, 2005

Submit to Appropriate District Office

State Lease - 4 Copies

Fee Lease - 3 Copies

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

1 API Number 30-045-33743		2 Pool Code 71599		3 Pool Name DAKOTA	
4 Property Code 3S976		5 Property Name IRISH			6 Well Number 2
7 OGRID No 5380		8 Operator Name XTO ENERGY INC			9 Elevation 6602

10 Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
K	22	25-N	10-W		1550	SOUTH	1900	WEST	SAN JUAN

11 Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County


12 Dedicated Acres 5 2320		13 Joint or Infill		14 Consolidation Code		15 Order No	
------------------------------	--	--------------------	--	-----------------------	--	-------------	--

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED  
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

16

XTO ENERGY INC.  
 IRISH No. 1E 21550' FSL 1900' FWL  
 SECTION 22, T25N, R10W, N.M.P.M., SAN JUAN COUNTY, N. M.  
 GROUND ELEVATION: 6602', DATE: SEPTEMBER 26, 2005

LAT. = 36°23'00.8" N.  
 LONG. = 107°53'09.2" W  
 NAD 27



AREA OF DISTURBANCE:  
 PAD = 255' x 290' = 1.7 ACRES  
 CONSTRUCTION ZONE 985' x 50' = 1.1 ACRES  
 TOTAL DISTURBANCE = 2.8 ACRES

NOTE: DAGGETT ENTERPRISES, INC. IS NOT LIABLE FOR UNDERGROUND UTILITIES OR PIPELINES. NEW MEXICO ONE CALL TO BE NOTIFIED 48 HOURS PRIOR TO EXCAVATION OR CONSTRUCTION.

CONTRACTOR SHOULD CALL ONE-CALL FOR LOCATION OF ANY MARKED OR UNMARKED BURIED PIPELINES OR CABLES ON WELL PAD AND OR ACCESS ROAD AT LEAST TWO (2) WORKING DAYS PRIOR TO CONSTRUCTION.

Exhibit E

Daggett Enterprises, Inc.	
Surveying and Oil Field Services	
P. O. Box 15068 • Farmington, NM 87401	
Phone (505) 326-1772 • Fax (505) 326-8019	
NEW MEXICO P.L.S. No. 14831	
DRAWN BY: A.E.	CHECKED: CHAS/PLS
DATE: 01/15/03	DATE: 12/15/05




# XTO ENERGY INC.

IRISH No. ~~TE~~ 21550 FSL 1900 FWL

SECTION 22, T-25-N, R-10-W, N.M.P.M., SAN JUAN COUNTY, NEW MEXICO

GROUND ELEVATION: 6602, DATE: SEPTEMBER 26, 2005


LATITUDE: 36°23'00.8" N (NAD 27) LONGITUDE: 107°53'09.2" W (NAD 27)



NOTE: DAGGETT ENTERPRISES, INC. IS NOT LIABLE FOR UNDERGROUND UTILITIES OR PIPELINES. NEW MEXICO ONE CALL TO BE NOTIFIED 48 HOURS PRIOR TO EXCAVATION OR CONSTRUCTION.

CONTRACTOR SHOULD CALL ONE-CALL FOR LOCATION OF ANY MARKED OR UNMARKED BURIED PIPELINES OR CABLES ON WELL PAD AND OR ACCESS ROAD AT LEAST TWO (2) WORKING DAYS PRIOR TO CONSTRUCTION.

Exhibit E

REVISION		DATE	REVISION BY
		<b>Daggett Enterprises, Inc.</b> Surveying and Oil Field Services P. O. Box 15068 • Farmington, NM 87401 Phone (505) 326-1772 • Fax (505) 326-8019 NEW MEXICO L.S. 14831	
		DRAWN BY: A.G. NAME: CR463	CHECKED BY: CR463 DATE: 12/15/05



Kim Champlin/FAR/CTOC

08/15/2008 09:32 AM

To arvintrujillo@frontiernet.net

cc kim\_champlin@xtoenergy.com

bcc

Subject Notice- Irish #1E Well Site

RE: Irish #1E Gas Well API #30-045-33743  
Sec 22K- T25N- R10W, San Juan County

Dear Mr Trujillo:

This submittal is pursuant to Rule 19.15.17.13 requiring operators to notify surface owners of on site burial of temporary pits. XTO Energy Inc. (XTO) is hereby providing written documentation of our intention to close the temporary pit associated with the aforementioned location by means of in place on site burial.

Should you have any questions or require additional information please feel free to contact me at your earliest convenience (505) 333-3100

Kim Champlin  
Environmental Representative  
XTO Energy  
San Juan Division  
(505) 333-3207 Office  
(505) 330-8357 Cell  
(505) 333-3280 Fax



December 8, 2008

Arvin Trujillo  
Navajo Nation  
PO Box 9000  
Window Rock, AZ 86515

Regarding: Irish #2 (Originally #1E) Gas Well API #30-045-33743  
Sec. 22K- T25N- R10W, San Juan County

Dear Mr. Trujillo,

Pursuant to NMAC Rule 19.15.17.13 requiring operators to notify surface owners of on site burial of temporary pits, XTO Energy Inc. (XTO) is hereby providing written documentation of closure of the temporary pit associated with the aforementioned location by means of in place on site burial. This temporary pit was closed in accordance to NMAC Rule 19.15.17.13.

Should you require any further information feel free to contact me at (505) 333-3100.

Respectfully submitted,

A handwritten signature in cursive script that reads 'Kim Champlin'.

Kim Champlin  
Sr. Environmental Representative  
XTO Energy Inc.  
San Juan Division


Cc: OCD  
File

7004 2510 0005 9631 4605

U.S. Postal Service  
**CERTIFIED MAIL<sup>TM</sup> RECEIPT**  
(Domestic Mail Only, No Insurance Coverage Provided)

For delivery information visit our website at [www.usps.com](http://www.usps.com)  
**OFFICIAL USE**

Postage	\$
Certified Fee	
Return Receipt Fee (Endorsement Required)	
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$



Sent To  
*Arren Trujillo Navajo Nation*  
Street, Apt. No.,  
or PO Box No. *P.O. Box 9000*  
City, State, ZIP+4<sup>®</sup>  
*Window Rock, AZ 86515*

SENDER: COM PS Form 3800, June 2002 See Reverse for Instructions VERY

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:  
*Arren Trujillo*  
*Navajo Nation*  
*P.O. Box 9000*  
*Window Rock, AZ 86515*  
*Irish #2*

A. Signature  
☒ *Dora Long* ☐ Agent  
☐ Addressee

B. Received by (Printed Name)  
*DORA LONG*

C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes  
If YES, enter delivery address below: ☐ No

3. Service Type  
☐ Certified Mail ☒ ~~SP~~ Express Mail  
☐ Registered ☐ Return Receipt for Merchandise  
☐ Insured Mail ☐ C.O.D.

4. Restricted Delivery? (Extra Fee) ☐ Yes

2. Article Number (Transfer from service label) 7004 2510 0005 9631 4605





"Rosenbaum Construction  
Co., Inc."  
<rosenbaumconstruction@ms  
n.com>

12/03/2008 11:08 AM

To "Brandon.Powell" <Brandon.Powell@state.nm.us>

cc "Kim\_Champlin" <Kim\_Champlin@xtoenergy.com>,  
"Tony\_Sternberger" <Tony\_Sternberger@xtoenergy.com>

bcc

Subject 72 HR NOTICE

BRANDON,

THIS IS OUR 72 HOUR NOTICE TO SOLIDIFY/MIX ON THE XTO LOCATION - IRISH 1E  
TOWNSHIP 25N, RANGE 10W, SECTION 22, QUARTER SECTION - K - NE/SW  
SAN JUAN COUNTY

THANKS,  
STEPHANNE COATS  
ROSENBAUM CONSTRUCTION  
505-325-6367



## COVER LETTER

Wednesday, October 15, 2008

Martin Nee  
XTO Energy  
382 County Road 3100  
Aztec, NM 87410  
TEL: (505) 333-3100  
FAX (505) 333-3280  
RE: Reserve Pit Samples

Order No.: 0810029

Dear Martin Nee:

Hall Environmental Analysis Laboratory, Inc. received 1 sample(s) on 10/2/2008 for the analyses presented in the following report.

These were analyzed according to EPA procedures or equivalent.

Reporting limits are determined by EPA methodology. No determination of compounds below these (denoted by the ND or < sign) has been made.

Please don't hesitate to contact HEAL for any additional information or clarifications.

Sincerely,

A handwritten signature in black ink, appearing to read "Andy Freeman", is written over a horizontal line.

Andy Freeman, Business Manager  
Nancy McDuffie, Laboratory Manager

NM Lab # NM9425  
AZ license # AZ0682  
ORELAP Lab # NM100001  
Texas Lab# T104704424-08-TX



4901 Hawkins NE ■ Suite D ■ Albuquerque, NM 87109  
505.345.3975 ■ Fax 505.345.4107  
[www.hallenvironmental.com](http://www.hallenvironmental.com)

**Hall Environmental Analysis Laboratory, Inc.**

Date: 15-Oct-08

**CLIENT:** XTO Energy  
**Lab Order:** 0810029  
**Project:** Reserve Pit Samples  
**Lab ID:** 0810029-01

**Client Sample ID:** Irish #1E Reserve Pit  
**Collection Date:** 9/29/2008 3:00:00 PM  
**Date Received:** 10/2/2008  
**Matrix:** SOIL

Analyses	Result	PQL	Qual	Units	DF	Date Analyzed
<b>EPA METHOD 8015B: DIESEL RANGE ORGANICS</b>						Analyst: SCC
Diesel Range Organics (DRO)	130	10		mg/Kg	1	10/7/2008
Motor Oil Range Organics (MRO)	170	50		mg/Kg	1	10/7/2008
Surr: DNOP	98.3	61.7-135		%REC	1	10/7/2008
<b>EPA METHOD 8015B: GASOLINE RANGE</b>						Analyst: DAM
Gasoline Range Organics (GRO)	ND	50		mg/Kg	10	10/12/2008 6:49:31 AM
Surr: BFB	88.6	58.8-123		%REC	10	10/12/2008 6:49:31 AM
<b>EPA METHOD 8021B: VOLATILES</b>						Analyst: DAM
Benzene	ND	0.50		mg/Kg	10	10/12/2008 6:49:31 AM
Toluene	ND	0.50		mg/Kg	10	10/12/2008 6:49:31 AM
Ethylbenzene	ND	0.50		mg/Kg	10	10/12/2008 6:49:31 AM
Xylenes, Total	ND	1.0		mg/Kg	10	10/12/2008 6:49:31 AM
Surr: 4-Bromofluorobenzene	96.8	66.8-139		%REC	10	10/12/2008 6:49:31 AM
<b>EPA METHOD 300.0: ANIONS</b>						Analyst: SLB
Chloride	1300	6.0		mg/Kg	20	10/9/2008 7:32:03 PM
<b>EPA METHOD 418.1: TPH</b>						Analyst: LRW
Petroleum Hydrocarbons, TR	72	20		mg/Kg	1	10/6/2008

**Qualifiers:**

- \* Value exceeds Maximum Contaminant Level
- E Value above quantitation range
- J Analyte detected below quantitation limits
- ND Not Detected at the Reporting Limit
- S Spike recovery outside accepted recovery limits

- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- MCL Maximum Contaminant Level
- RL Reporting Limit

## QA/QC SUMMARY REPORT

Client: XTO Energy  
Project: Reserve Pit Samples

Work Order: 0810029

Analyte	Result	Units	PQL	%Rec	LowLimit	HighLimit	%RPD	RPDLimit	Qual
<b>Method: EPA Method 300.0: Anions</b>									
Sample ID: MB-17278		MBLK			Batch ID: 17278	Analysis Date: 10/9/2008 4:26:47 AM			
Chloride	ND	mg/Kg	0.30						
Sample ID: LCS-17278		LCS			Batch ID: 17278	Analysis Date: 10/9/2008 4:09:23 AM			
Chloride	14.61	mg/Kg	0.30	97.4	90	110			
<b>Method: EPA Method 418.1: TPH</b>									
Sample ID: MB-17274		MBLK			Batch ID: 17274	Analysis Date: 10/6/2008			
Petroleum Hydrocarbons, TR	ND	mg/Kg	20						
Sample ID: LCS-17274		LCS			Batch ID: 17274	Analysis Date: 10/6/2008			
Petroleum Hydrocarbons, TR	91.14	mg/Kg	20	91.1	82	114			
Sample ID: LCSD-17274		LCSD			Batch ID: 17274	Analysis Date: 10/6/2008			
Petroleum Hydrocarbons, TR	89.70	mg/Kg	20	89.7	82	114	1.59	20	
<b>Method: EPA Method 8015B: Diesel Range Organics</b>									
Sample ID: MB-17265		MBLK			Batch ID: 17265	Analysis Date: 10/7/2008			
Diesel Range Organics (DRO)	ND	mg/Kg	10						
Motor Oil Range Organics (MRO)	ND	mg/Kg	50						
Sample ID: LCS-17265		LCS			Batch ID: 17265	Analysis Date: 10/7/2008			
Diesel Range Organics (DRO)	50.42	mg/Kg	10	101	64.6	116			
Sample ID: LCSD-17265		LCSD			Batch ID: 17265	Analysis Date: 10/7/2008			
Diesel Range Organics (DRO)	51.21	mg/Kg	10	102	64.6	116	1.56	17.4	
<b>Method: EPA Method 8015B: Gasoline Range</b>									
Sample ID: MB-17254		MBLK			Batch ID: 17254	Analysis Date: 10/12/2008 11:22:29 AM			
Gasoline Range Organics (GRO)	ND	mg/Kg	5.0						
Sample ID: LCS-17254		LCS			Batch ID: 17254	Analysis Date: 10/12/2008 11:52:56 AM			
Gasoline Range Organics (GRO)	23.63	mg/Kg	5.0	94.5	69.5	120			
<b>Method: EPA Method 8021B: Volatiles</b>									
Sample ID: MB-17254		MBLK			Batch ID: 17254	Analysis Date: 10/12/2008 11:22:29 AM			
Benzene	ND	mg/Kg	0.050						
Toluene	ND	mg/Kg	0.050						
Ethylbenzene	ND	mg/Kg	0.050						
Xylenes, Total	ND	mg/Kg	0.10						
Sample ID: LCS-17254		LCS			Batch ID: 17254	Analysis Date: 10/12/2008 11:52:56 AM			
Benzene	0.3162	mg/Kg	0.050	113	78.8	132			
Toluene	2.185	mg/Kg	0.050	109	78.9	112			
Ethylbenzene	0.4510	mg/Kg	0.050	113	69.3	125			
Xylenes, Total	2.687	mg/Kg	0.10	117	73	128			

## Qualifiers:

E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	S	Spike recovery outside accepted recovery limits

# Hall Environmental Analysis Laboratory, Inc.

## Sample Receipt Checklist

Client Name XTO ENERGY

Date Received:

10/2/2008

Work Order Number 0810029

Received by: ARS

Checklist completed by:

Signature

Date

Sample ID labels checked by:

Initials

Matrix:

Carrier name FedEx

Shipping container/cooler in good condition?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	Not Present <input type="checkbox"/>	
Custody seals intact on shipping container/cooler?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	Not Present <input type="checkbox"/>	Not Shipped <input type="checkbox"/>
Custody seals intact on sample bottles?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
Chain of custody present?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Chain of custody signed when relinquished and received?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Chain of custody agrees with sample labels?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Samples in proper container/bottle?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Sample containers intact?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Sufficient sample volume for indicated test?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
All samples received within holding time?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Water - VOA vials have zero headspace?	No VOA vials submitted <input checked="" type="checkbox"/>	Yes <input type="checkbox"/>	No <input type="checkbox"/>	
Water - Preservation labels on bottle and cap match?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
Water - pH acceptable upon receipt?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	

Container/Temp Blank temperature?

4°

<6° C Acceptable

If given sufficient time to cool.

COMMENTS:

Client contacted \_\_\_\_\_ Date contacted: \_\_\_\_\_ Person contacted \_\_\_\_\_

Contacted by: \_\_\_\_\_ Regarding: \_\_\_\_\_

Comments: \_\_\_\_\_

Corrective Action \_\_\_\_\_

## Chain-of-Custody Record

Client: XTO ENERGY

Address: 382 ROAD 3100  
AZTEC NM 87410

Phone #: 505-333-3207

email or Fax#:

QA/QC Package:

☐ Standard      ☐ Level 4 (Full Validation)

☐ Other \_\_\_\_\_

☐ EDD (Type) \_\_\_\_\_

Turn-Around Time: ..

☒ **Standard**      ☐ **Rush**

Project Name:

## RESERVE PIT SAMPLES

Project #: IRISH # 1E

Project Manager: \_\_\_\_\_

MARTIN NEE

Sampler: Kuet

On Ice ☒ Yes ☐ No

Sample Temperature: 60°C

[illegible]


Date:	Time:	Relinquished by:
10/1	8:00 AM	Kurt Huesler
Date:	Time:	Relinquished by:

Date: \_\_\_\_\_ Time: \_\_\_\_\_ Relinquished by: \_\_\_\_\_

Received by: *[Signature]* 10:05 10/2/08

Received by: \_\_\_\_\_

Remarks:  
E-MAIL RESULTS TO:  
KURT HOEKSTRA  
KIM CHAMPLIN



## HALL ENVIRONMENTAL ANALYSIS LABORATORY

[www.hallenvironmental.com](http://www.hallenvironmental.com)

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975      Fax 505-345-4107

## Analysis Request

				X	BTEX + MTBE + TMB's (8021)
					BTEX + MTBE + TPH (Gas only)
					TPH Method 8015B (Gas/Diesel)
				X	TPH (Method 418.1)
					EDB (Method 504.1)
					EDC (Method 8260)
					8310 (PNA or PAH)
					Anions ( $F, Cl, NO_3, PO_4, SO_4$ )
					8081 Pesticides / 8082 PCB's
					8260B (VOA)
					8270 (Semi-VOA)
				X	880-DFO 8015 M
				X	CHLORIDES 300.0
					Air Bubbles (Y or N)

If necessary, samples submitted to Hall Environmental may be subcontracted to other accredited laboratories. This serves as notice of this possibility. Any sub-contracted data will be clearly notated on the analytical report.



## COVER LETTER

Wednesday, December 24, 2008

Martin Nee  
XTO Energy  
382 County Road 3100  
Aztec, NM 87410

TEL: (505) 333-3100

FAX (505) 333-3280

RE: Reserve Pit Samples

Order No.: 0812367

Dear Martin Nee:

Hall Environmental Analysis Laboratory, Inc. received 1 sample(s) on 12/18/2008 for the analyses presented in the following report.

These were analyzed according to EPA procedures or equivalent. Below is a list of our accreditations. To access our accredited tests please go to [www.hallenvironmental.com](http://www.hallenvironmental.com) or the state specific web sites.

Reporting limits are determined by EPA methodology. No determination of compounds below these (denoted by the ND or < sign) has been made.

Please don't hesitate to contact HEAL for any additional information or clarifications.

Sincerely,

A handwritten signature in black ink, appearing to read 'Andy Freeman', is written over a horizontal line.

Andy Freeman, Business Manager  
Nancy McDuffie, Laboratory Manager

NM Lab # NM9425  
AZ license # AZ0682  
ORELAP Lab # NM100001  
Texas Lab# T104704424-08-TX



4901 Hawkins NE ■ Suite D ■ Albuquerque, NM 87109  
505.345.3975 ■ Fax 505.345.4107  
[www.hallenvironmental.com](http://www.hallenvironmental.com)

**Hall Environmental Analysis Laboratory, Inc.**

Date: 24-Dec-08

**CLIENT:** XTO Energy  
**Lab Order:** 0812367  
**Project:** Reserve Pit Samples  
**Lab ID:** 0812367-01

**Client Sample ID:** Irish #1E-Resample Reserve Pit  
**Collection Date:** 12/15/2008 1:00:00 PM  
**Date Received:** 12/18/2008  
**Matrix:** SOIL

Analyses	Result	PQL	Qual	Units	DF	Date Analyzed
EPA METHOD 300.0: ANIONS						Analyst: RAGS
Chloride	14	0.30		mg/Kg	1	12/22/2008 4:52:39 PM

**Qualifiers:**

- \* Value exceeds Maximum Contaminant Level
- E Estimated value
- J Analyte detected below quantitation limits
- ND Not Detected at the Reporting Limit
- S Spike recovery outside accepted recovery limits

- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- MCL Maximum Contaminant Level
- RL Reporting Limit



## QA/QC SUMMARY REPORT

Client: XTO Energy  
Project: Reserve Pit Samples

Work Order: 0812367

Analyte	Result	Units	PQL	%Rec	LowLimit	HighLimit	%RPD	RPDLimit	Qual
---------	--------	-------	-----	------	----------	-----------	------	----------	------

Method: EPA Method 300.0: Anions

Sample ID: MB-17905

MBLK

Batch ID: 17905 Analysis Date: 12/20/2008 10:08:02 AM

Chloride

ND

mg/Kg

0.30

Sample ID: LCS-17905

LCS

Batch ID: 17905 Analysis Date: 12/20/2008 10:25:26 AM

Chloride

15.35

mg/Kg

0.30

102

90

110

## Qualifiers:

E	Estimated value	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	S	Spike recovery outside accepted recovery limits

# Hall Environmental Analysis Laboratory, Inc.

## Sample Receipt Checklist

Client Name XTO ENERGY

Date Received:

12/18/2008

Work Order Number 0812367

Received by: TLS

Checklist completed by:

Signature

Date

Sample ID labels checked by:

Initials

Matrix:

Carrier name FedEx

Shipping container/cooler in good condition?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	Not Present <input type="checkbox"/>	
Custody seals intact on shipping container/cooler?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	Not Present <input type="checkbox"/>	Not Shipped <input type="checkbox"/>
Custody seals intact on sample bottles?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
Chain of custody present?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Chain of custody signed when relinquished and received?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Chain of custody agrees with sample labels?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Samples in proper container/bottle?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Sample containers intact?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Sufficient sample volume for indicated test?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
All samples received within holding time?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>		
Water - VOA vials have zero headspace?	No VOA vials submitted <input checked="" type="checkbox"/>	Yes <input type="checkbox"/>	No <input type="checkbox"/>	
Water - Preservation labels on bottle and cap match?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
Water - pH acceptable upon receipt?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
Container/Temp Blank temperature?	1°	<6° C Acceptable If given sufficient time to cool.		

COMMENTS:

Client contacted \_\_\_\_\_ Date contacted: \_\_\_\_\_ Person contacted \_\_\_\_\_

Contacted by: \_\_\_\_\_ Regarding: \_\_\_\_\_

Comments: \_\_\_\_\_

Corrective Action \_\_\_\_\_

Chain-of-Custody Record		Turn-Around Time:	
Client: <u>XTO ENERGY</u>		<input checked="" type="checkbox"/> Standard <input type="checkbox"/> Rush _____	
Address: <u>382 ROAD 3100</u> <u>AZTEC NM 87410</u>		Project Name: <u>RESERVE PIT SAMPLES</u>	
Phone #: <u>505-333-3207</u>		Project #: <u>RE-SAMPLE</u> <u>IRISH # 1E RESERVE PIT</u>	
email or Fax#:		Project Manager: <u>MARTIN NEE</u>	
QA/QC Package:		Sampler: <u>KURT</u>	
<input type="checkbox"/> Standard <input type="checkbox"/> Level 4 (Full Validation)		On-site: <input type="checkbox"/> YES <input type="checkbox"/> NO	
<input type="checkbox"/> Other _____		Sample Temperature: <u>77</u>	
<input type="checkbox"/> EDD (Type) _____			

[www.hallenvironmental.com](http://www.hallenvironmental.com)

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975      Fax 505-345-4107

## Analysis Request

[illegible]

If necessary, samples submitted to Hall Environmental may be subcontracted to other accredited laboratories. This serves as notice of this possibility. Any sub-contracted data will be clearly notated on the analytical report.

Submit 3 Copies To Appropriate District  
Office  
District I  
1625 N French Dr., Hobbs, NM 88240  
District II  
1301 W Grand Ave., Artesia, NM 88210  
District III  
1000 Rio Brazos Rd., Aztec, NM 87410  
District IV  
1220 S St. Francis Dr., Santa Fe, NM  
87505

State of New Mexico  
Energy, Minerals and Natural Resources

Form C-103  
June 19, 2008

OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

<b>SUNDRY NOTICES AND REPORTS ON WELLS</b> (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS)		WELL API NO. 30-045-33743
1. Type of Well: Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other		5. Indicate Type of Lease STATE <input type="checkbox"/> FEE <input type="checkbox"/>
2. Name of Operator XTO Energy Inc		6. State Oil & Gas Lease No.
3. Address of Operator 382 County Road 3100 Aztec, NM 87410		7. Lease Name or Unit Agreement Name Irish
4. Well Location Unit Letter K : 1550 feet from the South line and 1900 feet from the West line Section 22 Township 25N Range 10W NMPM County San Juan		8. Well Number #2
11. Elevation (Show whether DR, RKB, RT, GR, etc.)		9. OGRID Number 5380
		10. Pool name or Wildcat Basin Dakota

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
PERFORM REMEDIAL WORK <input type="checkbox"/>	PLUG AND ABANDON <input type="checkbox"/>	REMEDIAL WORK <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
TEMPORARILY ABANDON <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	COMMENCE DRILLING OPNS. <input type="checkbox"/>	P AND A <input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	MULTIPLE COMPL <input type="checkbox"/>	CASING/CEMENT JOB <input type="checkbox"/>	
DOWNHOLE COMMINGLE <input type="checkbox"/>			
OTHER <input type="checkbox"/>		OTHER: Seed Temporary Pit Area <input checked="" type="checkbox"/>	

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

The area where the temporary pit has been buried in place was seeded on April 8, 2009 using BLM Seed Mix by drilling on the contour (disk and seed contour).

BLM Seed Mix Special:>10 Inches of Precipitation

Fourwing Saltbush (Atriplex Canescens)	1.0 lbs
Indian Wheatgrass (Oryzopsis Hymenoides)	1.0 lbs
Western Wheatgrass (Agropyron Smithii)	2.0 lbs
Blue Gamma (Hatcheta or Alma)	0.25 lbs
Small Burnet (Delar)	1.0 lbs
Pubescent Wheatgrass	2.0 lbs
Intermediate Wheatgrass	2.0 lbs
Smooth Brome	2.0 lbs
Antelope Bitterbrush	0.10 lbs

Spud Date:

July 16, 2008

Rig Release Date:

July 26, 2008

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Kim Champlin TITLE EH&S Administrative Coord DATE 12/10/2009  
Type or print name Kim Champlin E-mail address: kim\_champlin@xtoenergy.com PHONE: (505) 333-3100  
**For State Use Only**

APPROVED BY: \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_  
Conditions of Approval (if any): \_\_\_\_\_

## TEMPORARY PIT INSPECTION FORM

**Well Name:** Irish # 1E

**API No.:** 30-045-33743

**Legals:**

**Sec:** 22

**Township:** 25N

**Range:** 10W

Inspector's	Inspection	Any visible liner	Any fluid seeps/	HC's on top of	Temp. pit free of misc	Discharg line	Fence	Any dead	Freeboard
Name	Date	breeches (Y/N)	spills (Y/N)	temp. pit (Y/N)	solid waste/ debris (Y/N)	integrity (Y/N)	integrity (Y/N)	wildlife/stock (Y/N)	Est. (ft)
B.Cummins	7/15/2008	No	No	No	Yes	No	Yes	No	+/- 8'
B.Cummins	7/16/2008	No	No	No	Yes	No	Yes	No	+/- 8'
B.Cummins	7/17/2008	No	No	No	Yes	No	Yes	No	+/- 8'
B.Cummins	7/18/2008	No	No	No	Yes	No	Yes	No	+/- 7'
B.Cummins	7/19/2008	No	No	No	Yes	No	Yes	No	+/- 7'
D.Elrod	7/20/2008	No	No	No	Yes	No	Yes	No	+/- 7'
D.Elrod	7/21/2008	No	No	No	Yes	No	Yes	No	+/- 7'
D.Elrod	7/22/2008	No	No	No	Yes	No	Yes	No	+/- 7'
D.Romango	7/23/2008	No	No	No	Yes	No	Yes	No	+/- 7'
D.Romango	7/24/2008	No	No	No	Yes	No	Yes	No	+/- 7'
D.Romango	7/25/2008	No	No	No	Yes	No	Yes	No	+/- 7'
D.Romango	7/26/2008	No	No	No	Yes	No	Yes	No	+/- 7'
D.Romango	7/27/2008	No	No	No	Yes	No	Yes	No	+/- 7'
D.Romango	7/28/2008	No	No	No	Yes	No	Yes	No	+/- 7'
M. Hartsell	8/4/2008	No	No	No	Yes	No	Yes	No	+/- 7'

**Notes:**

Provide Detailed Description: Observed one tear approx. 12"-14" long in an arc shape, and several small holes where rocks and sticks have poked through. All holes and tears on upper part of apron near the edge of the liner.

**Misc:**

## TEMPORARY PIT INSPECTION FORM

**Well Name:** Irish # 1E

**API No.:** 30-045-33743

**Legals:**

**Sec:** 22

**Township:** 25N

**Range:** 10W

Inspector's	Inspection	Any visible liner	Any fluid seeps/	HC's on top of	Temp. pit free of misc	Discharg line	Fence	Any dead	Freeboard
Name	Date	breeches (Y/N)	spills (Y/N)	temp. pit (Y/N)	solid waste/ debris (Y/N)	integrity (Y/N)	integrity (Y/N)	wildlife/stock (Y/N)	Est. (ft)
M. Hartsell	8/13/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	8/20/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	8/27/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	9/3/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	9/10/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	9/17/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	9/24/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	10/1/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	10/8/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	10/15/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	10/22/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	10/29/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	11/5/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	11/12/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	11/19/2008	No	No	No	Yes	No	Yes	No	>2'

**Notes:**

Provide Detailed Description:

**Misc:**

## TEMPORARY PIT INSPECTION FORM

Well Name: Irish # 1E

API No.: 30-045-33743

Legals:                      Sec: 22

Township: 25N

Range: 10W

Inspector's	Inspection	Any visible liner	Any fluid seeps/	HC's on top of	Temp. pit free of misc	Discharg line	Fence	Any dead	Freeboard
Name	Date	breeches (Y/N)	spills (Y/N)	temp. pit (Y/N)	solid waste/ debris (Y/N)	integrity (Y/N)	integrity (Y/N)	wildlife/stock (Y/N)	Est. (ft)
M. Hartsell	11/26/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	12/3/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	12/10/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	12/17/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	12/24/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	12/31/2008	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	1/7/2009	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	1/14/2009	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	1/21/2009	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	1/28/2009	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	2/4/2009	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	2/11/2009	No	No	No	Yes	No	Yes	No	>2'
M. Hartsell	2/18/2009	No	No	No	Yes	No	Yes	No	>2'

**Notes:**

Provide Detailed Description: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

**Misc:**

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

