


(SUBMIT IN TRIPLICATE)

Land Office Santa Fe, N. M.

Lease No. SF 080533

Unit _____



UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL		SUBSEQUENT REPORT OF WATER SHUT-OFF	
NOTICE OF INTENTION TO CHANGE PLANS		SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING	
NOTICE OF INTENTION TO TEST WATER SHUT-OFF		SUBSEQUENT REPORT OF ALTERING CASING	
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL		SUBSEQUENT REPORT OF RE-DRILLING OR REPAIR	
NOTICE OF INTENTION TO SHOOT OR ACIDIZE		SUBSEQUENT REPORT OF ABANDONMENT	
NOTICE OF INTENTION TO PULL OR ALTER CASING		SUPPLEMENTARY WELL HISTORY	
NOTICE OF INTENTION TO ABANDON WELL	<input checked="" type="checkbox"/>		

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

September 3, 19 57

Well No. Pool Four 41 is located 675 ft. from [N] line and 650 ft. from [E] line of sec. 22

22 21N 3N 18TH
(Sec. and Sec. No.) (Twp.) (Range) (Meridian)

Wildcat SANDOVAL New Mexico
(Field) (County or Subdivision) (State or Territory)

The elevation of the Kelly Bushing ~~derrick floor~~ above sea level is 7242 ft.


DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

Status: Total depth 5089'
Casing 4-5/8" at 215'
Hole size 7-7/8" from 215 to 5089'

Proposed Work:

- Place plugs as follows through open end drill pipe:
 - 50 sacks 4550-4800'
 - 50 sacks 3750-3900'
 - 50 sacks 1410-1560'
 - 50 sacks 100-250'
- Peel for top plug if not above 200', recement.
- Cap with a 10 sack cement plug, install marker and abandon in accordance with U.S.G.S. regulations.



I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company Shell Oil Company

Address 101 S. Behrend

Farmington, N. M.

By B. W. Shepard
B. W. Shepard

Title Exploitation Engineer

Verbal approval of plugging program, Mr. Blummer U.S.G.S. to B. J. Langford, 8-30-57.