

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☐ gas well ☒ other _____
2. NAME OF OPERATOR
DAVIS OIL COMPANY
3. ADDRESS OF OPERATOR
1424 Tenth Street Rock Springs, Wyo. 82901
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.) 1000' FSL 1640' FWL.
AT SURFACE: SE-SW Sec. 5 T22N R8W
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) _____

SUBSEQUENT REPORT OF:


☐
☐
☐
☐
☐
☐
☐
☒

5. LEASE
NM - 8904
6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME
Beard Federal
9. WELL NO.
#1
10. FIELD OR WILDCAT NAME
Wildecat
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 5 T22N R8W
12. COUNTY OR PARISH
San Juan
13. STATE
New Mexico
14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)
6797' GR



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Verbal plugging orders received from James Sims - U.S.G.S. Plugging witnessed by Ken Baker - U.S.G.S.

Plugging procedure:

Cast iron bridge plug @ 480'-2 3/8" tubing set @ 260'.

Pumped 60 sxs. class B cement down tubing-returns to surface in casing.

Closed casing valve & squeezed balance of cement into perfs to 1000 PSI. Removed casing head, left 2 3/8" tubing in hole.

Regulation dry hole marker set by welding to tubing & cementing w/ 40 sxs. cement.

Plugged and abandoned 5-29-80.

Location to be contoured and seeded per B.L.M. Specification at appropriate time.

Subsurface Safety Valve: Manu. and Type _____

Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct.

SIGNED

B. R. Baker

TITLE

Superintendent

DATE 6-6-80

APPROVED BY

CONDITIONS OF APPROVAL IF ANY

APPROVED

FEB 19 1982

For JAMES F. SIMS
DISTRICT ENGINEER

TITLE

DATE

*See Instructions on Reverse Side

