

Form 9-331b
(April 1952)

(SUBMIT IN TRIPLICATE)


Indian Agency

Jicarilla Apache

Allottee

Lease No. 36

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY



SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL.....	SUBSEQUENT REPORT OF WATER SHUT-OFF.....
NOTICE OF INTENTION TO CHANGE PLANS.....	SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING.....
NOTICE OF INTENTION TO TEST WATER SHUT-OFF.....	SUBSEQUENT REPORT OF ALTERING CASING.....
NOTICE OF INTENTION TO REDRILL OR REPAIR WELL.....	SUBSEQUENT REPORT OF REDRILLING OR REPAIR.....
NOTICE OF INTENTION TO SHOOT OR ACIDIZE.....	SUBSEQUENT REPORT OF ABANDONMENT.....
NOTICE OF INTENTION TO PULL OR ALTER CASING.....	SUPPLEMENTARY WELL HISTORY.....
NOTICE OF INTENTION TO ABANDON WELL.....	Subsequent Report of Perforating and Testing.....

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

January 31, 19 63

Well No. 1 is located 1850 ft. from $\begin{matrix} N \\ S \end{matrix}$ line and 790 ft. from $\begin{matrix} E \\ W \end{matrix}$ line of sec. 9

SW/4 Sec. 9
(1/4 Sec. and Sec. No.)

T24N
(Twp.)

R5W
(Range)

NMPM
(Meridian)

Northeast Haynes
(Field)

Rio Arriba County
(County or Subdivision)


New Mexico
(State or Territory)

The elevation of the derrick floor above sea level is 6535 ft.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

Recomplete Greenhorn string to Mesa Verde and perforate Upper Gallup. Spotted cement plug in 2 7/8" casing from 5890' to 5950' to plug-off Greenhorn formation. Perforated 2 7/8" Mesa Verde casing 4604'-4613' and 4593'-4599'. Perforated 4 1/2" Gallup 5618'-5632' and 5694'-5698'. Sandfraced Gallup w/41,000# sand, 1550# ADOMITE, & 1071 bbls. distillate. Mesa Verde flowed 937 MCF gas and 25 bbls. condensate on 24/64" choke in 24 hours. Upper Gallup tested 10 BOPD, IP total Gallup formation, 17 BOPD.



I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company Continental Oil Company

Address Box 3312

Durango, Colorado

By

Title District Superintendent

