

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)


1. oil well ☒ gas well ☐ other ☐
- 
2. NAME OF OPERATOR  
Getty Oil Company
- 
3. ADDRESS OF OPERATOR  
P.O. Box 3360, Casper, WY 82602
- 
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)  
AT SURFACE: 543' FNL & 1912' FEL  
AT TOP PROD. INTERVAL: Same  
AT TOTAL DEPTH: Same
- 
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

|                      |                                     |
|----------------------|-------------------------------------|
| TEST WATER SHUT-OFF  | <input type="checkbox"/>            |
| FRACTURE TREAT       | <input type="checkbox"/>            |
| SHOOT OR ACIDIZE     | <input type="checkbox"/>            |
| REPAIR WELL          | <input type="checkbox"/>            |
| PULL OR ALTER CASING | <input type="checkbox"/>            |
| MULTIPLE COMPLETE    | <input type="checkbox"/>            |
| CHANGE ZONES         | <input type="checkbox"/>            |
| ABANDON*             | <input checked="" type="checkbox"/> |
| (other) NIA          |                                     |

SUBSEQUENT REPORT OF:

|  |  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|--|
|  |  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|--|



- |                                                  |            |
|--------------------------------------------------|------------|
| 5. LEASE                                         |            |
| Contract #68                                     |            |
| 6. IF INDIAN, ALLOTTEE OR TRIBE NAME             |            |
| Jicarilla Apache                                 |            |
| 7. UNIT AGREEMENT NAME                           |            |
| -                                                |            |
| 8. FARM OR LEASE NAME                            |            |
| Jicarilla "B"                                    |            |
| 9. WELL NO.                                      |            |
| 16                                               |            |
| 10. FIELD OR WILDCAT NAME                        |            |
| Otero Gallup                                     |            |
| 11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA |            |
| Section 6-T24N-R5W                               |            |
| 12. COUNTY OR PARISH                             | 13. STATE  |
| Rio Arriba                                       | New Mexico |
| 14. API NO.                                      |            |
| -                                                |            |
| 15. ELEVATIONS (SHOW DF, KDB, AND WD)            |            |
| 6762' GL                                         |            |

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Getty Oil Company requests approval to P & A this well. Evaluation of this well found that it would not be economical to recompleate this well to any other zone.

Plugging operations will commence as follows:

1. MIRU pulling unit, ND tree.
2. Run free point on casing. Cutt off casing at free point, POH with 5 1/2" casing.
3. NU BOP. TIH with 2 3/8" workstring.
4. Spot Class B cement plugs from 2667'-2420' (28 sx) and 1970'-1870' (12 sx) inside casing. (Over)

Subsurface Safety Valve: Manu. and Type \_\_\_\_\_ Set @ \_\_\_\_\_ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE Area Superintendent DATE 7-14-82

APPROVED BY [Signature] TITLE \_\_\_\_\_ DATE \_\_\_\_\_  
CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

*for* JAMES F. SIMS  
DISTRICT ENGINEER

## Instructions

**General:** This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

**Item 4:** If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

**Item 17:** Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

17. 5. Spot a 100' Class 'B' cement plug at the depth where the casing has been cut off 50' (6 sx) inside the casing stub and 50' (18 sx) in the open hole above the casing stub.
6. Set a 100' Class 'B' cement plug from 375'-275' (42 sx). Tag this plug with the workstring before setting the surface plug.
7. Cut - off all casing 3' below surface, set a 50' (24 sx) surface plug from 50'-0'. Set an abandonment marker of 5 1/2" casing at least 10' long with at least 4' above the restored ground level with this information welded on it: JICARILLA 'B' - 16, UNIT B-SEC. 6-T24N-R5W, RIO ARriba COUNTY, NEW MEXICO
8. Remove all equipment from location and restore location to BIA, MMS, ~~and BIA~~ specifications.

**Note:** Plugs shall be placed by the balanced plug method with 9.2 ppg mud between plugs.

**NOTE:** If the procedure is to be altered in any manner, notify the Casper Area Office and the MMS in Farmington before proceeding with work.