

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Texaco Inc.

3. Address and Telephone No.

3300 N. Butler, Farmington N.M. 87401 (505)325-4397

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

660' FNL & 1980' FEL SEC 32 T25N-R5W **B**

5. Lease Designation and Serial No.

JIC CAR 68

6. If Indian, Allottee or Tribe Name

JICARILLA APACHE

7. If Unit or CA, Agreement Designation

8. Well Name and No.

JICARILLA B 13

9. API Well No.

30-039-18214

10. Field and Pool, or Exploratory Area

S. BLANCO PICTURED CLIFFS

11. County or Parish, State

RIO ARRIBA

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☒ Abandonment

☐ Recompletion

☐ Plugging Back

☐ Casing Repair

☐ Altering Casing

☐ Other

☐ Change of Plans

☐ New Construction

☐ Non-Routine Fracturing

☐ Water Shut-Off

☐ Conversion to Injection

☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

TEXACO INC. PROPOSES TO PLUG AND ABANDON THE SUBJECT WELL AS FOLLOWS:

1. Set CMT RET @ 2680'.
2. RU wireline and run CBL from 2680'-1680'.
3. TIH w/ 2 3/8" tbg and sting into ret. SQZ PC perfs and fill from 2820'-2680' w/ 80 sx class B cmt. Spot 50 sx cmt on top ret. Spot 9.2 #/gal mud 2050'-690'.
4. TOOH w/ tbg and RIH w/ perf gun, perf sqz holes @ 640'.
5. Spot cmt plug using the Balance Plug method from 590'-690' inside and outside csg w/ 55 sx class B cmt. Spot 9.2 #/gal mud 590'-365'.
6. RIH w/ perf gun, perf sqz holes @ 365'.
7. RU service co. and circ cmt to surface.
8. RDMOSU. ERECT P&A marker.

SEE ATTACHED FOR
CONDITIONS OF APPROVAL

Verbal approval was granted by Mr. Wayne Townsend of the BLM to Darren Segrest of Texaco on September 5, 1990 at 3:10 pm.

14. I hereby certify that the foregoing is true and correct

Signed

Alan A. Kleier

Title

Area Manager

Date

9/5/90

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

Ken Townsend

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

DATE: 5/9/90

JICARILLA B # 13

10 3/4" ● 313'
W/ 300SX CMT
CMT CIRC

**SQZ HOLES @ 640'
CMT PLUG 590'—690'
(W/ 100% EXCESS)**

CMT PLUG 2050'-2150'
(W/ 100% EXCESS)


CIBP • 2820'
W/ 3 SX CMT

DV 3751

TOC @ 5120'

CMT RET • 59 13'

5 1/2" J-55 • 6244'
TD 6245'



LOCATION
NE/4 NE/4 SEC 32 T25N-R5W

SQZ HOLES @ 365'

9.2 LB/GAL MUD
590'-365'
690'-2050'
2150'-2460'

TOC EST @ 1800'

CMT RET @ 2680'

PICTURED CLIFFS PERFORATIONS
2690'-2698'

CHACRA PERFORATIONS
3526'—3644'

CIBP ● 3740'
W/ 1 SX CMT

GALLUP PERFORATIONS
6053'-6155'
SQZ W/ 100 SX

DATE: 5/9/90

JICARILLA B #13

PRESENT COMPLETION

10 3/4" ● 313'
W/ 300SX CMT
CMT CIRC

LOCATION
NE/4 NE/4 SEC 32 T25N-R5W

TOC EST ● 1800'


CIBP ● 2820'
W/ 3 SX CMT

DV ● 3751

TOC ● 5120'

CMT RET ● 5913'

5 1/2" J-55 ● 6244'
TD 6245'



PICTURED CLIFFS PERFORATIONS
2690'-2698'

CHACRA PERFORATIONS
3526'-3644'

CIBP ● 3740'
W/ 1 SX CMT

GALLUP PERFORATIONS
6053'-6155'
SQZ W/ 100 SX