

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☒ well other ☐
2. NAME OF OPERATOR
Cotton Petroleum Corporation
3. ADDRESS OF OPERATOR
717 17th St., Suite 2200, Denver, Co. 80202
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1850' FWL, 900' FNL, Section 14
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☒
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:

☐
☐
☐
☐
☐
☐
☐
☐
☐

5. LEASE
Contract No. 129
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
Jicarilla Apache
7. UNIT AGREEMENT NAME
8. FARM OR LEASE NAME
Apache
9. WELL NO.
29
10. FIELD OR WILDCAT NAME
So. Blanco P. C. Chacra
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 14-T24N-R4W N.M.P.M.
12. COUNTY OR PARISH
Rio Arriba
13. STATE
New Mexico
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Cotton Petroleum wishes to change the APD on the Apache #29 to be a Chacra test instead of a Picture Cliff test. Proposed TD will be 4100' with the top of the Chacra at 3914'. Production casing will be run to 4100' and cemented with 100 sacks 65-35 poz, 12 1/2#/sx gilsonite followed by 600 sacks 50-50 poz with 2% gel. This volume will result in a cement top of 2000' (assuming 100% excess). This amount of cement will protect the Ojo Alamo.

All other information filed with the original APD is still applicable.

Subsurface Safety Valve: Manu. and Type _____

Set @ _____

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE Division Prod. Mgr. DATE February 22, 1980APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:APPROVED
(This space for Federal or State office use)


AS AMENDED

MAR 10 1980

JAMES F. SIMS
DISTRICT ENGINEER

See Instructions on Reverse Side

DATE FEB 22 1980

U. S. GEOLOGICAL SURVEY
DURANGO, COLO.

TO FILE
WITH ATTACHED
COMMENTS

ok [Signature]