

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☒ well other ☐

2. NAME OF OPERATOR
Getty Oil Company

3. ADDRESS OF OPERATOR
P.O. Box 3360, Casper, WY 82602-3360

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1520' FSL & 1850' FEL Sec. 28
AT TOP PROD. INTERVAL: same
AT TOTAL DEPTH: same


16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐

(other) Perf, acidize and frac

SUBSEQUENT REPORT OF:



5. LEASE
Contract #34

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
Jicarilla Apache

7. UNIT AGREEMENT NAME
-

8. FARM OR LEASE NAME
Jicarilla "C"

9. WELL NO.
32

10. FIELD OR WILDCAT NAME
Otero Chacra

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
J Sec. 28-T25N-R5W

12. COUNTY OR PARISH 13. STATE
Rio Arriba New Mexico

14. API NO.
-

15. ELEVATIONS (SHOW DF, KDB, AND WD)
6638' GR

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

On 8-19-82 MIRU completion unit. Tagged cmt @ 3500'. Drilled out cmt to FC @ 3704'. Ran CBL from 3704' to surface. Pressure tested casing to 3000 psi - held OK for 15 min. Spotted 100 gal 10% acetic acid and perf'd Chacra with 1 spf, 0.40" holes, 22 gram charge, total 19 holes as follows: 3473'-3476', 3486'-3496', 3554'-3556', 3573'-3575', 3582'-3584'.

On 8-20-82 acidized Chacra perfs 3473'-3584' with 600 gal 15% HCl.

On 8-21-82 frac'd Chacra perfs 3473'-3584' w/ 49,000 gal of 70% foam plus 5000# of 20-40 sand plus 60,000 lbs 10-20 sand.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct Area _____

SIGNED W. Bowen TITLE Superintendent DATE 9-20-82

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

ACCEPTED FOR RECORD

SEP 27 1982

*See Instructions on Reverse Side

NMOCC

FARMINGTON DISTRICT

BY

Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.