

EXHIBIT A

DEVELOPMENTAL PLAN
J. FELIX HICKMAN
Clark #11 Well
1865' FNL - 550' FEL
Sec. 5, T24N, R3W, NMPM
Rio Arriba County, NM

1. Existing roads are shown on Exhibit E.
Plan to improve and/or maintain existing roads as follows: Plan to build 250' of new road from the existing road to location.
2. Planned access road(s) are shown on Exhibit E.
 - A. New or reconstructed roads(s), if any, were centerline-flagged at the time of location staking.
 - B. Access road does cross Federal land.
3. Location of existing wells is shown on Exhibit F.
4. Location of existing and/or proposed facilities
 - A. Existing facilities owned or controlled by lessee/operator are shown on Exhibit F.
 - B. New facilities, in the event of production, are shown on Exhibit F.
Construction materials and methods: Materials obtained on site; work to be performed with a bulldozer.
Protective measures and devices to protect livestock and wildlife: As Required.
 - C. Plan for rehabilitation of disturbed areas no longer needed for operations after construction completed: As Required.
5. Location and Type of Water Supply
 - A. Location and type of water supply: Lindrith #3 water hole.
 - B. Method of transporting water: Water Truck.
 - C. Water well is not to be drilled on lease.
6. Source of Construction Materials
 - A. Materials are to be obtained on site.
 - B. These materials are from Federal land.
 - C. These materials are to be used as follows: Level location, build pits, construct roadway to location.
7. Methods for Handling Waste Disposal
 - A. Waste materials will be contained/disposed of as follows:
 - 1) Cuttings: Reserve Pit.
 - 2) Drilling fluids: Reserve Pit.
 - 3) Produced fluids (oil, water): Reserve Pit.
 - 4) Sewage: Drilling Contractor will provide facilities.
 - 5) Drilling contractor will provide a portable trash pit.
 - 6) Operator will be responsible for proper cleanup when the rig is moved.
 - 7) Reserve pits will be fenced on three sides during the drilling operations and on four sides when the rig is moved from location.
8. Ancillary facilities: No permanent camp is planned; no trailer house will be used on location while drilling. No airstrip is planned.
9. Well site layout is shown on Exhibit C.
Pits are to be unlined.