

DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT" for such proposals.)

1. OIL WELL ☒ GAS WELL ☐ OTHER ☐		5. LEASE DESIGNATION AND SERIAL NO. NM-0557389
2. NAME OF OPERATOR BCO, Inc.		6. IF INDIAN, ADOPTED OR TRIBAL NAME
3. ADDRESS OF OPERATOR P. O. Box 669 Santa Fe, New Mexico 87501		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 2310' FNL 1980' FWL Sec 12 T24N R8W		8. FARM OR LEASE NAME Nancy
14. PERMIT NO.		9. WELL NO. 4
15. ELEVATIONS (Show whether DP, RT, CR, etc.) GR 7287		10. FIELD AND POOL, OR WILDCAT Dufers Point Dak-Gallup
		11. SEC., T., R., M. OR BLK. AND SURVEY OR IRMA 12-24N-8W NMPM
		12. COUNTY OR PARISH San Juan
		13. STATE NM

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data:

NOTICE OF INTENTION TO:

SUBSEQUENT REPORT ON:

TEST WATER SHUT-OFF	☐	PULL OR ALTER CASING	☐
FRACTURE TREAT	☒	MULTIPLE COMPLETE	☐
SHOOT OR ACIDIZE	☒	ABANDON*	☐
REPAIR WELL	☒	CHANGE PLANS	☐
(Other)			

WATER SHUT-OFF	☐	REPAIRING WELL	☐
FRACTURE TREATMENT	☐	ALTERING CASING	☐
SHOOTING OR ACIDIZING	☐	ABANDONMENT	☐
(Other)			


(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROMISED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting and proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Set a retrievable bridge plug at 6750'. Spot sand on top of same.
Selectively perforate 55 shots from 5920-6330. Cement zone with 75 sacks Class B Neat cement and squeeze same.
Drill out cement from 5920-6330.
Perforate 6286-6252, 6230-6176 and frac with 125,000 #'s 10-20 sand.
Perforate 6086-6024, 5974-5980 and frac with 75,000 #'s 10-20 sand.
Swab and place well in production. Retrievable bridge plug may be removed before we place the well in production or we may decide to test Gallup and remove retrievable bridge plug at a later date.

No additional surface damage will be caused by the above work.

Verbal notice of the above given to USGS 4-12-78



18. I hereby certify that the foregoing is true and correct

SIGNED Harry R. Byle TITLE President DATE 4-12-78

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY: