

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)


1. oil ☐ well gas ☒ well other ☐
2. NAME OF OPERATOR
El Paso Natural Gas Company
3. ADDRESS OF OPERATOR
P.O. Box 289, Farmington, NM
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1710'N, 1550'E
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

- TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:

- ☒
☐
☐
☐
☐
☐
☐
☐
☐
☐



5. LEASE
SF 079160
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
Rincon Unit
8. FARM OR LEASE NAME
Rincon Unit
9. WELL NO.
232
10. FIELD OR WILDCAT NAME
Otero Chacra
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 12, T-26-N, R-7-W
NMPM
12. COUNTY OR PARISH
Rio Arriba
13. STATE
New Mexico
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
6580' GL

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

- 12-4-80: Spudded well. Drilled surface hole. Ran 3 joints of 8 5/8", 24#, K-55 surface casing 128' set at 142'. Cemented w/ 106 cu. ft. cement. Circ. to usrface. WOC 12 hours; held 600#/30 minutes.
- 12-15-80: TD 3901'. Ran 144 joints 2 7/8", 6.4#, K-55 production casing 3891' set at 3901'. Baffle set at 3891'. Cemented w/ 743 cu. ft. cement. WOC 18 hours. Top of cement at 1250'.
- 12-30-80: PBTD 3891' Tested casing to 4000#, OK. Perfed: 3760, 3765, 3770, 3775, 3780, 3847, 3852' W/1 SPZ. Fraced w/ 37,000# 10/20 38,000 gal. wtr. Flushed w/ 1450 gal. wtr.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED A. P. Brisco TITLE Drilling Clerk DATE December 17, 1980

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

BW

NMOCC