

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☐ gas well ☒ other ☐  
2. NAME OF OPERATOR  
El Paso Exploration Company  
3. ADDRESS OF OPERATOR  
P.O. Box 289, Farmington, NM 87401  
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)  
790'S, 1850'E  
AT SURFACE:  
AT TOP PROD. INTERVAL:  
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐  
FRACTURE TREAT ☐  
SHOOT OR ACIDIZE ☐  
REPAIR WELL ☐  
PULL OR ALTER CASING ☐  
MULTIPLE COMPLETE ☐  
CHANGE ZONES ☐  
ABANDON\* ☐  
(other) ☐

SUBSEQUENT REPORT OF:


☐  
☒  
☐  
☐  
☐  
☐  
☐  
☐  
☐  
☐

RECEIVED

SEP 2 1980

U. S. GEOLOGICAL SURVEY

5. LEASE  
Jic. Cont. #152W  
6. IF INDIAN, ALLOTTEE OR TRIBE NAME  
Jicarilla  
7. UNIT AGREEMENT NAME  
8. FARM OR LEASE NAME  
Jicarilla 152 W  
9. WELL NO.  
5A  
10. FIELD OR WILDCAT NAME  
S. Blanco PC & Blanco MV  
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA  
Sec. 7, T-26-N, R-5-W  
NMPM  
12. COUNTY OR PARISH  
Rio Arriba  
13. STATE  
New Mexico  
14. API NO.  
15. ELEVATIONS (SHOW DF, KDB, AND WD)  
6959' GL



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

8-23-80: Perfed Point Lookout:  
5708,5713,5736,5756,5760,5764,5768,5712,5716,5820,5843,5870,5905,6054,6094' W/1 SPZ.  
Fraced w/ 39,000# 20/40 sand, 79,000 gal. wtr. Flushed w/ 7810 gal. wtr.

Perfed Cliff House & Menefee:  
5247,5252,5257,5331,5335,5340,5390 5395,5400,5434,5438,5488,5496,5544,5580,5636,5642,  
5682' W/1 SPZ. Fraced w/ 47,000# 20/40 sand, 88,700 gal. wtr. Flushed w/ 7777 gal. w  
wtr.

Perfed Pictured Cliffs:  
3478,3484,3490,3496,3502,3508,3513,3520,3536,3541,3545,3553,3558,3566,3581' W/1 SPZ.  
Fraced w/ 78,000# 10/20 sand, 88,000 gal. wtr. Flushed w/ 6890 gal. wtr.

Subsurface Safety Valve: Manu. and Type \_\_\_\_\_ Set @ \_\_\_\_\_ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE Drilling Clerk DATE August 28, 1980

(This space for Federal or State office use)

APPROVED BY [Signature] TITLE \_\_\_\_\_ DATE \_\_\_\_\_  
CONDITIONS OF APPROVAL, IF ANY:

SEP 02 1980

BY [Signature]  
FARMINGTON DISTRICT

\*See Instructions on Reverse Side

NMOCC