


UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir,  
Use "APPLICATION FOR PERMIT--" for such proposals

SUBMIT IN TRIPPLICATE



FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

5. Lease Designation and Serial No.  
SF 078064

6. If Indian, Allottee or Tribe Name

7. If Unit or CA. Agreement Designation

Carson Unit

13 #2

8. Well Name and No.  
Carson Unit NO. 21-13

9. API Well No.  
30-045-05444

10. Field and Pool, or Exploratory Area  
Bisti Lower Gallup

11. County or Parish, State  
San Juan County, New Mexico

1. Type of Well  
☐ Oil Well ☐ Gas Well ☒ Other Water Supply Well

2. Name of Operator  
Central Resources, Inc.

3. Address and Telephone No.  
P.O. Box 1247, Bloomfield, New Mexico 87413 (505)-632-3476

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
560.' FNL, 1880.' FWL, Sec 13, T25N, R12W

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☒ Notice of Intent  
☐ Subsequent Report  
☐ Final Abandonment Notice

☒ Abandonment  
☐ Recompletion  
☐ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☐ Other

☐ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Central Resources, Inc. intends to plug the well in accordance with regulations. Production equipment will be removed and the well will be plugged as specified. **Perforate and squeeze will be used unless casing can be recovered over the specified interval or there is evidence cement is in place behind the casing.**

Proposed procedure:

- Notify the Farmington BLM office at 505-599-8907 24 hours prior to commencement of plugging operations.
- Pull all retrievable downhole production equipment.
- Set a CIBP at 4750' and spot 50' of cement on top at top of Lower Gallup at 4760'.
- Spot a 100' cement plug from 3896' to 3796' across the top of the Mancos at 3846'.
- Spot a 100' cement plug from 2087' to 1987' across the top of the Menefee at 2037'.
- Spot a 100' cement plug from 1234' to 1134' across the top of the Pictured Cliffs at 1184'.
- Spot a 153' cement plug from 153' to surface across the surface casing shoe at 103'.
- Cut wellhead and install dry hole marker. Clear and remediate location.

Please take into account the number of existing P&A procedures, the number of P&A procedures you have requested and the available equipment and allow Central Resources, Inc. until the end of 2001 to complete this abandonment.

14. I hereby certify that the foregoing is true and correct

Signed Rodney L. Seale  
Rodney L. Seale

Title District Engineer

Date June 28, 2000

(This space for Federal or State office use)

Approved by \_\_\_\_\_ Title \_\_\_\_\_

Date 8/23/00

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any manner within its jurisdiction.

\*See Instruction on Reverse Side

# CENTRAL RESOURCES, INC.

## Carson Unit No. 21-13

Review Date:

11-1-95 by Giant

Elevation: 6356' GL, 6365' KB

Location: 660' FNL, 1880' FWL, Sec 13,  
T25-N, R12-W, San Juan County,  
New Mexico

Field: Bisti Lower Gallup

Zone: Lower Gallup

Perfs: 4860' - 4974'

Spud Date: April 15, 1958 12:00 AM

