

DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL ☐ GAS WELL ☒ OTHER ☐ 2. NAME OF OPERATOR Tenneco Oil Company 3. ADDRESS OF OPERATOR 1200 Lincoln Tower Bldg., Denver, Colorado 80203 4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 1650' FEL and 800' FSL	5. LEASE DESIGNATION AND SERIAL NO. N00-C-14-20-5235 6. IF INDIAN, ALLOTTEE OR TRIBE NAME Navajo 7. UNIT AGREEMENT NAME 8. FARM OR LEASE NAME Mountview Com - 26D 9. WELL NO. 1 10. FIELD AND POOL, OR WILDCAT Basin Dakota 11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 26, T 25N, R 10W 12. COUNTY OR PARISH 13. STATE San Juan New Mexico
14. PERMIT NO. 15. ELEVATIONS (Show whether DF, RT, GR, etc.) 6652' GR	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐

FRACTURE TREAT ☐

SHOOT OR ACIDIZE ☐

REPAIR WELL ☐

(Other) ☐

FULL OR ALTER CASING ☐

MULTIPLE COMPLETE ☐

ABANDON* ☐

CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐

FRACTURE TREATMENT ☐

SHOOTING OR ACIDIZING ☒

(Other) ☐

REPAIRING WELL ☐


ALTERING CASING ☐

ABANDONMENT* ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

6/12/74 - PBTD 6356'. Tested casing 1000 psi. OK.
 6/13/74 - WO tbg. Displaced hole w/Cond. POH laying dwn tbg. Tbg. string defective.
 6/14/74 - 6/18/74 - SD to inspect tbg.
 6/19/74 - WO Surf. equip.
 6/22/74 - Perforated casing S/csg gun 6286' - 6271' (15', 31 holes) 6200' - 6251' (9', 19 holes) 6240' - 6236' (4', 9 holes)
 6/23/74 - RU to frac. GIH w/tbg. Land tbg at 6156'. Remvd BOP & instal well head. SD Cond frac dwn tbg w/50,000# 20-40 SD, 10,000# 10-20 SD in 6 equal stgs. AIR 15 BPM at 5,000 psi. Break dwn psi 3400#, ISIP 3200#; 5 min SIP 3075#, 15 min SIP 2850#; TLTR 1385 bbl.
 6/24/74 - Prepare to test.



18. I hereby certify that the foregoing is true and correct

SIGNED Saul F. Rogers

TITLE Sr. Production Clerk

DATE 7/2/74

(This space for Federal or State office use)

APPROVED BY _____

TITLE _____

DATE _____

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side