

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> PLUG BACK <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. NOOC-14-20-5017	
b. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME Navajo	
2. NAME OF OPERATOR El Paso Natural Gas Company		7. UNIT AGREEMENT NAME	
3. ADDRESS OF OPERATOR PO Box 289, Farmington, NM 87401		8. FARM OR LEASE NAME Hostein Yazza	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)* At surface 1900' S, 1130' W At proposed prod. zone 1850' same		9. WELL NO. 1	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* 25 miles Southeast of Bloomfield, NM		10. FIELD AND POOL, OR WILDCAT Basin Dakota	
15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) 1130'		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 26, T-25-N, R-9-W NMPM	
16. NO. OF ACRES IN LEASE 160		12. COUNTY OR PARISH San Juan	
17. NO. OF ACRES ASSIGNED TO THIS WELL w/ 320.00		13. STATE NM	
18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. 9000'		20. ROTARY OR CABLE TOOLS Rotary	
21. ELEVATIONS (Show whether DF, RT, GR, etc.) 6562' GL		22. APPROX. DATE WORK WILL START*	

23. PROPOSED CASING AND CEMENTING PROGRAM				
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
13 3/4"	9 5/8"	32.3#	200'	224 cu.ft.circ. to surface
6 1/4"	4 1/2"	10.5#	6560'	1251 cu.ft. - 3 stages

1st stage cement - 401 cu.ft. to cover Gallup
2nd stage cement - 494 cu.ft. to cover Mesa Verde
3rd stage cement - 356 cu.ft. to cover Ojo Alamo

Selectively perforate and sandwater fracture the Dakota formation.

A 3000 psi WP and 6000 psi test double gate preventer equipped with blind and pipe rams will be used for blow out prevention on this well.

This gas is dedicated.

The W/2 of Section 26 is dedicated to this well.
IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED A. G. Luicks TITLE Drilling Clerk DATE 5-18-79

(This space for Federal or State office use)

PERMIT NO. _____ APPROVAL DATE _____

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

oh Erich

AYMAC

*See Instructions On Reverse Side

OIL CONSERVATION DIVISION

STATE OF NEW MEXICO
ENERGY AND MINERALS DEPARTMENTP. O. BOX 2088
SANTA FE, NEW MEXICO 87501Form C-102
Revised 10-1-78

All distances must be from the outer boundaries of the Section.

Operator EL PASO NATURAL GAS COMPANY		Lease HOSTEIN YAZ7A (NAVAJO ALLOT-NOO C-14-20-5017)		Well No. 1
Unit Letter L	Section 26	Township T25N	Range R7W	County San Juan
Actual Postage Location of Well: 1850 feet from the South line and 1130 feet from the West line				
Ground Level Elev. 6562	Producing Formation Dakota	Pool Basin Dakota	Dedicated Acreage: 320.00 Acres	


1. Outline the acreage dedicated to the subject well by colored pencil or hatchure marks on the plat below.
2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty).
3. If more than one lease of different ownership is dedicated to the well, have the interests of all owners been consolidated by communitization, unitization, force-pooling, etc?

☒ Yes ☐ No If answer is "yes," type of consolidation Comm -

If answer is "no," list the owners and tract descriptions which have actually been consolidated. (Use reverse side of this form if necessary.)

No allowable will be assigned to the well until all interests have been consolidated (by communitization, unitization, forced-pooling, or otherwise) or until a non-standard unit, eliminating such interests, has been approved by the Division.

NOTE: THIS PLAT IS REISSUED TO REFLECT A MOVED LOCATION TO COMPLY W/REQUIREMENTS. 6-1-79



CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.

D. G. Guico

Name

Drilling Clerk

Position

El Paso Natural Gas

Company

June 5, 1979

Date

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my knowledge and belief.

Date Surveyed

May 31, 1979Registered Professional Engineer
and/or Land SurveyorFred B. Kerr Jr.

Certificate No.


3950

Multi-Point Surface Use Plan

Hostein Yazza #1

1. Existing Road - Please refer to Map No. 1 which shows the existing roads. New roads which will be required have been marked on this map. All existing and new roads will be properly maintained during the duration of this project.
2. Planned Access Roads - Please refer to Map No. 1. The grade of the access roads will be consistent with that of the local terrain. The road surface will not exceed twenty feet (20') in width. Upon completion of the project, the access road will be adequately drained to control soil erosion. Drainage facilities may include ditches, water bars, culverts or any other measure deemed necessary by trained Company personnel to insure proper drainage. Gates and/or cattleguards will be installed if necessary.
3. Location of Existing Wells - Please refer to Map No. 2.
4. Location of Tank Batteries, Production Facilities, and Production Gathering and Service Lines - Please refer to Maps No. 1 and No. 2. Map No. 2 shows the existing gas gathering lines. Map No. 1 shows the existing roads and new proposed access roads. All known production facilities are shown on these two maps.
5. Location and Type of Water Supply - Water for the proposed project will be obtained from Huerfano Water Well #2.
6. Source of Construction Materials - No additional materials will be required to build either the access road or the proposed location.
7. Methods of Handling Waste Materials - All garbage and trash materials will be put into a burn pit shown on the attached Location Plat No. 1. When clean-up operations are begun on the proposed project, the burn pit with its refuse will be buried to a depth of at least three feet (3'). A latrine, the location of which is also shown on Plat No. 1,

7. cont'd. will be provided for human waste. If large amounts of liquids are left in the reserve pit after completion of the project, the pit will be fenced until the liquids have had adequate time to dry. The location clean-up will not take place until such time as the reserve pit can be properly covered over to prevent run-off from carrying any of these materials into the watershed. No earthen pit will be located on natural drainages; all earthen pits will be so constructed as to prevent leakage from occurring.
8. Ancillary Facilities - No camps or airstrips will be associated with this project.
9. Wellsite Layout - Please refer to the attached Plat No. 1.
10. Plans for Restoration of the Surface - After completion of the proposed project, the location will be cleaned and leveled. The location will be left in such a condition that will enable reseeding operations to be carried out. Seed mixture as designated by the responsible government agency will be used. The reseeding operation will be performed during the time period set forth by the regulatory body. The location production equipment will be painted as designated by the responsible government agency.
11. Other Information - The terrain is sagebrush flats with sagebrush growing. Cattle, sheep and horses occasionally graze the proposed project site.
12. Operator's Representative - W.D. Dawson, PO Box 990, Farmington, NM
13. Certification - I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by El Paso Natural Gas Company and its contractors and sub-contractors in conformity with this plan and the terms and conditions under which it is approved.



L. A. Aimes
Project Drilling Engineer

May 11, 1979

Operation Plan - Hostein Yazza #1

I. Location: 1900'S, 1130'W, Section 26, T-25-N, R-9-W, San Juan County, NM
Field: Basin Dakota Elevation: 6572'GL

II. Geology:

A. Formation Tops:	Ojo Alamo	990'	Point Lookout	4160'
	Kirtland	1160'	Gallup	5250'
	Fruitland	1595'	Greenhorn	6106'
	Pic.Cliffs	1793'	Graneros	6212'
	Lewis	1870'	Dakota	6310'
	Mesa Verde	3318'	Total Depth	6560'

B. Logging Program: Induction Electric and Gamma Ray Density at TD.

C. Coring: none

III. Drilling:

A. Mud Program: mud from surface to Total Depth.

IV. Materials:

A. Casing Program:	<u>Hole Size</u>	<u>Depth</u>	<u>Csg.Size</u>	<u>Wt.&Grade</u>
	12 1/4"	200'	8 5/8"	24.0# K-55
	7 7/8"	6560'	4 1/2"	10.5# K-55

B. Float Equipment: 8 5/8" surface casing - B&W guide shoe (Prod.No.FC-06)
4 1/2" production casing - Baker guide shoe (Prod. No. 102-01) and self-fill insert valve (Prod. No. 177-13). Two Baker multiple stage cementers (Prod.No. 200-03) equipped for three stage cementing. Set tool for second stage at 4760' and tool for third stage at 1970'. Run 20 Baker centralizers (Prod.No. 200-03) spaced as follows: one on each of the bottom 8 joints, one below each stage tool and five above each stage tool spaced every other joint.

C. Tubing: 6560' of 2 3/8", 4.7#, J-55 tubing, common pump seating nipple and Baker expendable check valve with drill type guide.

D. Wellhead Equipment: Gray 8" - 2000 psi wellhead, Drawing #E-14921. Gray representative to set slips on the production casing.

V. Cementing:

Surface casing (12 1/4" x 8 5/8") - use 160 sks. of Class "B" cement with 1/4# gel-flake per sack and 3% calcium chloride (189 cu.ft. of slurry, 100% excess to circulate). WOC 12 hours. Test to 600#/30 min.

Operations Plan - Hostein Yazza #1

V. Cementing, cont'd.


Production casing - (7 7/8" x 4 1/2")

First stage - use 170 sks. of 65/35 Class "B" Pozmix with 6% gel and 2% calcium chloride mixed with 8.3 gallons water per sack followed by 100 sks. 50/50 Class "B" Pozmix with 2% gel, 2% calcium chloride and 1/4# fine tuf-plug per cu.ft. (401 cu.ft. of slurry, 25% excess to cover the Gallup).

Second stage - circulate mud for 2 hours, then cement with 305 sks. of 65/35 Class "B" Pozmix with 6% gel and 2% calcium chloride and 8.3 gallons of water per sack (494 cu.ft. of slurry, 50% excess to cover the Mesa Verde)..


Third stage - circulate mud for 2 hours, then cement using 220 sks. Class "B" Pozmix with 6% gel and 2% calcium chloride mixed with 8.3 gallons water per sack (356 cu.ft. of slurry, 60% excess to fill to base of Ojo Alamo). Run temperature survey on top stage only at 8 hours. WOC 18 hours.

Typical B.O.P. Installation
for Dakota Well



Series 900 Double Gate BOP, rated
at 3000 psi Working Pressure

When gas drilling operations begin a Shaffer type
50 or equivalent rotating head is installed on top of
the flow nipple and the flow line is converted into
a blowie line.



PRT.				SEP.				DATE				TO				W.O.			
PRINT RECORD																			
ENG. REC.								DATE											
DRAWN								J.L.H. 8-16-78											
CHECKED																			
CHECKED																			
PROJ. APP.																			
DESIGN																			
W.O.																			

El Paso Natural Gas Company


TYPICAL LOCATION PLAT FOR
MESAVERDE OR DAKOTA DRILL SITE

SCALE: 1" = 50'

DWG. NO.

REV.

EL PASO NATURAL GAS COMPANY
Hostein Yazza #1
SW 26-25-9



MAP #1

LEGEND OF RIGHT-OF-WAYS


EXISTING ROADS	—————
EXISTING PIPELINES	+ + +
EXISTING ROAD & PIPELINE	+ + +
PROPOSED ROADS	—————
PROPOSED PIPELINES	+ + +
PROPOSED ROAD & PIPELINE	+ + +

EL PASO NATURAL GAS COMPANY

Hostein Yazza #1

SW 26-25-9

R-9-W



Map #2
Proposed Location