


UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir,  
Use "APPLICATION FOR PERMIT--" for such proposals.

SUBMIT IN TRIPLICATE



FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

5. Lease Designation and Serial No.  
SF 078064

6. If Indian, Allottee or Tribe Name

7. If Unit or CA. Agreement Designation

Carson Unit WWF 13 #1

1. Type of Well  
☐ Oil Well ☐ Gas Well ☒ Other Water Supply Well

8. Well Name and No.  
1-13

2. Name of Operator  
Central Resources, Inc.

9. API Well No.  
30045 30226

3. Address and Telephone No.  
P.O. Box 1247, Bloomfield, New Mexico 87413 (505)-632-3476

10. Field and Pool, or Exploratory Area  
Mesaverde

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
1320' FSL, 660' FEL, Sec 13, T25N, R12W

11. County or Parish, State  
San Juan County, New Mexico

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☒ Notice of Intent  
☐ Subsequent Report  
☐ Final Abandonment Notice

☒ Abandonment  
☐ Recompletion  
☐ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☐ Other

☐ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Central Resources, Inc. intends to plug the well in accordance with regulations. Production equipment will be removed and the well will be plugged as specified. **Perforate and squeeze will be used unless casing can be recovered over the specified interval or there is evidence cement is in place behind the casing.**

Proposed procedure:

- Notify the Farmington BLM office at 505-599-8907 24 hours prior to commencement of plugging operations.
- Pull all retrievable downhole production equipment.
- Set a cement retainer at 1900' and squeeze w/ 100 sx leaving 50' on top of retainer.
- Set a 100' cement plug from 1055' to 1155' across the Pictured Cliffs at 1105'.
- Set a 100' cement plug from 647' to 747' across the Fruitland Coal at 697'.
- Set and/or squeeze a 100' cement plug from 100' to surface to cover the surface casing shoe at 56'.
- Cut wellhead and install dry hole marker. Clear and remediate location.

Please take into account the number of existing P&A procedures, the number of P&A procedures you have requested and the available equipment and allow Central Resources, Inc. until the end of 2001 to complete this abandonment.

14. I hereby certify that the foregoing is true and correct

Signed Rodney L. Seale Title District Manager Date April 24, 2000  
Rodney L. Seale

(This space for Federal or State office use)

Approved by \_\_\_\_\_ Title \_\_\_\_\_ Date 5/22/00  
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any manner within its jurisdiction.

\*See Instruction on Reverse Side

# CENTRAL RESOURCES, INC.

## Carson Unit "13" No. 1 WSW

Review Date: 4-22-00 by Rod Seale

Elevation: 6400' GL, 6412' KB

Location: 1320' FSL, 660' FEL, Sec 13, 25-N, 12-W, San Juan County, New Mexico

Field:

Zone: Menefee

Perfs: 1956' - 2541'

Spud Date: March 27, 1957 12:00 AM

