

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☒ well other ☐
2. NAME OF OPERATOR
AMOCO PRODUCTION COMPANY
3. ADDRESS OF OPERATOR
501 Airport Drive Farmington, NM 87401
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
1190' FSL x 1165' FEL,
AT SURFACE: Section 25, T-28-N, R-4-W
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:		SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF	<input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>	<input type="checkbox"/>
(other) <u>Spud & Set Casing</u>		

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Spudded 12-1/4" hole on 1/14/78. Drilled to 314'. Set 8-5/8" 24# K-55 casing at 314' with 250 sx Class "B", 2% CaCl₂. Circulated cement. Pressure tested to 600#; held OK.

Drilled 7-7/8" hole to a total depth of 4350'. Set 4-1/2" 10.5# K-55 casing at 4350' with 1150 sx Class "B", 50:50 Poz, 6% gel, 2 lbs. medium turp plug per sx. Tailed in with 100 sx Class "B" Neat.

Subsurface Safety Valve: Manu. and Type _____

18. I hereby certify that the foregoing is true and correct



Original Signed By E. E. SVOBODA TITLE Area Adm. Supvr. DATE 2/14/78

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

5. LEASE
NM 14919
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
Valencia Canyon Unit
7. UNIT AGREEMENT NAME
Valencia Canyon Unit
8. FARM OR LEASE NAME
Choza Mesa Pictured Cliffs
9. WELL NO.
19
10. FIELD OR WILDCAT NAME
Choza Mesa Pictured Cliffs
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
SE/4 SE/4 Section 25,
T-28-N, R-4-W
12. COUNTY OR PARISH
Rio Arriba
13. STATE
NM
14. API NO.
30-039-21597
15. ELEVATIONS (SHOW DF, KDB, AND WD)
7243' GL

(NOTE: Report results of multiple completion or zone change on Form 9-330.)



*See Instructions on Reverse Side

U. S. GEOLOGICAL SURVEY
DURANGO, COLO.