

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☐ gas well ☒ other ☐

2. NAME OF OPERATOR
El Paso Natural Gas Company

3. ADDRESS OF OPERATOR
P.O. Box 289, Farmington, NM

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 800'S, 1520'E
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:	SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF <input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	<input checked="" type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE <input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES <input type="checkbox"/>	<input type="checkbox"/>
ABANDON* <input type="checkbox"/>	<input type="checkbox"/>
(other) <input type="checkbox"/>	<input type="checkbox"/>

5. LEASE
SF 079290 A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
San Juan 28-7 Unit

8. FARM OR LEASE NAME
San Juan 28-7 Unit

9. WELL NO.
51A

10. FIELD OR WILDCAT NAME
Undes PC & Blanco MV


11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 24, T-28-N, R-7-W
NMPM

12. COUNTY OR PARISH 13. STATE
Rio Arriba New Mexico

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)
6243' GL

(NOTE: Report results of multiple completions or zone changes on Form 9-330.)



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

- 3-23-81: PBDT 5573'. Tested casing to 3500#, Held OK. Perfed Point Lookou 5190, 5194, 5202, 5208, 5224, 5240, 5254, 5260, 5285, 5293, 5347, 5357, 5393, 5435, 5461, 5487, 5501, 5550' W/1 SPZ. Fraced w/ 51,000# 20/40 sand, 111,240 gal. wtr. Flushed w/ 6680 gal. wtr.
- 3-24-81: Perfed C.H. & Menefee: 4610, 4624, 4631, 4666, 4674, 4720, 4729, 4860, 4923, 5021, 5090, 5100, 5110' W/1 SPZ. Fraced w/ 51,000# 20/40 sand, 153,000 gal. wtr. Flushed w/ 6300 gal. wtr.
Perfed Pic. Cliffs: 2970-80, 2980-90, 2998-3013, 3018-30, 3040-47' W/15 SPZ. Fraced w/ 49,940# 10/20 sand, 69,940 gal. wtr. Flushed w/ 5040 gal. wtr.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED A. P. Duico TITLE Drilling Clerk DATE April 6, 1981

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

ACCEPTED FOR RECORD

NMOCC

APR 09 1981

FARMINGTON DISTRICT
BY E. J. [Signature]