## **UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT**

 a.	Type of Work	5. Lease Number
1.	DRILL	SF-079521 C70 7
	DKILL	Unit Reporting Number
b.	Type of Well	6. If Indian, All. or Tribe
	GAS GAS	277
	Operator	Unit Agreement Name
	RESOURCES Oil & Gas Company FEB 20	/ED N
	Address & Phone No. of Operator - Oil CON	By/Farm or Lease Name
-	PO Box 4289, Farmington, NM 7499 DIST.	San Juan 28-5 Unit Well Number
	(505) 326-9700	56M
<u> </u>	Location of Well	10. Field, Pool, Wildcat
	1650' FSL, 661' FEL	Blanco MV/Basin DK
	·	11. Sec., Twn, Rge, Mer. (NMPM)
	Latitude 36° 36.9, Longitude 107° 22.5	Sec. 32, T-28-N, R-5-W API# 30-039- 26255
14.	Distance in Miles from Nearest Town	12. County 13. State
	40 miles from Blanco	Rio Arriba NM
15.	Distance from Proposed Location to Nearest Property or L	ease Line
16.	Acres in Lease	17. Acres Assigned to Well
	, 1000 in 2000	318.72 S/2
18.	Distance from Proposed Location to Nearest Well, Drlg, C	ompl, or Applied for on this Lease
	1500' This action is subject to technical and	20. Rotary or Cable Tools
19.	Proposed Depteural review pursuant to 43 CFR 3165.3 7728' and appeal pursuant to 43 CFR 3165.4.	Rotary
21.	Elevations (DF, FT, GR, Etc.)	22. Approx. Date Work will Start ARE DRILLING OPERATIONS AUTHORIZED ARE
	6475' GR	GIRLECT TO COMPLIANCE WITH ATTACHES
23.	Proposed Casing and Cementing Program	"GENERAL REQUIREMENTS"
_••	See Operations Plan attached	
	Marie / lane	10-19-99
24.	Authorized by: Regulatory/Compliance Adminis	
	Regulatory/Compilance Admitted	
PFR	MIT NO. APPRO	OVAL DATE
		<del></del>

Archaeological Report to be submitted
Threatened and Endangered Species Report to be submitted
NOTE: This format is issued in lieu of U.S. BLM Form 3160-3
Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or presentations as to any matter within its jurisdiction.

TO THE CONTRACT OF THE SHORT OF THE CONTRACT O

Marie Land

DISTRICT I P.O. Box 1980, Hobbs, N.M. 88241-1980

P.O. Drawer DD, Artesia, N.M. 88211-0719

State of New Mexico Energy, Minerals & Natural Resources Department

Form C-102 Revised February 21, 1994 Instructions on back

Submit to Appropriate District Office

OIL CONSERVATION DIVISION

State Lease — 4 Copies

1000 Rio Brazos Rd., Aztec, N.M. 87410

DISTRICT II

P.O. Box 2088 Santa Fe, NM 87504-2088 pro -2 PM 1: 22

☐ AMENDED REPORT

Fee Lease - 3 Copies

PO Box 2088, Santa Fe, NM 87504-2088

12 Dedicated Acres

5/318.72

Mini te fniol E


WELL LOCATION AND ACREAGE DEDICATION PLAT

'API Number			-	<sup>2</sup> Pool Code	<sup>3</sup> Pool Name						
30-039-26255 72319/715					Blanco Mesaverde/Basin Dak				akota	kota	
<sup>4</sup> Property Co			Property Name					<sup>4</sup> Well Number			
7460		SAN JUAN 28-5 UNIT						1	56 <b>M</b>		
OGRID No.				*Operator Name					* Elevation 6475'		
14538				BURLINGTON RESOURCES OIL & GAS COMPANY							
	<del></del>	-	*******		<sup>10</sup> Surface	Location		•			
UL or lot no.	Section 32	Township 28-N	Ran <b>ge</b> 5-W	Lot Idn	Feel from the 1650	North/South line SOUTH	Feet from the 661	East/West EAST		County RIO ARRIBA	
			<sup>11</sup> Botto	m Hole	Location I	f Different Fr	om Surfac <b>e</b>				
UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West	line	County	

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

19 Order No.

34 Consolidation Code



#### OPERATIONS PLAN

Well Name: San Juan 28-5 Unit #56M

Location: 1650'FSL, 661'FEL, Sec 32, T-28-N, R-5-W

Rio Arriba County, NM

Latitude 36° 36.9, Longitude 107° 22.5

Formation: Blanco Mesa Verde/Basin Dakota

Elevation: 6475' GL

Formation Tops:	Top	Bottom	Contents
Surface	San Jose	2610'	
Ojo Alamo	2610'	2787 <b>′</b>	aquifer
Kirtland	2787 <b>'</b>	2918 <b>'</b>	gas
Fruitland	2918 <b>'</b>	3300 <b>'</b>	gas
Pictured Cliffs	330 <b>0'</b>	3402'	gas
Lewis	3 <b>402'</b>	38 <b>86'</b>	gas
Intermediate TD	3502'		
Mesa Verde	388 <b>6′</b>	4252 <b>'</b>	gas
Chacra	4252'	4976 <b>'</b>	gas
Massive Cliff House	4976'	5140'	gas
Menefe <b>e</b>	5140'	5468'	gas
Massive Point Lookout	5468'	5971 <b>'</b>	gas
Mancos	5971 <b>'</b>	6637 <b>′</b>	gas
Gallup	6637 <b>'</b>	738 <b>8′</b>	gas
Greenhorn	738 <b>8</b> '	7450'	gas
Graneros	7450'	7490 <b>'</b>	gas
Dakota	7490'		gas
TD (4 1/2"liner)	7728'		-

## Logging Program:

Cased hole - CBL-CCL-GR - TD to surface

## Mud Program:

Interval	Type	Weight	Vis.	Fluid Loss
	Spud	8.4-9.0	40-50	no control
200- 3502'	LSND	8.4-9.0	30-60	no control
3502- 7728'	Gas	n/a	n/a	n/a

Pit levels will be visually monitored to detect gain or loss of fluid control.

# Casing Program (as listed, the equivalent, or better):

Hole Size	Depth Interval 0' - 200'	Csg.Size 9 5/8"		Grade WC-50
8 3/4"	0' - 3502'	7 <b>"</b>	20.0#	
6 1/4"	3402' - 7728'	4 1/2"	10.5#	

#### Tubing Program:

0' - 7728' 2 3/8" 4.7# J-55

# BOP Specifications, Wellhead and Tests:

# Surface to Intermediate TD -

11" 2000 psi minimum double gate BOP stack (Reference Figure #1). After nipple-up prior to drilling out surface casing, rams and casing will be tested to 600 psi for 30 minutes.

## Intermediate TD to Total Depth -

11" 2000 psi minimum double gate BOP stack (Reference Figure #1). After nipple-up prior to drilling out intermediate casing, rams and casing will be tested to 1500 psi for 30 minutes.

### Surface to Total Depth -

2" nominal, 2000 psi minimum choke manifold (Reference Figure #3).

## Completion Operations -

7 1/16" 2000 psi double gate BOP stack (Reference Figure #2). After nipple-up prior to completion, pipe rams, casing and liner top will be tested to 2000 psi for 15 minutes.

#### Wellhead -

9 5/8" x 7" x 2 3/8" x 3000 psi tree assembly.

#### General -

- Pipe rams will be actuated once each day and blind rams will be actuated once each trip to test proper functioning.
- An upper kelly cock valve with handle available and drill string valves to fit each drill string will be available on the rig floors at all times.
- BOP pit level drill will be conducted weekly for each drilling crew.
- All BOP tests and drills will be recorded in daily drilling reports.
- Blind and pipe rams will be equipped with extension hand wheels.

#### Cementing:

9 5/8" surface casing - cement with 159 sx Class "B" cement with 1/4# flocele/sx and 3% calcium chloride (188 cu.ft. of slurry, 200% excess to circulate to surface). WOC 8 hrs. Test casing to 600 psi for 30 minutes.

Saw tooth guide shoe on bottom. Bowspring centralizers will be run in accordance with Onshore Order #2.

# 7" intermediate casing -

Lead w/319 sx Class "B" w/3% sodium metasilicate, 7# gilsonite/sx and 1/2# flocele/sx. Tail w/90 sx 50/50 Class "B" Poz w/2% calcium chloride, 2% gel (1035 cu.ft. of slurry, 100% excess to circulate to surface.) WOC minimum of 8 hours before drilling out intermediate casing. If cement does not circulate to surface, a CBL will be run during completion operations to determine TOC. Test casing to 1500 psi for 30 minutes.

7" intermediate casing alternative two stage: Stage collar at 2818'. First stage: cement with w/106 sx Class "B" 50/50 poz w/2% gel, 2% calcium chloride, 0.5 pps Cellophane. Second stage: 291 sx Class "B" with 3% sodium metasilicate, 1/2 pps Cellophane, 10 pps Gilsonite (1035 cu.ft., 100% excess to circulate to surface).

Cement nose guide shoe on bottom with float collar spaced on top of shoe joint. Bowspring centralizers spaced every other joint off bottom, to the base of the Ojo Alamo at 2787'. Two turbolating centralizers at the base of the Ojo Alamo at 2787'. Bowspring centralizers spaced every fourth joint from the base of the Ojo Alamo to the base of the surface casing.

### 4 1/2" Production Liner -

Cement to cover minimum of 100' of 4  $1/2" \times 7"$  overlap. Lead with 474 sx 50/50 Class "H" Poz with 2% gel, 0.25# flocele/sx, 5# gilsonite/sx, 0.2% retardant and 0.4% fluid loss additive (622 cu.ft.), 40% excess to cement 4  $1/2" \times 7"$  overlap). WOC a minimum of 18 hrs prior to completing.

Cement float shoe on bottom with float collar spaced on top of shoe joint.

To facilitate higher hydraulic stimulation completion work, no liner hanger will be used. In its place, a long string of 4 1/2" casing will be run and cemented with a minimum of 100' of cement overlap between the 4  $1/2" \times 7"$  casing strings. After completion of the well, a 4 1/2" retrievable bridge plug will be set below the top of cement in the 4  $1/2" \times 7"$  overlap. The 4 1/2" casing will then be backed off above the top of cement in the 4 1/2" x 7" overlap and laid down. The 4 1/2" bridge plug will then be retrieved and the production tubing will be run to produce the well.

• If hole conditions permit, an adequate water spacer will be pumped ahead of each cement job to prevent cement/ mud contamination or cement hydration.

# Special Drilling Operations (Gas/Mist Drilling):

The following equipment will be operational while gas/mist drilling:

- An anchored blooie line will be utilized to discharge all cuttings and circulating medium to the blow pit a minimum of 100' from the wellhead.
- The blooie line will be equipped with an automatic igniter or pilot
- Compressors will be located a minimum of 100' from the wellhead in the opposite direction from the blooie line.
- Engines will have spark arresters or water cooled exhaust.
- Deduster equipment will be utilized.
- The rotating head will be properly lubricated and maintained.
- A float valve will be utilized above the bit.
- Mud circulating equipment, water, and mud materials will be sufficient to maintain control of the well.

## Additional Information:

- The Dakota and Mesa Verde formations will be completed and commingled.
- No abnormal temperatures or hazards are anticipated.
- Anticipated pore pressures are as follows:

Fruitland Coal 800 psi 800 psi Pictured Cliffs 700 psi Mesa Verd**e** 2500 psi Dakota

- Sufficient LCM will be added to the mud system to maintain well control, if lost circulation is encountered.
- The south half of Section 32 is dedicated to the Mesaverde and the Dakota in this well.

•		M	ded.	idated.	
Dr	illing	Engi	neer		

10/20/99 Date

