



(SUBMIT IN TRIPLICATE)



APPROVED

UNITED STATES
DEPARTMENT OF THE INTERIOR
SEP 17 1962 GEOLOGICAL SURVEYIndian Agency Wichita Falls

Allottee

Lease No. 2-110-110-0107-AP. T. McGRAITH
Oil District Engineer

SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL	<input checked="" type="checkbox"/>	SUBSEQUENT REPORT OF WATER SHUT-OFF	
NOTICE OF INTENTION TO CHANGE PLANS		SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING	
NOTICE OF INTENTION TO TEST WATER SHUT-OFF		SUBSEQUENT REPORT OF ALTERING CASING	
NOTICE OF INTENTION TO REDRILL OR REPAIR WELL		SUBSEQUENT REPORT OF REDRILLING OR REPAIR	
NOTICE OF INTENTION TO SHOOT OR ACIDIZE		SUBSEQUENT REPORT OF ABANDONMENT	
NOTICE OF INTENTION TO PULL OR ALTER CASING		SUPPLEMENTARY WELL HISTORY	
NOTICE OF INTENTION TO ABANDON WELL			

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

U. S. GEOLOGICAL SURVEY
FARMINGTON, NEW MEXICO

September 17, 1962

Well No. 27-3 is located 1270 ft. from S line and 1270 ft. from W line of sec. 24SW/4 - Sec. 24
(1/4 Sec. and Sec. No.)27N
(Twp.)9W
(Range)27N
(Meridian)Blanco Mountains
(Field)San Juan
(County or Subdivision)New Mexico
(State or Territory)The elevation of the derrick floor above sea level is 6100 ft. (est.)

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

It is our intention to Drill Well No. 27-3 to around 1400' to test Mosaverts formation. Our casing program is as follows:200' - 6-5/8" OD 24# J-55 Casing - To be cemented w/200 sacks cement. Cement to be circulated to surface.1400' - 4-1/2" OD 12.5# J-55 Casing - Cement in 2 stages as follows: 1st Stage: Cement w/250 sha. 90% pozzol and 90% reg. w/2% gel and 12 1/2 #/gal silicate added per sack around casing shoe. 2nd Stage: A DV tool will be run and set at a point below the Pictured Cliffs formation and 560 sacks 90% pozzol and 90% reg. cement will be pumped through tool to cover Pictured Cliffs formation and circulate to surface.The designated Drilling Unit is W/2 Section 24-27N-9W.

I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company SKELLY OIL COMPANYBox 200Address Blanco Mountains
San Juan, New Mexico

By

Title

Asst. Dist. Eng.

[illegible]