

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK



1a. TYPE OF WORK DRILL ☒ DEEPEN ☐ PLUG BACK ☐			5. LEASE DESIGNATION AND SERIAL NO. W 078902		
b. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER ☐ SINGLE ZONE ☒ MULTIPLE ZONE ☐			6. IF INDIAN, ALLOTTEE OR TRIBE NAME		
2. NAME OF OPERATOR PAN AMERICAN PETROLEUM CORPORATION			7. UNIT AGREEMENT NAME Gallegos Canyon Unit		
3. ADDRESS OF OPERATOR P. O. Box 480, Farmington, New Mexico			8. FARM OR LEASE NAME		
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)* At surface 790' FNL & 790' FNL At proposed prod. zone Same			9. WELL NO. 247		
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* 8 miles southeast of Farmington, New Mexico			10. FIELD AND POOL, OR WILDCAT Basin Dakota		
16. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) 790'		16. NO. OF ACRES IN LEASE 43,146.62	17. NO. OF ACRES ASSIGNED TO THIS WELL 320.14		
18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. 1100' (PC)		19. PROPOSED DEPTH 6,100'	20. ROTARY OR CABLE TOOLS Rotary		
21. ELEVATIONS (Show whether DP, RT, GR, etc.) To be reported later			22. APPROX. DATE WORK WILL START* March 9, 1966		

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8"	24#	350'	200 sacks
7-7/8"	4-1/2"	10.5#	6100'	1400 sacks (Two stage tool not 100' below base of Mesaverde with possible third stage tool set below Pictured Cliffs)

Completion will be determined upon reaching total depth.

Copies of Location Plat are attached.



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. ORIGINAL SIGNED BY
G. W. Eaton, Jr.
SIGNED **G. W. Eaton, Jr.** TITLE **Area Engineer** DATE **March 7, 1966**
(This space for Federal or State office use)

PERMIT NO. _____ APPROVAL DATE _____
APPROVED BY *Gu* TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

*See Instructions On Reverse Side

Instructions

General: This form is designed for submitting proposals to perform certain well operations, as indicated, on all types of lands and leases for appropriate action by either a Federal or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 1: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable State or Federal regulations concerning subsequent work proposals or reports on the well.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on this reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal or State agency offices.

Items 15 and 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective production zone.

Item 22: Consult applicable Federal or State regulations, or appropriate officials, concerning approval of the proposal before operations are started.