

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

(Other instructions on
reverse side)

30-045-23852

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK		DRILL <input checked="" type="checkbox"/>		DEEPEN <input type="checkbox"/>		PLUG BACK <input type="checkbox"/>	
b. TYPE OF WELL		OIL WELL <input type="checkbox"/>		GAS WELL <input checked="" type="checkbox"/>		OTHER <input type="checkbox"/>	
2. NAME OF OPERATOR		El Paso Natural Gas Company		SINGLE ZONE <input type="checkbox"/>		MULTIPLE ZONE <input checked="" type="checkbox"/>	
3. ADDRESS OF OPERATOR		PO Box 289, Farmington, NM 87401		7. UNIT AGREEMENT NAME			
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*)		At surface 1690'S, 1080'E		8. FARM OR LEASE NAME		Jones A	
At proposed prod. zone same				9. WELL NO.		6A	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*		11 miles southeast of Blanco, NM		10. FIELD AND POOL, OR WILDCAT		Blanco Mesa Verde	
15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any)		950		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA		Sec. 14, T-28-N, R-8-W	
16. NO. OF ACRES IN LEASE		1851.96		12. COUNTY OR PARISH		San Juan	
17. NO. OF ACRES ASSIGNED TO THIS WELL		E/ 320.00		13. STATE		NM	
18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.		1000'		19. PROPOSED DEPTH		5597'	
20. ROTARY OR CABLE TOOLS		Rotary		21. ELEVATIONS (Show whether DF, RT, GR, etc.)		6367' GL	
22. APPROX. DATE WORK WILL START*				23. PROPOSED CASING AND CEMENTING PROGRAM			
24. SIZE OF HOLE		25. SIZE OF CASING		26. WEIGHT PER FOOT		27. SETTING DEPTH	
13 3/4"		9 5/8"		36.0#		200'	
8 3/4"		7"		20.0#		3285'	
6 1/4"		4 1/2" liner		10.5#		3135-5597'	
28. QUANTITY OF CEMENT		29. QUANTITY OF CEMENT		30. QUANTITY OF CEMENT		31. QUANTITY OF CEMENT	
224 cu.ft. to circulate		301 cu.ft. to cover Ojo Alamo		428 cu.ft. to circ. liner			

Selectively perforate and sandwater fracture the Mesa Verde formation.

A 3000 psi WP and 6000 psi test double gate preventer equipped with blind and pipe rams will be used for blow out prevention on this well.

This gas is dedicated.

The E/2 of Section 14 is dedicated to this well.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED D. G. Buico TITLE Drilling Clerk DATE 9-20-79

(This space for Federal or State office use)

PERMIT NO. _____ APPROVAL DATE _____

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY : _____

***See Instructions On Reverse Side**

All distances must be from the outer boundaries of the Section.

Operator EL PASO NATURAL GAS COMPANY			Lease JONES A (SF-078390)		Well No. 6A
Unit Letter I	Section 14	Township 28N	Range 8W	County San Juan	
Actual Footage Location of Well: 1690 feet from the South line and 1080 feet from the East line					
Ground Level Elev. 6367	Producing Formation Mesa Verde		Pool Blanco Mesa Verde	Dedicated Acreage: 320.00 Acres	

1. Outline the acreage dedicated to the subject well by colored pencil or hachure marks on the plat below.
2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty).
3. If more than one lease of different ownership is dedicated to the well, have the interests of all owners been consolidated by communitization, unitization, force-pooling, etc?

☐ Yes ☐ No If answer is "yes," type of consolidation _____

If answer is "no," list the owners and tract descriptions which have actually been consolidated. (Use reverse side of this form if necessary.) _____

No allowable will be assigned to the well until all interests have been consolidated (by communitization, unitization, forced-pooling, or otherwise) or until a non-standard unit, eliminating such interests, has been approved by the Commission.

	CERTIFICATION	
	I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.	
	<i>A. J. Busio</i> Name: Drilling Clerk	
	Position: El Paso Natural Gas Co.	
	Date: September 20, 1979	
	Date Surveyed: August 28, 1979	
	Registered Professional Engineer and/or Land Surveyor: <i>Fred B. Kerr Jr.</i> Fred B. Kerr Jr.	
	Certificate No.: 3950	

Multi-Point Surface Use Plan

Jones A #6A

1. Existing Road - Please refer to Map No. 1 which shows the existing roads. New roads which will be required have been marked on this map. All existing and new roads will be properly maintained during the duration of this project.
2. Planned Access Roads - Please refer to Map No. 1. The grade of the access roads will be consistent with that of the local terrain. The road surface will not exceed twenty feet (20') in width. Upon completion of the project, the access road will be adequately drained to control soil erosion. Drainage facilities may include ditches, water bars, culverts or any other measure deemed necessary by trained Company personnel to insure proper drainage. Gates and/or cattleguards will be installed if necessary.
3. Location of Existing Wells - Please refer to Map No. 2.
4. Location of Tank Batteries, Production Facilities, and Production Gathering and Service Lines - Please refer to Maps No. 1 and No. 2. Map No. 2 shows the existing gas gathering lines. Map No. 1 shows the existing roads and new proposed access roads. All known production facilities are shown on these two maps.
5. Location and Type of Water Supply - Water for the proposed project will be obtained from Manzaneras Mesa Water Well.
6. Source of Construction Materials - No additional materials will be required to build either the access road or the proposed location.
7. Methods of Handling Waste Materials - All garbage and trash materials will be put into a burn pit shown on the attached Location Plat No. 1. When clean-up operations are begun on the proposed project, the burn pit with its refuse will be buried to a depth of at least three feet (3'). A latrine, the location of which is also shown on Plat No. 1,

7. cont'd. will be provided for human waste. If large amounts of liquids are left in the reserve pit after completion of the project, the pit will be fenced until the liquids have had adequate time to dry. The location clean-up will not take place until such time as the reserve pit can be properly covered over to prevent run-off from carrying any of these materials into the watershed. No earthen pit will be located on natural drainages; all earthen pits will be so constructed as to prevent leakage from occurring.
8. Ancillary Facilities - No camps or airstrips will be associated with this project.
9. Wellsite Layout - Please refer to the attached Plat No. 1.
10. Plans for Restoration of the Surface - After completion of the proposed project, the location will be cleaned and leveled. The location will be left in such a condition that will enable reseeding operations to be carried out. Seed mixture as designated by the responsible government agency will be used. The reseeding operation will be performed during the time period set forth by the regulatory body. The location production equipment will be painted as designated by the responsible government agency.
11. Other Information - The terrain is sagebrush flats with sagebrush growing. Cattle and deer are occasionally seen on the proposed project site.
12. Operator's Representative - W.D. Dawson, PO Box 990, Farmington, NM
13. Certification - I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by El Paso Natural Gas Company and its contractors and sub-contractors in conformity with this plan and the terms and conditions under which it is approved.



L. A. Aimes
Project Drilling Engineer

September 17, 1979

Operations Plan
Jones A #6A

I. Location: 1690'S, 1080'E, Section 14, T-28-N, R-8-W, San Juan County, NM

Field: Blanco Mesa Verde

Elevation: 6367'

II. Geology:

A. Formation Tops:	Surface	San Jose	Lewis	3086'
	Ojo Alamo	1951'	Mesa Verde	4557'
	Kirtland	2098'	Menefee	4681'
	Fruitland	2621'	Point Lookout	5147'
	Pic.Cliffs	2919'	Total Depth	5597'

B. Logging Program: GR-Ind. and GR-Density at Total Depth.

C. Coring Program: none

D. Natural Gauges: 4550', 4670', 5140' and at Total Depth.
Also gauge any noticeable increase in gas. Record all gauges in daily drilling report and on morning report.

III. Drilling:

A. Mud Program: mud from surface to 3285'. Gas from intermediate casing to Total Depth.

IV. Materials:

A. Casing Program:	<u>Hole Size</u>	<u>Depth</u>	<u>Casing Size</u>	<u>Wt.&Grade</u>
	13 3/4"	200'	9 5/8"	36.0# K-55
	8 3/4"	3285'	7"	20.0# K-55
	6 1/4"	3135-5597'	4 1/2"	10.5# K-55

B. Float Equipment: 9 5/8" surface casing - cement guide shoe.

7" intermediate casing - cement guide shoe and self-fill insert float valve, 5 stabilizers every other joint above shoe. Run float two joints above shoe.

4 1/2" liner - 4 1/2" liner hanger with neoprene packoff.
Geyser shoe and flapper type float collar

C. Tubing: 5597' of 2 3/8", 4.7#, J-55 8rd EUE tubing with a common pump seating nipple one joint above bottom. Tubing will be open ended.

D. Wellhead Equipment: 10" 2000 x 9 5/8" casing head. 10" 2000 x 6" 2000 xmas tree.


Operations Plan - Jones A #6A

V. Cementing:

9 5/8" surface casing - use 190 sks. of Class "B" cement with 1/4# gel-flake per sack and 3% calcium chloride (224 cu.ft. of slurry, 100% excess to circulate to surface). WOC 12 hours. Test casing to 600#/30 minutes.

7" intermediate casing - use 113 sks. of 65/35 Class "B" Poz with 6% gel and 2% calcium chloride (8.3 gallons of water per sack) followed by 100 sks. of Class "B" with 2% calcium chloride (301 cu.ft. of slurry, 50% excess to cover Ojo Alamo). Run temperature survey at 8 hours. WOC 12 hours. Test casing to 1200#/30 minutes.

4 1/2" liner - precede cement with 20 barrels of gel water (2 sks. gel) Cement with 308 sks. of 50/50 Class "B" Poz with 2% gel, 0.6% Halad-9, 6.25# gilsonite plus 1/4# Flocele per sack (428 cu.ft. of slurry, 70% excess to circulate liner). WOC 18 hours.



PRT.		SEP.	DATE	TO	W.O.
ENG. REC.		DATE			
DRAWN		J.L.H.	8-16-78		
CHECKED					
CHECKED					
PROJ. APP.					
DESIGN					

 El Paso Natural Gas Company


TYPICAL LOCATION PLAT FOR
MESAVERDE OR DAKOTA DRILL SITE

SCALE: 1" = 50'

DWG.
NO.

RE

Typical B.O.P. Installation
 Lot Mesa Verde Well




Series 900 Double Gate BOP, rated
 at 3000 psi Working Pressure
 When gas drilling operations begin a Shaffer type 50
 or equivalent rotating head is installed on top of the
 flow nipple and the flow line is converted into a blowie line

EL PASO NATURAL GAS COMPANY

Jones A #6A

SE 14-28-8



MAP #1

LEGEND OF RIGHT-OF-WAYS

EXISTING ROADS


EXISTING PIPELINES

EXISTING ROAD & PIPELINE

PROPOSED ROADS

PROPOSED PIPELINES

PROPOSED ROAD & PIPELINE




EL PASO NATURAL GAS COMPANY

Jones A #6A

SE 14-28-8

R-8-W

T
28
N



MAP #2

Proposed Location ●