

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well gas well other

2. NAME OF OPERATOR
Tenneco Oil Company

3. ADDRESS OF OPERATOR
720 S. Colorado Blvd., Denver, CO 80222

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
790'FNL, 990'FEL, Unit A
AT SURFACE:
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

5. LEASE
SF-078390

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME
Price

9. WELL NO.
3

10. FIELD OR WILDCAT NAME
Basin Dakota

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 15; T28N; R8W

12. COUNTY OR PARISH
San Juan

13. STATE
New Mexico


14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)
5894'GR

REQUEST FOR APPROVAL TO:

- TEST WATER SHUT-OFF
- FRACTURE TREAT
- SHOOT OR ACIDIZE
- REPAIR WELL
- PULL OR ALTER CASING
- MULTIPLE COMPLETE
- CHANGE ZONES
- ABANDON*

SUBSEQUENT REPORT OF:



(NOTE: Report results of multiple completion or zone change on Form 9-330.)

(other) Status Report: Completion

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

2/19-2/24/80

MIRUCU on 2/19/80. Installed BOP's. Tagged cmt @ 6875'. Press. tested csm to 3500 PSI. Spotted 500 gal 7 1/2% DI HCL. Ran GR-CCL. Perf'd Dakota @ 6690-6700, 6778-82, 6817-19, 6860-64, 6870-72, 6878-84, 6896-6920. Acidized w/1500 gal 15% HCL, dropped 156 balls. Frac'd w/40000 gal 30# XL gel, 40000# 20/40 sand, 10000# 10/20 sand. Frac'd 2nd stage w/40000# 20/40 sand, 15000# 10/20 sand. Cleaned out to PBD w/foam. Landed 2 3/8" tubg @ 6693'. Kicked well w/N2. RDMOCU 2/24. Flowing to clean up. Waiting on AOF.



Subsurface Safety Valve: Manu. and Type _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED _____ TITLE Admin. Supervisor DATE 2/26/80

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

ACCEPTED FOR RECORD

AMOCO

MAR 4 1980

*See Instructions on Reverse Side

BY M.L. Kuchera