

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Form Approved.
Budget Bureau No. 42-R1424

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☒ other
well well
2. NAME OF OPERATOR
DEPCO, Inc.
3. ADDRESS OF OPERATOR
1000 Petroleum Building - Denver, CO 80202
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1075' FEL, 1600' FSL (NE/4 SE/4)
AT TOP PROD. INTERVAL: Same
AT TOTAL DEPTH: Same

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:	SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF <input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE <input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES <input type="checkbox"/>	<input type="checkbox"/>
ABANDON* <input type="checkbox"/>	<input type="checkbox"/>
(other) <input type="checkbox"/>	Subsequent Report of Operations

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Spudded 3 PM 4-17-81. Drilled 12 1/4" hole to 149' KB. Ran 3 jts - 133.00' - 8-5/8" 24# - K55 - R3 - ST&C casing landed @ 145' KB. Cemented w/100 sx Class "B" regular containing 3% CaCl₂ & one sx Flocele. Cement circd to surface. PD 7 PM 4-17-81. WOC 12 hrs.

Drilled 7-7/8" hole to 1825' TD. Ran 44 jts - 1803.75' - 4 1/2" - 10.5# - J55 - R3 - ST&C casing landed @ 1815' KB. Cemented w/245 sx 65/35 Pozmix, 12% gel, 12 1/2# gil-sonite/sx followed by 100 sx Class "B" regular. Cement circd to surface. PD 1:25 PM. Rig released 2 PM 4-19-81. WOC.

Subsurface Safety Valve: Manu. and Type _____

Set @ _____

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] Prod. Supt. - So. DATE 4/20/81
Rockies

(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:


TITLE _____

DATE _____

*See Instructions on Reverse Side

5. LEASE
--
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
--
7. UNIT AGREEMENT NAME
--
8. FARM OR LEASE NAME
Federal 31
9. WELL NO.
43
10. FIELD OR WILDCAT NAME
West Kutz P.C.
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 31-T27N-R11W
12. COUNTY OR PARISH
San Juan
13. STATE
NM
14. API NO.
30-045-24965
15. ELEVATIONS (SHOW DF, KDB, AND WD)
6121' GR 6133' KB

(NOTE: Report results of multiple completion or zone change on Form 9-330.)



ACCEPTED FOR RECORD

APR 24 1981

FARMINGTON DISTRICT
BY [Signature]