

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well ☐ gas ☒ well ☐ other ☐
2. NAME OF OPERATOR
EL PASO NATURAL GAS CO.
3. ADDRESS OF OPERATOR
BOX 990, FARMINGTON, NEW MEXICO
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 990'N, 990'E
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO: SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF	☐	☒
FRACTURE TREAT	☐	☒
SHOOT OR ACIDIZE	☐	☐
REPAIR WELL	☐	☐
PULL OR ALTER CASING	☐	☐
MULTIPLE COMPLETE	☐	☐
CHANGE ZONES	☐	☐
ABANDON*	☐	☐
(other) Cement Squeeze-		Sidetrack Drilled

5. LEASE
SF 078945
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
San Juan 29-7 Unit
8. FARM OR LEASE NAME
San Juan 29-7 Unit
9. WELL NO.
84 (OWW)
10. FIELD OR WILDCAT NAME
Blanco M.V.
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 1, T-29-N, R-7-W
NMPM
12. COUNTY OR PARISH
Rio Arriba
13. STATE
New Mexico
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
6827 GL

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*
6/3/78: Could not pull stuck tubing and ran free point. Cut off tubing at 5433'. Pulled tubing.
6/5/78: Set cement retainer at 5285'. Squeezed open hole w/214' cf. cement. Perfed 2 squeeze holes at 2940'. Set retainer at 2835 and hesitation squeezed with 148 cf. cement.
6/6/78: Drilled retainer at 2831'. Tested 7" casing, OK. Drilled retainer at 5285' and cement to 5320'. Tested squeeze hole at 2940' to 800 lbs., did not hold.
6/7/78: Set cement retainer at 2892'. Squeezed w/148 cf. cement.
6/8/78: Drilled retainer at 2892'. Drilled cement to 5445' and started side track

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft. (OVER)


18. I hereby certify that the foregoing is true and correct

SIGNED N. G. Guasco TITLE Drilling Clerk DATE June 16, 1978

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side



RECEIVED
JUN 20 1978
U.S. GEOLOGICAL SURVEY
DENVER, COLO.

