

submitted in lieu of Form 3160-5

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

Sundry Notices and Reports on Wells

1. Type of Well
GAS

2. Name of Operator
MERIDIAN OIL

3. Address & Phone No. of Operator
PO Box 4289, Farmington, NM 87499 (505) 326-9700

4. Location of Well, Footage, Sec., T, R, M
1070' FSL, 1700' FWL Sec. 35, T-29-N, R-10-W, NMPM

5. Lease Number
SF-080724A

6. If Indian, All. or
Tribe Name

7. Unit Agreement Name

8. Well Name & Number
Zachry #2

9. API Well No.

10. Field and Pool
Aztec PC/
Basin Ft Coal

11. County and State
San Juan Co, NM

12. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OTHER DATA

Type of Submission

Type of Action

☒ Notice of Intent

☐ Abandonment

☐ Change of Plans

☐ Subsequent Report

☒ Recompletion

☐ New Construction

☐ Final Abandonment

☐ Plugging Back

☐ Non-Routine Fracturing

☐ Casing Repair

☐ Water Shut off

☐ Altering Casing

☐ Conversion to Injectio

☐ Other -

13. Describe Proposed or Completed Operations

It is intended to add and complete by perforating and fracture stimulation the Fruitland Coal formation to this wellbore. Production from the Pictured Cliffs and Fruitland Coal will be commingled. Application is being made to the NMCOD for commingling.

RECEIVED

JAN 31 1994

OIL CON. DIV
DIST. 3

14. I hereby certify that the foregoing is true and correct.

Signed [Signature] (SD) Title Regulatory Affairs Date 12/30/93

APPROVED

(This space for Federal or State Office use)

APPROVED BY _____ Title _____

JAN 06 1994

CONDITION OF APPROVAL, if any:

DISTRICT MANAGER

Submit to Appropriate
District Office.
State Lease - 4 copies.
Fee Lease - 3 copies.

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-385
Revised 1-1-89

OIL CONSERVATION DIVISION

P.O. Box 2088

Santa Fe, New Mexico 87504-2088

DISTRICT I
P.O. Box 1980, Hobbs, NM 88240

DISTRICT II
P.O. Drawer 00, Azusa, NM 88210

DISTRICT III
1000 Rio Rancho Rd., Azusa, NM 87430

WELL LOCATION AND ACREAGE DEDICATION PLAT

All Distances must be from the outer boundaries of the section.

Operator Meridian Oil Inc.			Lease Zachry			Well No. 2		
Unit Letter N	Section 35	Township 29 North	Range 10 West	County San Juan				
Actual Foreign Leases of Well: 1070 feet from the South line and 1700 feet from the West line.								
Ground level Elev. 5753'			Fruitland Coal/Pic.Cliffs			Basin/Aztec		
						Dedicated Acreage 320/160 Acres		

1. Outline the acreage dedicated to the subject well by colored pencil or ink on the plat below:

2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty):

3. If more than one lease of different ownership is dedicated to the well, have the interest of all owners been considered by communication, consensus, force-pooling, etc.?

☐ Yes ☐ No If answer is "yes" type of consideration:

If answer is "no" list the owners and what consideration which have actually been considered. (Use reverse side of this form if necessary.)

No allowable well be assigned to the well until all interests have been considered (by communication, consensus, force-pooling, or otherwise) or until a non-consent suit, eliminating such interest, has been approved by the Division.

*Not resurveyed prepared
from a plat dated 12-22-54
by Ernest V. Echhawk.

OPERATOR CERTIFICATION

I hereby certify that the information
contained herein is true and complete to the
best of my knowledge and belief.

Peggy Bradfield
Signature

Peggy Bradfield

Printed Name:

Regulatory Representative

Position:

Meridian Oil Inc.

Company:

12-30-93

Date:

SURVEYOR CERTIFICATION

I hereby certify that the well location shown
on this plat was plotted from field notes of
actual surveys made by me or under my
supervision and that the same are true and
correct to the best of my knowledge and
belief. 1-3-94

Date Surveyed: C. Edm.

Needle Creek

Signature of Surveyor
Professional Surveyor

9857

RECEIVED

JAN 31 1994

OIL CON. DIV
DIST

Pertinent Data Sheet - Zachry #2

Location: 1070' FSL, 1700' FWL, Section 35, T29N, R10W, San Juan County, New Mexico

Field: Aztec Pictured Cliffs

Elevation: 5753' DF

TD: 2060'

PBTD: 2060'

Completed: 03-08-55

Spud Date: 02-22-55

DP #: 32190B

Casing Record:

<u>Hole Size</u>	<u>Csg Size</u>	<u>Wt. & Grade</u>	<u>Depth Set</u>	<u>Cement</u>	<u>Top/Cement</u>
12 1/4"	9 5/8"	36.0# H-40	92'	100 sxs	Surface/Circ
8 3/4"	5 1/2"	15.5# J-55	1978'	150 sxs	

Tubing Record:

<u>Tbg Size</u>	<u>Wt. & Grade</u>	<u>Depth Set</u>
1"	1.7#	1808'

Formation Tops:

Kirtland: 1012'
Fruitland: 1650'
Pictured Cliffs: 1978'

Logging Record: Micro, IES

Stimulation:

Open Hole Sand Frac 1978' - 2060' w/13,500 gal oil & 163 sxs sand.

Workover History:


Production History:

Transporter:

RECEIVED
JAN 19 1994
OIL CON. DIV.
DIST 3



RECEIVED
JAN 31 1994
OIL CON. DIV.
DIST 3

ZACHRY #2
CURRENT
AZTEC PICTURED CLIFFS
UNIT N, SEC 35, T29N, R10W, SAN JUAN COUNTY, NM



RECEIVED
JAN 2 1994
OIL CON. DIV.
DIST. 3

RECEIVED
JAN 31 1994
OIL CON. DIV.
DIST. 3



RECEIVED
JAN 31 1994
OIL CON.
DIST. 3

ZACHRY #2
Recommend Completion Procedure
SW/4 Section 35 T29N R10W

1. Test rig anchors and repair if necessary. Install 2-400 bbl frac tanks on location and fill with 2% KCl water. Filter all water to 25 microns.
2. MOL and RU. Comply to all NMOCD, BLM and MOI rules & regulations. Hold safety meeting. ND wellhead. NU BOP. Test operation of rams. NU two relief lines.
3. TOOH w/ 1808' of 1" tbg, tally and inspect.
4. TIH w/ 4-3/4" bit and 5-1/2" casing scraper on 2-3/8" tbg and clean out to 5-1/2" casing shoe @ 1978'. TOOH.
5. TIH w/ 4-3/4" bit on 2-3/8" work-string and clean out to open hole TD @ 2060'. Load hole w/ 20 bbls 2% KCl water. TOOH.
6. RU & RIH w/ CNL-CCL-GR and log from casing shoe @ 1978' to 1600'
7. RIH and wireline set 5-1/2" CIBP @ 1972'. Load hole w/ water. TOOH.
8. TIH w/ fullbore packer and 2-3/8" tubing, load hole w/ 2% KCl water, set packer @1930', test CIBP to 3000 psi for 15 minutes. Test tubing/casing annulus to 500 psi for 15 minutes. Equalize pressure and unseat packer. TOOH.
9. RU wireline and run CBL from PBTD (1972') to 150'. If CBL appears inadequate, re-run log with 750 psi surface pressure. If bond still appears unacceptable, contact production engineering. Send copy of CBL to production engineering.
10. Insure both 400 bbl tanks on location are filled with 2% KCl water in preparation for Fruitland coal fracs. Filter all water to 25 microns.

RECEIVED
JAN 31 1994
OIL CON DIV
DIST. 3

RECEIVED
JAN 21 1994
OIL CON DIV
DIST. 3

ZACHRY #2
Recommend Completion Procedure
SW/4 Section 35 T29N R10W
Page 2

*****LOWER COAL*****

11. RU wireline and perf the following coal interval w/ 4" HSC w/ 19.8 gram charges @ 4 SPF (correlate depths to CNL-CCL-GR log).

1954-1969'

Total: 15 feet: 60 holes

12. TIH w/ 3-1/2" 9.3# N-80 FJ frac string and set fullbore pkr @ 1920'. Load backside w/ 2% KCl water.
13. RU treatment company for frac. Hold safety meeting with all personnel. Pressure test surface lines to 5000 psi. Fracture treat lower coal according to attached schedule w/ 70Q foam at 20 BPM with 65,000 lbs of 20/40 mesh Arizona sand. Flush with 15 bbls gel. Estimated treating pressure is 1700 psi. **MAXIMUM PRESSURE IS LIMITED TO 4000 PSI** Monitor backside and braden head pressures during frac. Monitor bottomhole and surface treating pressure, rate, foam quality and sand concentration with computer van. Frac during daylight only.
14. SI well for 3 hours for gel break.
15. After gel break, open well through choke manifold & monitor flow. Flow @ 20 bbls/hr, or less if sand is observed.
16. Re-fill 400 bbl frac tanks with 2% KCl water and filter to 25 microns.
17. When well ceases to flow, TOOH w/ pkr and frac string. TIH w/ 2-3/8" tbg and csg scraper to 1970'. TOOH. TIH and set 5-1/2" RBP @ 1940'.

RECEIVED
JAN 12 1994
OIL CON. DIV.]
DIST. 3

RECEIVED
JAN 31 1994
OIL CON. D.
DIST 3

RECEIVED

JAN 2 1994

OIL CON. DIV.
DIST. 3

ZACHRY #2
Recommend Completion Procedure
SW/4 Section 35 T29N R10W
Page 3

*****UPPER COAL*****

18. RU wireline and perf the following coal interval w/ 4" HSC w/ 19.8 gram charges @ 4 SPF (correlate depths to CNL-CCL-GR log).

1852-1865', 1886-1893', 1908-1911

Total: 23 feet: 92 holes

19. TIH w/ frac string and set pkr @ 1920'. Pressure test BP to 3000 psi surface pressure.
20. Release pkr, PU to 1750', load backside and set pkr @ approx 1750'.
21. RU treatment company for frac. Hold safety meeting with all personnel. Pressure test surface lines to 5000 psi. Fracture treat upper coal according to attached schedule w/ 70Q foam at 30 BPM with 75,000 lbs of 20/40 mesh Arizona sand. Tag all sand w/ 0.4 mCI/1000# Ir-192 tracer. Flush with 15 bbls gel. Estimated treating pressure is 2300 psi. MAXIMUM PRESSURE IS LIMITED TO 4000 PSI! Monitor backside and braden head pressures during frac. Monitor bottomhole and surface treating pressure, rate, foam quality and sand concentration with computer van. Frac during daylight only.
22. SI well for 3 hours for gel break.
23. After gel break, open well through choke manifold & monitor flow. Flow @ 20 bbls/hr, or less if sand is observed.
24. When well ceases to flow, TOOH w/ pkr and frac string. TIH w/ retrieving head on 2-3/8" tbg and clean out upper zone until sand flow stops. Take Pitot gauge before releasing BP. Release RBP set @ 1940' and TOOH.
25. TIH w/ 2 3/8" tbg open ended and clean out lower coal until sand stops. After clean up, flow test the Coal for 24 hrs, taking pitot gauges every 6 hrs. Take final Pitot gauge and gas & water samples. TOOH
26. TIH w/ 2-3/8" tbg and 4 3/4" bit, clean out to PBTD. Blow well clean. Drill out CIPB set @ 1972', clean out to open hole TD. TOOH laying down 2-3/8" tbg.
27. RU wireline and run After - Frac - GR log from 2002' to 1800'.
28. TIH w/ 2020' of 1-1/2" tbg w/ standard seating nipple one jt off bottom and pump-off plug on bottom. Land tbg string.
29. ND BOP and NU independent wellhead. Pump off plug. Take final Pitot gauge. Rig down & release rig.

Approve:


J. A. Howieson

VENDORS:

Wireline:
Fracturing:
RA Tagging:

Blue Jet
Western
Protechnics

325-5584
327-6222
326-7133

RECEIVED

JAN 31 1994

OIL CON. DIV.
DIST. 3